

STATE OF VERMONT  
AGENCY OF TRANSPORTATION

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES

TOTALS

DESCRIPTIONS

DETAILED SUMMARY OF QUANTITIES

SUMMARY OF ESTIMATED QUANTITIES													TOTALS				DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES						
													FULL E&C	EROSION CONTROL	AIRPORT	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
															1			1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
															600			600	CY	COMMON EXCAVATION	203.15				
															6500			6500	CY	SOLID ROCK EXCAVATION	203.16				
															500	EST.	500		CY	MUCK EXCAVATION	203.20				
															3500			3500	CY	EARTH BORROW	203.30				
															75			75	CY	TRENCH EXCAVATION OF EARTH	204.20				
															1200			1200	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
															250			250	LF	6 INCH UNDERDRAIN PIPE	605.10				
															100			100	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20				
															2			2	EACH	UNDERDRAIN FLUSHING BASIN	605.95				
															10			10	HR	BULLDOZER RENTAL, TYPE I	608.10				
															10			10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
															10			10	HR	TRUCK RENTAL	608.37				
															10			10	HR	LOADER RENTAL, TYPE I	608.40				
															100			100	MGAL	DUST CONTROL WITH WATER	609.10				
															800			800	CY	STONE FILL, TYPE II	613.11				
															1600			1600	LF	CHAIN - LINK FENCE, 6 FEET	620.12				
															24			24	LF	GATE FOR CHAIN - LINK FENCE, 6 FEET	620.16				
															14			14	EACH	BRACING ASSEMBLY FOR CHAIN - LINK FENCE, 6 FEET	620.21				
															950			950	LF	REMOVAL OF EXISTING FENCE	620.55				
															180			180	LF	PLANK RAIL	621.15				
															110			110	TON	CRUSHED STONE BEDDING	629.54				
															1			1	LS	FIELD OFFICE, ENGINEERS	631.10				
															1			1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
															1			1	LS	MOBILIZATION / DEMOBILIZATION	635.11				
															1			1	LS	TRAFFIC CONTROL	641.10				
															300			300	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
															1000			1000	SY	GEOTEXTILE UNDER STONE FILL	649.31				
															110			110	SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41				
															1200			1200	SY	GEOTEXTILE FOR SILT FENCE	649.51				
															920			920	LB	SEED	651.15				
															2300			2300	LB	FERTILIZER	651.18				
															9			9	TON	AGRICULTURAL LIMESTONE	651.20				
															9			9	TON	HAY MULCH	651.25				
															1750			1750	CY	TOPSOIL	651.35				
															1			1	LS	EPSC	652.10				
															60			60	HR	MONITORING EPSC	652.20				
															1			1	LU	MAINTENANCE OF EPSC (N.A.B.I.)	652.30				
															6000			6000	SY	TEMPORARY EROSION MATTING	653.20				
															60			60	CY	VEHICLE TRACKING PAD	653.35				
															3500			3500	LF	BARRIER FENCE	653.50				

PRINTING PARAMETERS: AUSTIN J. WARDEN  
 PRINTED BY: AUSTIN J. WARDEN  
 PRINT DATE: 2/21/2008  
 PRINT TIME: 10:58 AM  
 FOR CONTACT: 303.248.3000

PROJECT NUMBER: 04-3183  
 SHEET NUMBER: 4  
 OF 27

REV	DATE	BY
△	02/21/08	CKF



PROJECT NAME: HIGHGATE  
 PROJECT NUMBER: AIR 04-3183  
 FILE NAME: QUANTITY SHEET.DGN  
 PROJECT LEADER: M. CHURCHILL  
 DESIGNED BY: P. ENZIEN  
**QUANTITY SHEET 1**  
 PLOT DATE: 2/21/2008  
 DRAWN BY: J. OAKMAN  
 CHECKED BY: P. ENZIEN  
 SHEET 4 OF 27