STATE OF VERMONT
AGENCY OF TRANSPORTATION

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

| TOTALS | | | DESCRIPTIONS | | | |
|---|---|---|---|---|---|---|
| FINAL | ROUND | GRAND TOTAL | UNIT | ITEMS | ITEM NUMBER |
| 3215 | 35 | 3250 | CY | COMMON EXCAVATION | 203.15 |
| 6298 | 2 | 6300 | CY | EARTH BORROW | 203.30 |
| 290 | 10 | 300 | SY | COLD PLANING-BIT.PAVEMENT | 210.10 |
| 2754 | 46 | 2800 | CY | SUBBASE OF GRAVEL (P-154) | 301.15 |
| 300 | | 300 | CY | SUBBASE OF CRUSHED GRAVEL (COARSE GRADED) | 301.25 |
| 2 | | 2 | CWT | EMULSIFIED ASPHALT | 404.65 |
| 1 | | 1 | LU | PRICE ADJUSTMENT ASPHALT CEMENT (NABI) | 406.50 |
| 570 | | 570 | LF | JOINT SEALER HOT POURED | 524.11 |
| 460 | | 460 | LF | 12" RCP CLASS III | 601.0805 |
| 6 | | 6 | EACH | 15" RCPES CLASS III (MOD) (12") | 601.6810 |
| 5 | | 5 | EACH | CONCRETE MANHOLE WITH CAST IRON COVER (MOD) (ELEC. HANDHOLES) | 604.11 |
| 4 | | 4 | EACH | PRECAST REINFORCED CONC. MANHOLE W/ CAST IRON COVER (MOD) (ELEC. MH) | 604.21 |
| 50 | | 50 | HR | BULLDOZER RENTAL, TYPE I | 608.10 |
| 50 | | 50 | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I | 608.25 |
| 50 | | 50 | HR | TRUCK RENTAL | 608.37 |
| 50 | | 50 | HR | LOADER RENTAL, TYPE I | 608.40 |
| 500 | | 500 | MGAL | DUST CONTROL WITH WATER | 609.10 |
| 1 | | 1 | TON | DUST & ICE CONTROL WITH CALCIUM CHLORIDE | 609.15 |
| 26 | 4 | 30 | CY | STONE FILL, TYPE I | 613.10 |
| 2 | 8 | 10 | CY | STONE FILL, TYPE I (MOD) | 613.10 |
| 100 | | 100 | LF | PVC SEWER PIPE (4") | 628.35 |
| 1 | | 1 | LS | FIELD OFFICE-ENGINEERS | 631.10 |
| 1 | | 1 | LS | TESTING EQUIPMENT - BITUMINOUS | 631.17 |
| 1 | | 1 | LU | FIELD OFFICE TELEPHONE (NABI) | 631.25 |
| 1 | | 1 | LS | MOBILIZATION | 635.10 |
| 1 | | 1 | LS | TRAFFIC CONTROL (MOD) | 641.10 |
| 10000 | | 10000 | SY | GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR | 649.11 |
| 233 | 17 | 250 | SY | GEOTEXTILE FOR SILT FENCE | 649.51 |
| 30 | | 30 | LB | SEED | 651.15 |
| 300 | | 300 | LB | FERTILIZER | 651.18 |
| 2 | 3 | 5 | TON | AGRICULTURAL LIMESTONE | 651.20 |
| 2 | 3 | 5 | TON | HAY MULCH | 651.25 |
| 2900 | | 2900 | CY | TOPSOIL | 651.35 |
| 1 | | 1 | LS | EROSION & SEDIMENT CONTROL PLAN | 652.10 |
| 200 | | 200 | HR | MONITORING EROSION & SEDIMENT CONTROL PLAN | 652.20 |
| 1 | | 1 | LU | FIELD MAINTENANCE OF EROSION & SEDIMENT CONTROL PLAN (NABI) | 652.30 |
| 2200 | | 2200 | LF | ELECTRICAL CONDUIT (MOD) (L-110) | 678.21 |
| 3500 | | 3500 | CY | P-209 CRUSHED AGGREGATE BASE COURSE | 854.04 |
| 51 | | 51 | EACH | AIRCRAFT TIE DOWN ANCHOR, TYPE A | 854.07 |
| 12 | | 12 | EACH | AIRCRAFT TIE DOWN ANCHOR, TYPE A (MOD)(REMOVE) | 854.07 |

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

Dufresne-Henry

PROJECT NAME: **Franklin County State Airport**
PROJECT NUMBER: **AIR 04-3170**

FILE NAME: **quantity sheet.xls**
PROJECT LEADER: **MLC**
DESIGNED BY: **MLC**
**QUANTITY SHEET**

PLOT DATE: **4/6/2004**
DRAWN BY: **JDO**
CHECKED BY: **DD**
SHEET **3** OF **17**