QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	AVIATION	FULL CE ITEMS	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	12,250		12,250	CY	COMMON EXCAVATION	203.15	
	2,000		2,000	CY	SOLID ROCK EXCAVATION	203.16	
	3,200		3,200	CY	GRANULAR BORROW (MOD.- P-154)	203.32	
	3,600		3,600	SY	FINE GRADING SUBGRADE	203.40	
	320		320	CY	TRENCH EXCAVATION OF EARTH	204.20	
	40		40	CY	TRENCH EXCAVATION OF ROCK	204.21	
	500		500	SY	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	205.20	
	650		650	SY	COLD PLANING- BITUMINOUS PAVEMENT	210.10	
	700		700	CY	SUBBASE OF GRAVEL (MOD. - P-208)	301.15	
	250		250	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	
	600		600	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	
	100		100	LF	JOINT SEALER, HOT POURED	524.11	
	100		100	LF	15" CPEP	601.0910	
	1		1	EA	15" CPEPES	601.7010	
	1		1	EA	PRECAST REINFORCED CONCRETE CATCH BASIN W/ CAST IRON GRATE	604.20	
	450		450	LF	6" UNDERDRAIN	605.10	
	3		3	EA	UNDERDRAIN FLUSHING BASIN	605.95	
	60		60	HOUR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
	70		70	HOUR	POWER BROOM RENTAL	608.30	
	10		10	MGAL	DUST CONTROL WITH WATER	609.10	
	20		20	CY	STONE FILL, TYPE I	613.10	
70			70	CY	STONE FILL, TYPE I (MOD.-CONSTRUCTION ENTRANCE)	613.10	
10,000			10,000	LF	SNOW FENCE (MOD. - PDF)	620.70	
	600		600	HOUR	FLAGGERS	630.15	
		1	1	LS	FIELD OFFICE - ENGINEERS	631.10	
		1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
		1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
		1	1	LU	FIELD OFFICE - TELEPHONE (NABI)	631.25	
	1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
	150		150	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	
	3600		3600	SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	
	450		450	SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	
500			500	SY	GEOTEXTILE FOR SILT FENCE	649.51	
215			215	LB	SEED	651.15	
1500			1500	LB	FERTILIZER	651.18	
6			6	TON	AGRICULTURAL LIMESTONE	651.20	
6			6	TON	HAY MULCH	651.25	
1000			1000	CY	TOPSOIL	651.35	
1			1	LS	EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.10	
24			24	HR	MONITORING EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.20	
1			1	LU	MAINTENANCE OF EROSION PREVENTION AND SEDIMENT CONTROL PLAN (NABI)	652.30	
5500			5500	SY	EROSION MATTING	654.10	
	200		200	LF	ELECTRICAL CONDUIT (2") (PVC)	678.21	
	9		9	EA	AIRCRAFT TIE DOWN ANCHOR, TYPE A	854.07	
	650		650	SF	P-620, RUNWAY AND TAXIWAY PAINTING	864.03	
	200		200	LF	L-108, CABLE TRENCH	864.04	
	600		600	LF	L-108, I/C #8 L-824 TYPE C, 5KV	864.05	
	500		500	LF	L-108, #8 COUNTERPOISE WIRE (MOD.-#6)	864.06	
	4		4	EA	L-125, TAXIWAY GUIDANCE SIGN	864.14	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: **CLARENDON**
PROJECT NUMBER: **AIR 04-3172-C2**

FILE NAME: 38397036sheet2.dgn
PROJECT MANAGER: S. FORTNEY
DESIGNED BY: R. DEWEY
QUANTITY SHEET

PLOT DATE: 2/16/2006
DRAWN BY: R. DEWEY
CHECKED BY: G. D'AMICO
SHEET 2 OF 27