

BORING LOG										Boring No.: B-34																																																																																																															
Project Name										Page No.: 1 of 1																																																																																																															
Knapp Airport										File No.: 965-03																																																																																																															
Berlin, Vermont										Checked By: KEW/AMH																																																																																																															
GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140																																																																																																																									
Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Don Howey Date Started: July 17, 2006 Date Finished: July 17, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft										Casting: H.S.A. SS Sampler: SS Date: 7/17/06 9:00 Depth (ft): 8.0 Elev. (ft): Notes: Wet sample																																																																																																															
<table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Coring Interval (ft)</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">PFB Reading (ft)</th> <th rowspan="2">Strata Description</th> <th rowspan="2">Symbol</th> <th rowspan="2">Sample Description</th> </tr> <tr> <th>0-6</th> <th>6-12</th> <th>12-18</th> <th>18-24</th> <th>24-30</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>24</td> <td>SS</td> <td>15</td> <td>0</td> <td>3</td> <td>7</td> <td>15</td> <td>11</td> <td></td> <td></td> <td></td> <td>Topsoil Sandy Silt</td> <td></td> <td>Medium dense, brown SILT, some fine to coarse Sand, trace (+) fine to coarse Gravel, (moist)</td> </tr> <tr> <td>2</td> <td>24</td> <td>SS</td> <td>16</td> <td>2</td> <td>6</td> <td>5</td> <td>11</td> <td>15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, gray SILT, some fine Sand, trace (-) fine Gravel, (moist)</td> </tr> <tr> <td>3</td> <td>24</td> <td>SS</td> <td>18</td> <td>4</td> <td>9</td> <td>10</td> <td>12</td> <td>14</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, grayish brown SILT, trace (+) fine SAND, (moist)</td> </tr> <tr> <td>4</td> <td>24</td> <td>SS</td> <td>22</td> <td>6</td> <td>9</td> <td>10</td> <td>12</td> <td>16</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, brown SILT, some fine to coarse SAND, (moist)</td> </tr> <tr> <td>5</td> <td>24</td> <td>SS</td> <td>24</td> <td>8</td> <td>10</td> <td>16</td> <td>12</td> <td>16</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, gray SILT, little fine to coarse Sand, trace fine Gravel, (with occasional 1/2" thick fine Sand seams), (wet)</td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>10</td> <td>Bottom of Exploration at 10.0 ft</td> <td></td> </tr> </tbody> </table>										Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description	0-6	6-12	12-18	18-24	24-30	1	24	SS	15	0	3	7	15	11				Topsoil Sandy Silt		Medium dense, brown SILT, some fine to coarse Sand, trace (+) fine to coarse Gravel, (moist)	2	24	SS	16	2	6	5	11	15						Medium dense, gray SILT, some fine Sand, trace (-) fine Gravel, (moist)	3	24	SS	18	4	9	10	12	14						Medium dense, grayish brown SILT, trace (+) fine SAND, (moist)	4	24	SS	22	6	9	10	12	16						Medium dense, brown SILT, some fine to coarse SAND, (moist)	5	24	SS	24	8	10	16	12	16						Medium dense, gray SILT, little fine to coarse Sand, trace fine Gravel, (with occasional 1/2" thick fine Sand seams), (wet)	10												10	Bottom of Exploration at 10.0 ft			
Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval										Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description																																																																																																						
					0-6	6-12	12-18	18-24	24-30																																																																																																																
1	24	SS	15	0	3	7	15	11				Topsoil Sandy Silt		Medium dense, brown SILT, some fine to coarse Sand, trace (+) fine to coarse Gravel, (moist)																																																																																																											
2	24	SS	16	2	6	5	11	15						Medium dense, gray SILT, some fine Sand, trace (-) fine Gravel, (moist)																																																																																																											
3	24	SS	18	4	9	10	12	14						Medium dense, grayish brown SILT, trace (+) fine SAND, (moist)																																																																																																											
4	24	SS	22	6	9	10	12	16						Medium dense, brown SILT, some fine to coarse SAND, (moist)																																																																																																											
5	24	SS	24	8	10	16	12	16						Medium dense, gray SILT, little fine to coarse Sand, trace fine Gravel, (with occasional 1/2" thick fine Sand seams), (wet)																																																																																																											
10												10	Bottom of Exploration at 10.0 ft																																																																																																												
Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.										Boring No.: B-34																																																																																																															

BORING LOG										Boring No.: B-35																																																																																																																
Project Name										Page No.: 1 of 1																																																																																																																
Knapp Airport										File No.: 965-03																																																																																																																
Berlin, Vermont										Checked By: KEW/AMH																																																																																																																
GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140																																																																																																																										
Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Jake Wimet Date Started: July 21, 2006 Date Finished: July 21, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft										Casting: H.S.A. SS Sampler: SS Date: 7/21/06 9:00 Depth (ft): Elev. (ft): Notes: None observed																																																																																																																
<table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Coring Interval (ft)</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">PFB Reading (ft)</th> <th rowspan="2">Strata Description</th> <th rowspan="2">Symbol</th> <th rowspan="2">Sample Description</th> </tr> <tr> <th>0-6</th> <th>6-12</th> <th>12-18</th> <th>18-24</th> <th>24-30</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>24</td> <td>SS</td> <td>12</td> <td>0</td> <td>2</td> <td>7</td> <td>12</td> <td>14</td> <td></td> <td></td> <td></td> <td>0.5</td> <td>Topsoil Sandy Silt</td> <td></td> <td>Medium dense, Top 6": TOPSOIL Bottom 6": fractured ROCK, some fine Sand, little (-) SILT, (moist)</td> </tr> <tr> <td>2</td> <td>24</td> <td>SS</td> <td>20</td> <td>2</td> <td>6</td> <td>7</td> <td>8</td> <td>12</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, brownish tan fine SAND and SILT, trace coarse Sand, trace Root fibers, (moist)</td> </tr> <tr> <td>3</td> <td>24</td> <td>SS</td> <td>18</td> <td>4</td> <td>6</td> <td>7</td> <td>12</td> <td>16</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, brown SILT and fine SAND, little (-) medium Sand, (moist)</td> </tr> <tr> <td>4</td> <td>24</td> <td>SS</td> <td>19</td> <td>6</td> <td>16</td> <td>15</td> <td>18</td> <td>27</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Dense, brownish gray fine SAND and SILT, little medium to coarse Sand, little fine to coarse Gravel, (with pieces of fractured Rock), (moist)</td> </tr> <tr> <td>5</td> <td>24</td> <td>SS</td> <td>19</td> <td>8</td> <td>12</td> <td>12</td> <td>15</td> <td>17</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, fine SAND and SILT (slightly plastic), little coarse Sand, little fine Gravel, (moist to wet)</td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>10</td> <td>Bottom of Exploration at 10.0 ft</td> <td></td> </tr> </tbody> </table>										Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description	0-6	6-12	12-18	18-24	24-30	1	24	SS	12	0	2	7	12	14				0.5	Topsoil Sandy Silt		Medium dense, Top 6": TOPSOIL Bottom 6": fractured ROCK, some fine Sand, little (-) SILT, (moist)	2	24	SS	20	2	6	7	8	12						Medium dense, brownish tan fine SAND and SILT, trace coarse Sand, trace Root fibers, (moist)	3	24	SS	18	4	6	7	12	16						Medium dense, brown SILT and fine SAND, little (-) medium Sand, (moist)	4	24	SS	19	6	16	15	18	27						Dense, brownish gray fine SAND and SILT, little medium to coarse Sand, little fine to coarse Gravel, (with pieces of fractured Rock), (moist)	5	24	SS	19	8	12	12	15	17						Medium dense, fine SAND and SILT (slightly plastic), little coarse Sand, little fine Gravel, (moist to wet)	10												10	Bottom of Exploration at 10.0 ft			
Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval										Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description																																																																																																							
					0-6	6-12	12-18	18-24	24-30																																																																																																																	
1	24	SS	12	0	2	7	12	14				0.5	Topsoil Sandy Silt		Medium dense, Top 6": TOPSOIL Bottom 6": fractured ROCK, some fine Sand, little (-) SILT, (moist)																																																																																																											
2	24	SS	20	2	6	7	8	12						Medium dense, brownish tan fine SAND and SILT, trace coarse Sand, trace Root fibers, (moist)																																																																																																												
3	24	SS	18	4	6	7	12	16						Medium dense, brown SILT and fine SAND, little (-) medium Sand, (moist)																																																																																																												
4	24	SS	19	6	16	15	18	27						Dense, brownish gray fine SAND and SILT, little medium to coarse Sand, little fine to coarse Gravel, (with pieces of fractured Rock), (moist)																																																																																																												
5	24	SS	19	8	12	12	15	17						Medium dense, fine SAND and SILT (slightly plastic), little coarse Sand, little fine Gravel, (moist to wet)																																																																																																												
10												10	Bottom of Exploration at 10.0 ft																																																																																																													
Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.										Boring No.: B-35																																																																																																																

BORING LOG										Boring No.: B-36																																																																																																																
Project Name										Page No.: 1 of 1																																																																																																																
Knapp Airport										File No.: 965-03																																																																																																																
Berlin, Vermont										Checked By: KEW/AMH																																																																																																																
GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140																																																																																																																										
Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Don Howey Date Started: July 18, 2006 Date Finished: July 18, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft										Casting: H.S.A. SS Sampler: SS Date: 7/18/06 9:00 Depth (ft): Elev. (ft): Notes: None observed																																																																																																																
<table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Coring Interval (ft)</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">PFB Reading (ft)</th> <th rowspan="2">Strata Description</th> <th rowspan="2">Symbol</th> <th rowspan="2">Sample Description</th> </tr> <tr> <th>0-6</th> <th>6-12</th> <th>12-18</th> <th>18-24</th> <th>24-30</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>24</td> <td>SS</td> <td>12</td> <td>0</td> <td>1</td> <td>3</td> <td>5</td> <td>5</td> <td></td> <td></td> <td></td> <td>0.5</td> <td>Topsoil Sandy Silt</td> <td></td> <td>Top 6": TOPSOIL Bottom 6": Loose, brown SILT, little fine to coarse Sand, little fine to coarse Gravel, trace Root fibers, (moist)</td> </tr> <tr> <td>2</td> <td>24</td> <td>SS</td> <td>17</td> <td>2</td> <td>6</td> <td>6</td> <td>13</td> <td>26</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Medium dense, brown SILT, little fine to coarse Sand, trace fine to coarse Gravel, (moist)</td> </tr> <tr> <td>3</td> <td>24</td> <td>SS</td> <td>4</td> <td>4</td> <td>30</td> <td>28</td> <td>23</td> <td>15</td> <td></td> <td></td> <td></td> <td>4</td> <td>Glacial Till</td> <td>Dense, greenish brown SILT, little fine Sand, (moist)</td> </tr> <tr> <td>4</td> <td>24</td> <td>SS</td> <td>8</td> <td>6</td> <td>11</td> <td>10</td> <td>22</td> <td>43</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Dense, brown Clayey SILT, little (+) fine to coarse Sand, trace (+) fine Gravel, (moist to wet)</td> </tr> <tr> <td>5</td> <td>24</td> <td>SS</td> <td>24</td> <td>8</td> <td>31</td> <td>34</td> <td>45</td> <td>60</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Very dense, brown SILT and fine to coarse SAND, little fine to coarse Gravel, (moist)</td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>10</td> <td>Bottom of Exploration at 10.0 ft</td> <td></td> </tr> </tbody> </table>										Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description	0-6	6-12	12-18	18-24	24-30	1	24	SS	12	0	1	3	5	5				0.5	Topsoil Sandy Silt		Top 6": TOPSOIL Bottom 6": Loose, brown SILT, little fine to coarse Sand, little fine to coarse Gravel, trace Root fibers, (moist)	2	24	SS	17	2	6	6	13	26						Medium dense, brown SILT, little fine to coarse Sand, trace fine to coarse Gravel, (moist)	3	24	SS	4	4	30	28	23	15				4	Glacial Till	Dense, greenish brown SILT, little fine Sand, (moist)	4	24	SS	8	6	11	10	22	43						Dense, brown Clayey SILT, little (+) fine to coarse Sand, trace (+) fine Gravel, (moist to wet)	5	24	SS	24	8	31	34	45	60						Very dense, brown SILT and fine to coarse SAND, little fine to coarse Gravel, (moist)	10												10	Bottom of Exploration at 10.0 ft			
Depth (ft)	Coring Interval (ft)	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval										Coring Time (min./ft)	PFB Reading (ft)	Strata Description	Symbol	Sample Description																																																																																																							
					0-6	6-12	12-18	18-24	24-30																																																																																																																	
1	24	SS	12	0	1	3	5	5				0.5	Topsoil Sandy Silt		Top 6": TOPSOIL Bottom 6": Loose, brown SILT, little fine to coarse Sand, little fine to coarse Gravel, trace Root fibers, (moist)																																																																																																											
2	24	SS	17	2	6	6	13	26						Medium dense, brown SILT, little fine to coarse Sand, trace fine to coarse Gravel, (moist)																																																																																																												
3	24	SS	4	4	30	28	23	15				4	Glacial Till	Dense, greenish brown SILT, little fine Sand, (moist)																																																																																																												
4	24	SS	8	6	11	10	22	43						Dense, brown Clayey SILT, little (+) fine to coarse Sand, trace (+) fine Gravel, (moist to wet)																																																																																																												
5	24	SS	24	8	31	34	45	60						Very dense, brown SILT and fine to coarse SAND, little fine to coarse Gravel, (moist)																																																																																																												
10												10	Bottom of Exploration at 10.0 ft																																																																																																													
Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.										Boring No.: B-36																																																																																																																

- Notes:
- 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable; O.R. = Out of Range
 - 2) Water level readings have been made at times and under conditions stated, fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded.
 - 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer
 - 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50%
 - 5) Stratification lines represent approximate boundary between material types, transitions may be gradual.
 - 6) Bedrock cores collected at locations c-1, c-2, and c-3 typically consist of gray, soft, moderately weathered phyllite bedrock of very poor to fair quality, the rock was fissile and crumbled with moderate finger pressure. Fractures were typically noted along the effusive planes between approximately 60 and 70 degrees (measures from the horizontal). Rock quality designation (RQD) values ranged between 0 and 55%. The rock type was consistent with mapping data published on the Continental Geologic Map of Vermont (doll, 1961) and a rock outcrop located approximately 500 feet north of the site (along Airport Road).
 - 7) Bedrock removal for this project can be accomplished using conventional mechanical equipment. Mechanical removal methods can include excavating, ripping, hoe-ramping and splitting. A alternative method of removal is blasting.
 - 8) The effort and difficulty of rock removal will generally increase with the depth once the upper, more weathered rock has been penetrated (estimated up to between 5 and 10 feet deep).
 - 9) Rock Reuse Potential - the type and condition of rock anticipated for removal will be poor aggregate for use in the base course below new pavements.

Hoyle, Tanner & Associates, Inc.

150 Dow Street
 Manchester, NH 03101-1227
 Tel 603-669-5555
 Fax 603-669-4168
 Web Page: www.hoyletanner.com
 Hoyle Tanner & Associates © 2008

PROJECT NAME: E. F. KNAPP STATE AIRPORT
 A.I.P. 3-50-0001-011-2009
 PROJECT NUMBER: BERLIN AIR 04-3216
 FILE NAME: z05h378shf.br 1.dgn
 PROJECT LEADER: S. FORTNEY
 DESIGNED BY: S. BOUCHARD
 BORING LOGS B34-B36
 PLOT DATE: 11/22/2011
 DRAWN BY: D. STANDISH
 CHECKED BY: J. DOWNAR
 SHEET 166 OF 173