

BORING LOG		Boring No.: B-43																																																																																																																												
Project Name		Page No.: 1 of 1																																																																																																																												
Knapp Airport		File No.: 965-03																																																																																																																												
Berlin, Vermont		Checked By: KEW/AMH																																																																																																																												
<p>GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140</p>																																																																																																																														
<p>Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Dan Howey Date Started: July 18, 2006 Date Finished: July 18, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft</p>																																																																																																																														
<p>Casing: H.S.A. SS L.D.: 2.25 in. 1.38 in. Hammer Wt.: NA 140 lbs Hammer Fall: NA 30 in. Rig Type: Simco 2800 Hammer Type: Safety Hammer</p>		<p>Sampler: SS Date: 7/18/06, 0:00 None observed</p>																																																																																																																												
<p>Groundwater Observations</p> <table border="1"> <thead> <tr> <th>Date</th> <th>Depth (ft)</th> <th>Elev. (ft)</th> <th>Notes</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>				Date	Depth (ft)	Elev. (ft)	Notes																																																																																																																							
Date	Depth (ft)	Elev. (ft)	Notes																																																																																																																											
<p>Sample Information</p> <table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Casing Elev./ft</th> <th rowspan="2">Number</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">RQD Reading (%)</th> </tr> <tr> <th>0 - 6</th> <th>6 - 12</th> <th>12 - 18</th> <th>18 - 24</th> </tr> </thead> <tbody> <tr> <td>0.4</td> <td></td> <td>1</td> <td>SS</td> <td>24</td> <td>17</td> <td>0</td> <td>2</td> <td>3</td> <td>4</td> <td>3</td> <td></td> <td></td> </tr> <tr> <td>2</td> <td></td> <td>2</td> <td>SS</td> <td>24</td> <td>17</td> <td>2</td> <td>3</td> <td>5</td> <td>5</td> <td>9</td> <td></td> <td></td> </tr> <tr> <td>3</td> <td></td> <td>3</td> <td>SS</td> <td>24</td> <td>16</td> <td>4</td> <td>11</td> <td>15</td> <td>25</td> <td>29</td> <td></td> <td></td> </tr> <tr> <td>4</td> <td></td> <td>4</td> <td>SS</td> <td>24</td> <td>21</td> <td>6</td> <td>23</td> <td>21</td> <td>27</td> <td>37</td> <td></td> <td></td> </tr> <tr> <td>5</td> <td></td> <td>5</td> <td>SS</td> <td>24</td> <td>18</td> <td>8</td> <td>24</td> <td>15</td> <td>17</td> <td>26</td> <td></td> <td></td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Depth (ft)	Casing Elev./ft	Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)	0 - 6	6 - 12	12 - 18	18 - 24	0.4		1	SS	24	17	0	2	3	4	3			2		2	SS	24	17	2	3	5	5	9			3		3	SS	24	16	4	11	15	25	29			4		4	SS	24	21	6	23	21	27	37			5		5	SS	24	18	8	24	15	17	26			10													15													20													<p>Strata Description</p> <p>Depth & Elevation (feet)</p> <p>0.4 Topsoil Sandy Silt</p> <p>4 Glacial Till</p> <p>10 Bottom of Exploration at 10.0 ft</p>		<p>Sample Description</p> <p>Classification System: Bernierster</p> <p>Top 5": TOPSOIL Bottom 12": Loose, brown SILT, little fine to coarse Sand, trace fine Gravel, trace Root fibers, (moist)</p> <p>Medium dense, brown SILT, little fine to coarse Sand, trace fine Gravel, trace Root fibers, (moist)</p> <p>Dense, brown SILT, little fine to coarse Sand, trace fine Gravel, 2" thick seam of very dark brown silty fine Sand at very bottom (possibly weathered Gravel, (moist)</p> <p>Dense, light brown SILT and fine to coarse SAND, some fine to coarse Gravel, (moist)</p> <p>Dense, light brown SILT, some fine to coarse Gravel, little fine to coarse SAND, (moist)</p>	
Depth (ft)	Casing Elev./ft							Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)																																																																																																												
		0 - 6	6 - 12	12 - 18	18 - 24																																																																																																																									
0.4		1	SS	24	17	0	2	3	4	3																																																																																																																				
2		2	SS	24	17	2	3	5	5	9																																																																																																																				
3		3	SS	24	16	4	11	15	25	29																																																																																																																				
4		4	SS	24	21	6	23	21	27	37																																																																																																																				
5		5	SS	24	18	8	24	15	17	26																																																																																																																				
10																																																																																																																														
15																																																																																																																														
20																																																																																																																														
<p>Remarks</p>																																																																																																																														
<p>Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.</p>																																																																																																																														
		Boring No.: B-43																																																																																																																												

BORING LOG		Boring No.: B-44																																																																																																																												
Project Name		Page No.: 1 of 1																																																																																																																												
Knapp Airport		File No.: 965-03																																																																																																																												
Berlin, Vermont		Checked By: KEW/AMH																																																																																																																												
<p>GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140</p>																																																																																																																														
<p>Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Dan Howey Date Started: July 18, 2006 Date Finished: July 18, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft</p>																																																																																																																														
<p>Casing: H.S.A. SS L.D.: 2.25 in. 1.38 in. Hammer Wt.: NA 140 lbs Hammer Fall: NA 30 in. Rig Type: Simco 2800 Hammer Type: Safety Hammer</p>		<p>Sampler: SS Date: 7/18/06, 9:10 Wet sample</p>																																																																																																																												
<p>Groundwater Observations</p> <table border="1"> <thead> <tr> <th>Date</th> <th>Depth (ft)</th> <th>Elev. (ft)</th> <th>Notes</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>				Date	Depth (ft)	Elev. (ft)	Notes																																																																																																																							
Date	Depth (ft)	Elev. (ft)	Notes																																																																																																																											
<p>Sample Information</p> <table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Casing Elev./ft</th> <th rowspan="2">Number</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">RQD Reading (%)</th> </tr> <tr> <th>0 - 6</th> <th>6 - 12</th> <th>12 - 18</th> <th>18 - 24</th> </tr> </thead> <tbody> <tr> <td>0.4</td> <td></td> <td>1</td> <td>SS</td> <td>24</td> <td>15</td> <td>0</td> <td>2</td> <td>6</td> <td>7</td> <td>7</td> <td></td> <td></td> </tr> <tr> <td>2</td> <td></td> <td>2</td> <td>SS</td> <td>24</td> <td>17</td> <td>2</td> <td>5</td> <td>8</td> <td>9</td> <td>15</td> <td></td> <td></td> </tr> <tr> <td>3</td> <td></td> <td>3</td> <td>SS</td> <td>24</td> <td>18</td> <td>4</td> <td>9</td> <td>11</td> <td>13</td> <td>16</td> <td></td> <td></td> </tr> <tr> <td>4</td> <td></td> <td>4</td> <td>SS</td> <td>24</td> <td>10</td> <td>6</td> <td>13</td> <td>15</td> <td>12</td> <td>18</td> <td></td> <td></td> </tr> <tr> <td>5</td> <td></td> <td>5</td> <td>SS</td> <td>24</td> <td>16</td> <td>8</td> <td>17</td> <td>21</td> <td>32</td> <td>49</td> <td></td> <td></td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Depth (ft)	Casing Elev./ft	Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)	0 - 6	6 - 12	12 - 18	18 - 24	0.4		1	SS	24	15	0	2	6	7	7			2		2	SS	24	17	2	5	8	9	15			3		3	SS	24	18	4	9	11	13	16			4		4	SS	24	10	6	13	15	12	18			5		5	SS	24	16	8	17	21	32	49			10													15													20													<p>Strata Description</p> <p>Depth & Elevation (feet)</p> <p>0.4 Topsoil Sandy Silt</p> <p>3 Glacial Till</p> <p>10 Bottom of Exploration at 10.0 ft</p>		<p>Sample Description</p> <p>Classification System: Bernierster</p> <p>Top 4": TOPSOIL Bottom 11": Medium dense, light brown/olive SILT, some (+) fine to coarse Sand, (moist)</p> <p>Medium dense, light brown/olive SILT, some f. Sand, trace fine Gravel (moist)</p> <p>Medium dense, brown fine to medium SAND, some Silt, (moist)</p> <p>Medium dense, light brown/olive SILT, some (+) fine to medium Sand, (wet)</p> <p>Very dense, light brown/olive SILT, little (+) fine to coarse Sand, trace fine Gravel (moist)</p>	
Depth (ft)	Casing Elev./ft							Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)																																																																																																												
		0 - 6	6 - 12	12 - 18	18 - 24																																																																																																																									
0.4		1	SS	24	15	0	2	6	7	7																																																																																																																				
2		2	SS	24	17	2	5	8	9	15																																																																																																																				
3		3	SS	24	18	4	9	11	13	16																																																																																																																				
4		4	SS	24	10	6	13	15	12	18																																																																																																																				
5		5	SS	24	16	8	17	21	32	49																																																																																																																				
10																																																																																																																														
15																																																																																																																														
20																																																																																																																														
<p>Remarks</p>																																																																																																																														
<p>Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.</p>																																																																																																																														
		Boring No.: B-44																																																																																																																												

BORING LOG		Boring No.: B-45																																																																																																								
Project Name		Page No.: 1 of 1																																																																																																								
Knapp Airport		File No.: 965-03																																																																																																								
Berlin, Vermont		Checked By: KEW/AMH																																																																																																								
<p>GEODESIGN INCORPORATED Geotechnical Engineers-Environmental Consultants-Construction Engineers P.O. Box 699 Windsor, VT 05089 Phone: 802-674-2033 Fax: 802-674-5943 1233 Shelburne Rd, Suite 360 South Burlington, VT 05403 Phone: 802-652-5140</p>																																																																																																										
<p>Boring Company: Specialty Drilling & Investigation Foreman: Chris Aldrich GeoDesign Rep.: Jack Wilmitt Date Started: July 21, 2006 Date Finished: July 21, 2006 N. Coordinate: E. Coordinate: Ground Surface Elevation (feet): Station: Offset: ft</p>																																																																																																										
<p>Casing: H.S.A. SS L.D.: 2.25 in. 1.38 in. Hammer Wt.: NA 140 lbs Hammer Fall: NA 30 in. Rig Type: Simco 2800 Hammer Type: Safety Hammer</p>		<p>Sampler: SS Date: 7/21/06, 0:00 None observed</p>																																																																																																								
<p>Groundwater Observations</p> <table border="1"> <thead> <tr> <th>Date</th> <th>Depth (ft)</th> <th>Elev. (ft)</th> <th>Notes</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>				Date	Depth (ft)	Elev. (ft)	Notes																																																																																																			
Date	Depth (ft)	Elev. (ft)	Notes																																																																																																							
<p>Sample Information</p> <table border="1"> <thead> <tr> <th rowspan="2">Depth (ft)</th> <th rowspan="2">Casing Elev./ft</th> <th rowspan="2">Number</th> <th rowspan="2">Type</th> <th rowspan="2">Penetration (lb/in)</th> <th rowspan="2">Recovery (lb/in)</th> <th colspan="5">Blows / 6 inch Interval</th> <th rowspan="2">Coring Time (min./ft)</th> <th rowspan="2">RQD Reading (%)</th> </tr> <tr> <th>0 - 6</th> <th>6 - 12</th> <th>12 - 18</th> <th>18 - 24</th> </tr> </thead> <tbody> <tr> <td>0.5</td> <td></td> <td>1</td> <td>SS</td> <td>18</td> <td>12</td> <td>0.5</td> <td>41</td> <td>52</td> <td>65</td> <td></td> <td></td> </tr> <tr> <td>2</td> <td></td> <td>2</td> <td>SS</td> <td>24</td> <td>15</td> <td>2</td> <td>41</td> <td>54</td> <td>56</td> <td>68</td> <td></td> </tr> <tr> <td>3</td> <td></td> <td>3</td> <td>SS</td> <td>24</td> <td>15</td> <td>4</td> <td>26</td> <td>44</td> <td>57</td> <td>74</td> <td></td> </tr> <tr> <td>4</td> <td></td> <td>4</td> <td>SS</td> <td>24</td> <td>16</td> <td>6</td> <td>46</td> <td>41</td> <td>53</td> <td>68</td> <td></td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Depth (ft)	Casing Elev./ft	Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)	0 - 6	6 - 12	12 - 18	18 - 24	0.5		1	SS	18	12	0.5	41	52	65			2		2	SS	24	15	2	41	54	56	68		3		3	SS	24	15	4	26	44	57	74		4		4	SS	24	16	6	46	41	53	68		10												15												20												<p>Strata Description</p> <p>Depth & Elevation (feet)</p> <p>0.5 Pavement Base Course Gravel & Sand</p> <p>2 Subbase Sand</p> <p>5.2 Glacial Till</p> <p>8 Bottom of Exploration at 8.0 ft</p>		<p>Sample Description</p> <p>Classification System: Bernierster</p> <p>Very dense, gray-white fine to coarse SAND, some fine to coarse Gravel, trace Silt, (dry)</p> <p>Very dense, light brown fine to coarse SAND, little fine to coarse Gravel, trace Silt, (moist)</p> <p>Very dense, Top 14": light brown fine to coarse SAND, little fine to coarse Gravel, trace Silt, (moist) Bottom 1": brownish gray fine SAND, and SILT, some fine Gravel, little coarse Sand, (moist)</p> <p>Very dense, brownish gray fine to medium SAND and SILT, little (+) fine to coarse Gravel, trace coarse Sand, (moist to wet)</p>	
Depth (ft)	Casing Elev./ft							Number	Type	Penetration (lb/in)	Recovery (lb/in)	Blows / 6 inch Interval					Coring Time (min./ft)	RQD Reading (%)																																																																																								
		0 - 6	6 - 12	12 - 18	18 - 24																																																																																																					
0.5		1	SS	18	12	0.5	41	52	65																																																																																																	
2		2	SS	24	15	2	41	54	56	68																																																																																																
3		3	SS	24	15	4	26	44	57	74																																																																																																
4		4	SS	24	16	6	46	41	53	68																																																																																																
10																																																																																																										
15																																																																																																										
20																																																																																																										
<p>Remarks</p> <p>Boring location on the runway. Augered through 6" of asphalt prior to sampling S-1 from .5 to 2 feet below grade.</p>																																																																																																										
<p>Notes: 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable. 2) Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded. 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50% 5) Stratification lines represent approximate boundary between material types. Transitions may be gradual.</p>																																																																																																										
		Boring No.: B-45																																																																																																								

- Notes:
- 1) Soil Samples screened in the field using a Thermal Environmental Systems Model 580S Photoionization Detector (unless otherwise noted in Remarks). The meter was calibrated relative to a benzene in air standard. N.D. = None Detected; N.R. = Not Recorded; N.A. = Not Applicable; O.R. = Out of Range
 - 2) Water level readings have been made at times and under conditions stated, fluctuations of groundwater may occur due to other factors than those present at the time measurements were made. A.C. = After coring; N.R. = Not Recorded.
 - 3) Sample Type Coding: A = Auger; C = Core; D = Driven; G = Grab; PS = Piston Sample; SS = Split Barrel (Split Spoon); ST = Shelby Tube; V = Vane; WGR/H = Weight of Rod/Hammer
 - 4) Proportions Used: Trace = 1-10%; Little = 10-20%; Some = 20-35%; And = 35-50%
 - 5) Stratification lines represent approximate boundary between material types, transitions may be gradual.
 - 6) Bedrock cores collected at locations c-1, c-2, and c-3 typically consist of gray, soft, moderately weathered phyllite bedrock of very poor to fair quality, the rock was fissile and crumbled with moderate finger pressure. Fractures were typically noted along the fissile planes between approximately 60 and 70 degrees (measures from the horizontal). Rock quality designation (RQD) values ranged between 0 and 55%. The rock type was consistent with mapping data published on the Centennial Geologic Map of Vermont (dott, 1981) and a rock outcrop located approximately 500 feet north of the site (along Airport Road).
 - 7) Bedrock removal for this project can be accomplished using conventional mechanical equipment. Mechanical removal methods can include excavating, ripping, hoe-ramping and splitting. An alternative method of removal is blasting.
 - 8) The effort and difficulty of rock removal will generally increase with the depth once the upper, more weathered rock has been penetrated (estimated up to between 5 and 10 feet deep).
 - 9) Rock Reuse Potential - the type and condition of rock anticipated for removal will be poor aggregate for use in the base course below new pavements.

Hoyle, Tanner & Associates, Inc.
 150 Dow Street
 Manchester, NH 03101-1227
 Tel 603-669-5555
 Fax 603-669-4168
 Web Page: www.hoyletanner.com
 Hoyle Tanner & Associates © 2008

PROJECT NAME: E. F. KNAPP STATE AIRPORT
 A.I.P. 3-50-0001-011-2009
 PROJECT NUMBER: BERLIN AIR 04-3216

FILE NAME: z05h378sh_t.br 1.dgn
 PROJECT LEADER: S. FORTNEY
 DESIGNED BY: S. BOUCHARD
 BORING LOGS B43-B45

PLOT DATE: 11/22/2011
 DRAWN BY: D. STANDISH
 CHECKED BY: J. DOWNAR
 SHEET 169 OF 173