

QUANTITY SHEET

DESCRIPTIONS			
ITEM NUMBER	UNIT	ITEMS	PHASE II RUNWAY SAFETY AREA
601.996	LF	CLEANING CULVERT PIPE, IN-PLACE (GREATER THAN 24")	440
608.25	HOURL	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	100
609.10	MGAL	DUST CONTROL WITH WATER	3,000
619.10	CY	STONE FILL, TYPE I	30
620.12	LF	CHAIN LINK FENCE (6')	400
620.16	LF	GATE FOR CHAIN-LINK FENCE (6')	16
620.17	LF	GATE FOR CHAIN-LINK FENCE (8')	20
620.21	EA	BRACING ASSEMBLY FOR CHAIN LINK FENCE (6')	8
620.50	LF	REMOVING AND RESETTING FENCE	400
630.15	HOURL	FLAGGERS	1,440
631.10	LS	FIELD OFFICE, ENGINEERS	1
631.26	DL	FIELD OFFICE TELEPHONE	4,000
635.11	LS	MOBILIZATION/DEMobilIZATION	1
649.11	SY	GEOTEXTILE FOR ROADBED SEPARATOR	150
649.31	SY	GEOTEXTILE UNDER STONE FILL	1,360
649.51	SY	GEOTEXTILE FOR SILT FENCE	500
651.15	LB	SEED	1,200
651.18	LB	FERTILIZER	8,000
651.20	TON	AGRICULTURAL LIMESTONE	25
651.25	TON	HAY MULCH	38
651.35	CY	TOPSOIL	4,800
653.20	SY	TEMPORARY EROSION MATTING	33,500
653.21	SY	PERMANENT EROSION MATTING	24,000
653.35	CY	VEHICLE TRACKING PAD	800
653.55	LF	PROJECT DEMARCATION FENCE	8,200
653.60	LF	EROSION LOG	200
D-701-5.1.1	LF	12" DIA. CPEP	80
D-701-5.1.2	LF	18" DIA. CPEP	1,260
D-701-5.1.3	EA	18" DIA. CPEPES	2
D-701-5.1.4	LF	36" DIA. CPEP(SL)	16
D-701-5.1.5	LF	24" DIA. CPEP	2
D-701-5.1.6	LF	30" DIA. CPEP	55
D-701-5.2	CY	CONCRETE FOR PIPE CRADLES	5
D-701-5.3	CY	ROCK EXCAVATION	50
D-751-5.1	EA	PRECAST REINFORCED CONCRETE MANHOLE	6
D-751-5.3	EA	PRECAST REINFORCED CONCRETE DROP INLET	7
G-152-4.1	SY	GEOGRID REINFORCEMENT	11,000
L-125-5.1	LS	MODIFICATIONS TO MALSR & VASI	1
L-125-5.2	LS	INSTALLATION OF TEMPORARY PAPI SYSTEM	1
L-150-5.1	EA	TEMPORARY RUNWAY THRESHOLD LIGHTING	1
M-1-14.1	LS	REMOBILIZATION	1
M-10-5.1	LS	TEMPORARY CONSTRUCTION ITEMS	1
P-151-4.3	ACRE	CLEARING AND GRUBBING	1
P-152-4.1	CY	UNCLASSIFIED EXCAVATION	9,000
P-152-4.2	CY	EMBANKMENT IN PLACE	250,000
P-152-4.3	SF	SEGMENTAL RETAINING WALL	7,000
P-156-5.1	SY	TEMPORARY SEEDING AND MULCHING	33,500
P-156-5.3	CY	TEMPORARY BENCHES, DIKES, DAMS, & SEDIMENT BASINS	6,200
P-620-5.1	SF	TEMPORARY AIRFIELD PAVEMENT MARKINGS	18,500
P-620-5.2	SF	PERMANENT AIRFIELD PAVEMENT MARKINGS	21,600
P-620-5.3	SF	REMOVAL OF AIRFIELD PAVEMENT MARKINGS	39,600



AIP 3-50-0015-34

VERMONT AGENCY OF TRANSPORTATION



PROJECT NAME: RUTLAND SOUTHERN VERMONT REGIONAL AIRPORT
CLARENDON, VERMONT
PROJECT NUMBER: AV14-8018-300
FILE NAME: z07h124qs.dgn
PROJECT LEADER: F. WALSH
DESIGNED BY: G. D'AMICO
QUANTITY SHEET
PLOT DATE: 6/2/2013
DRAWN BY:
CHECKED BY:
SHEET 3 OF 36