QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
8200	LF	ELECTRICAL CONDUIT, (MOD.)	678.21	-
2000	SF	P-620 RUNWAY AND TAXI-WAY PAINTING	864.03	-
8200	LF	CABLE TRENCH L-108	864.04	-
8200	LF	L-108, 1/C #8, L-824, TYPE C 5KV	864.05	-
8200	LF	L-108, #8 COUNTERPOISE WIRE	864.06	-
1	LS	L-109, INSTALLATION OF AIRPORT TRANSFORMER VAULT EQUIPMENT (MOD.)	864.07	-
60	LF	L-110, 2 WAY X 4'' DIA. U.G. ELEC. DUCT	864.08	-
300	LF	L-110, 4 WAY X 4'' DIA. U.G. ELEC. DUCT	864.09	-
78	EA	MEDIUM INTENSITY TAXIWAY LIGHTS BASE MOUNTED	864.11	-
5	EA	TAXI-WAY GUIDANCE SIGNS, 5 PANEL, SIZE 1, STYLE 2, CLASS 2	864.14	-
4	EA	TAXI-WAY GUIDANCE SIGNS, 5 PANEL, SIZE 1, STYLE 2, CLASS 2 (MOD.)	864.14	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

REVISED 9-15-93 P.D

PROJECT NAME RUTLAND TAXI-WAY PROJECT
PROJECT NUMBER 04-3083