



STATE OF VERMONT
AGENCY OF TRANSPORTATION



CONTRACT PLANS

THESE PLANS, DO NOT REFLECT
CHANGES MADE ON THE PROJECT.



INDEX OF SHEETS


- 1 TITLE SHEET
- 2 GENERAL PROJECT LAYOUT
- 3 SAFETY NOTES
- 4 GENERAL CONSTRUCTION AND SAFETY NOTES
- 5-6 LOCALIZER SITE DETAILS
- 7 LOCALIZER RELOCATION - SITE PLAN
- 8 SEDIMENTATION / EROSION CONTROL PLANS
- 9 BORING LOGS

PROPOSED IMPROVEMENTS
RUTLAND STATE AIRPORT
CLARENDON, VERMONT
AIP NO. 3-50-0015-10
E.A. 043111

TO INCLUDE: LOCALIZER SITE PREPARATION

AP-2 STANDARDS 06/01/94
AP-3 06/01/94
AP-10 06/01/94

| TABLE OF QUANTITIES | | |
|---------------------|------------------------|--------------------|
| ITEM NO. | DESCRIPTION | ESTIMATED QUANTITY |
| N/A | LOCALIZER SITE WORK | 1 LUMP SUM |
| L-170 | UTILITY COST ALLOWANCE | 1 LUMP SUM |
| 635.10 | MOBILIZATION | 1 LUMP SUM |



LOCATION MAP

APPROXIMATE SCALE : 1" = 1 MILE

Date NOV 03 1997

 The Belden Company, Inc.
 Contractor
Carl D. Belden
 Signature
 Vice President

Alan Kerwin
 Secretary of Transportation's Signature

A.A.I.A. OF 1982 SECTION 509(d) ASSURANCES
 IN COMPLIANCE WITH THE AIRPORT AND AIRWAYS IMPROVEMENT ACT OF 1982, SECTION 509 (d) AND THE SPONSOR'S CERTIFICATION, DATED _____, THESE PLANS AND SPECIFICATIONS HAVE BEEN PREPARED IN ACCORDANCE WITH CURRENT FAA STANDARDS IDENTIFIED IN F.A.R. PART 132. ANY DEVIATION FROM THE FAA STANDARD WERE APPROVED IN A LETTER BY THE FAA, DATED _____, 1998, AND ARE DISCUSSED IN THE ENGINEERING REPORT ACCOMPANYING THESE PLANS.
 _____ DESIGN ENGINEER _____ DATE _____

URS Greiner, Inc.
 STATE OF VERMONT
 APPROVED *URS Greiner, Inc.* DATE 6-18-97
 DIRECTOR OF RAIL, HIGHWAY & PUBLIC TRANSPORTATION
 DEPARTMENT OF TRANSPORTATION
 FEDERAL AVIATION ADMINISTRATION
 APPROVED _____ DATE _____
 CHIEF, AIRPORTS DIVISION

GENERAL CONSTRUCTION AND SAFETY NOTES

GENERAL NOTES

1. THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT PLANS AND SPECIFICATIONS AND ALL RULES, REGULATIONS, STANDARDS OR SPECIFICATIONS REFERENCED THEREIN. THE PROJECT IS SUBJECT TO INSPECTION BY REPRESENTATIVES OF THE VERMONT AGENCY OF TRANSPORTATION (VAOT), AND THE FEDERAL AVIATION ADMINISTRATION (FAA).
2. THE PROJECT IS TO BE COMPLETED IN CONFORMANCE WITH THESE "CONSTRUCTION PHASING PLANS AND NOTES," AS CONTAINED IN THE PLANS, AND SHALL BE CONSTRUCTED IN A TIMELY MANNER IN ACCORDANCE WITH THE CONTRACTOR'S APPROVED PROJECT SCHEDULE. THE SCHEDULE SHALL PROVIDE FOR COMPLETION OF THE PHASES AS SHOWN ON THE PLANS AND DESCRIBED IN THE CONTRACT SPECIFICATIONS.
3. THE CONTRACTOR IS EXPECTED TO MEET COMPLETION OF CRITICAL PORTIONS OF THE PROJECT AND OPEN THOSE SEGMENTS TO TRAFFIC BY THE SPECIFIED TIMES AND TO COMPLETE THE ENTIRE PROJECT ON TIME.
4. RUTLAND STATE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF ALL WORK WITH THE AIRPORT MANAGER & THE PROJECT RESIDENT ENGINEER IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
5. CONSTRUCTION AND MAINTENANCE OPERATIONS BY OTHERS MAY OCCUR CONCURRENTLY AND AT TIMES IN THE VICINITY OF CONSTRUCTION ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL COORDINATE HIS OPERATIONS AND COOPERATE WITH MAINTENANCE CROWS AND OTHER CONTRACTORS WORKING ON THE AIRPORT.
6. ACCESS TO THE SITE - THE CONTRACTOR'S ACCESS POINTS TO THE SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT PLAN. SUBSEQUENT DISTRIBUTION OFFICE FOR ALL VEHICLES AND PERSONNEL WHO ENTER THROUGH THESE ACCESS POINTS, THE CONTRACTOR SHALL MAINTAIN A SECURITY GUARD AT EACH GATE BEING USED AT ALL TIMES WHILE CONSTRUCTION IS UNDERWAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING ALL ACCESS POINTS BEING USED AT THE END OF EACH CONSTRUCTION DAY ON WHEN ACCESS POINTS ARE UNATTENDED.
7. HAUL ROUTES - APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE OR TOWN HIGHWAYS) WITH THE APPROPRIATE AGENCIES WHO HAVE JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO COMMENCING THE WORK. EXISTING ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
8. CONTRACTOR'S STAGING AREAS - AN AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE. THIS AREA IS SHOWN ON THE GENERAL PROJECT LAYOUT. THE CONTRACTOR'S STAGING AREA SHALL BE GRADED, TOPSOILED, SEEDED, AND MULCHED UPON COMPLETION OF USE, AT THE CONTRACTOR'S EXPENSE.
9. DISPOSAL AREA - WASTE AREAS WILL BE MADE AVAILABLE FOR THE DISPOSAL OF EXCESS MATERIALS. THE MANNER IN WHICH MATERIALS ARE PLACED IN EMBANKMENTS SHALL BE AS SPECIFIED BY THE ENGINEER. WASTE MATERIALS INCLUDE THOSE ITEMS WHICH ARE A DIRECT RESULT OF CONSTRUCTION (BRUSH (E.G. CUTS, CANES, ETC.) SHALL BE DISPOSED OF THROUGH PROPER SANITARY METHODS.
10. SAFETY - THE CONTRACTOR SHALL CONDUCT HIS ACTIVITIES IN A SAFE MANNER AS SPECIFIED IN THE SECTION TITLED, "SAFETY REQUIREMENTS DURING CONSTRUCTION" ON THIS SHEET.
11. PROTECTION OF AND REPAIR OF DAMAGE TO EXISTING CABLES - LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OF CABLES DAMAGED DUE TO CONTRACTOR'S OPERATIONS MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND SHALL BE AT THE CONTRACTOR'S EXPENSE. WHEN FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF AN FAA REPRESENTATIVE. THE FAA MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.
12. EXISTING AIRFIELD LIGHTING SYSTEMS - INTERRUPTION OF EXISTING AIRFIELD LIGHTING SYSTEMS NOT INCLUDED IN THIS PROJECT SHALL NOT BE PERMITTED. ALL AIRFIELD LIGHTING CIRCUITS AFFECTED BY THIS PROJECT SHALL BE MAINTAINED BY THE CONTRACTOR DURING OPERATIONAL PERIODS IN ACCORDANCE WITH THE SPECIFICATIONS AND/OR AS DIRECTED BY THE ENGINEER.
13. CONSTRUCTION LIMITS - ALL CONTRACTOR VEHICLES AND TRAFFIC (UNLESS OTHERWISE AUTHORIZED) SHALL REMAIN WITHIN THE BOUNDARIED CONSTRUCTION LIMITS. HAUL ROUTES, STAGING AREAS, STORAGE AND STOCKPILING LIMITS ARE FURTHER DEFINED IN THE SECTION TITLED, "SAFETY REQUIREMENTS DURING CONSTRUCTION" ON THIS SHEET.

14. PORTABLE FLOODLIGHTING - THE CONTRACTOR SHALL PROVIDE PORTABLE FLOODLIGHTING WHEN REQUIRED FOR CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL PROVIDE SUFFICIENT UNITS SO THAT ALL WORK AREAS ARE ILLUMINATED TO A LEVEL OF 5 HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY.
15. THE CONTRACTOR SHALL OBTAIN ALL PERMITS AND LICENSES REQUIRED FOR HIS PROJECT WORK ON THE PROJECT AT HIS OWN EXPENSE.
16. EXISTING TOPOGRAPHIC FIELD SURVEYS FOR THIS PROJECT AREA WERE PERFORMED BY LITTLE RIVER SURVEY CO. IN 1955 & 1957.
17. THE HORIZONTAL CONTROL ON THIS PROJECT IS TIED TO THE 1983 AND 1988 NATIONAL GEODETIC HORIZONTAL AND VERTICAL DATUM, RESPECTIVELY.

SAFETY REQUIREMENTS DURING CONSTRUCTION

- (A) FEDERAL AVIATION ADMINISTRATION (FAA) ADVISORY CIRCULARS (AC), ORDERS AND FEDERAL AVIATION REGULATIONS (FAR).
THE FOLLOWING PUBLICATIONS CONTAIN DEFINITIONS/DESCRIPTIONS OF CRITICAL AIRPORT OPERATING AREAS. THE AREAS DEFINED BELOW PERTAIN TO AIRFIELD SAFETY REQUIREMENTS AND ARE REFERENCED THROUGHOUT THE CONTRACT DOCUMENTS. COPIES OF THESE PUBLICATIONS ARE AVAILABLE THROUGH THE FAA OR CAN BE ORDERED BY MAIL FROM:
U.S. DEPARTMENT OF TRANSPORTATION
SUBSEQUENT DISTRIBUTION OFFICE
ARMONK EAST BUSINESS CENTER
3341 Q 79TH AVE.
LAWSONVILLE, MD. 20785
AND CAN BE REVIEWED AT THE OFFICES OF THE VERMONT AGENCY OF TRANSPORTATION, MAIL, AIR AND PUBLIC TRANSPORTATION DIVISION, NATIONAL LIFE BUILDING, MONTPELIER, VERMONT.
(1) AC 150/5370-3, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", CURRENT EDITION.
(2) FAR PART 77 "OBJECTS AFFECTING NAVIGABLE AIRSPACE", CURRENT EDITION.
(3) AC 150/5300-13 "AIRPORT DESIGN", CURRENT EDITION, ESTABLISHES DESIGN OPERATIONAL AND MAINTENANCE STANDARDS FOR AIRPORTS. STANDARD TERMS USED IN THE CONTRACT PLANS AND SPECIFICATIONS ARE DEFINED BELOW:
(a) RUNWAY PROTECTION ZONE (RPZ): A TRIANGULAR AREA CENTERED ON THE RUNWAY BEGINNING AT A POINT 500 FEET BEYOND THE END OF THE AREA USABLE FOR TAKEOFF OR LANDING. THE RPZ IS SHOWN ON THE GENERAL PROJECT LAYOUT PLAN.
(b) OBJECT FREE AREA (OFA): A TWO DIMENSIONAL GROUND AREA SURROUNDING RUNWAYS, TAXIWAYS, AND TAXILANES WHICH IS CLEAR OF OBJECTS EXCEPT FOR OBJECTS WHOSE LOCATION IS FIXED BY FUNCTION.
(c) SAFETY AREA - THE SURFACE ADJACENT TO RUNWAYS, TAXIWAYS, AND TAXILANES OVER WHICH AIRCRAFT SHOULD, IN DRY WEATHER, BE ABLE TO CROSS AT NORMAL SPEEDS WITHOUT INCURRING SIGNIFICANT DAMAGE. A SAFETY AREA IS GRADED, DRAINED AND COMPACTED. IT IS FREE OF ANY HOLETS, TRENCHES, BUMPS OR OTHER SURFACE VARIATIONS OR OBJECTS OTHER THAN THOSE WHICH MUST BE THERE BECAUSE OF THEIR ESSENTIAL AERONAUTICAL FUNCTION. THE SAFETY AREA REQUIRES THE CAPABILITY OF SUPPORTING MAINTENANCE VEHICLES AND AIRCRAFT RESCUE AND FIRE FIGHTING VEHICLES UNDER NORMAL (DRY) CONDITIONS.
(3) GENERAL SAFETY REQUIREMENTS
(1) THE CONTRACTOR SHALL ACQUAINT HIS SUPERVISORS AND EMPLOYEES WITH THE AIRPORT ACTIVITY AND OPERATIONS THAT ARE INHERENT TO RUTLAND STATE AIRPORT AND SHALL CONDUCT HIS CONSTRUCTION ACTIVITIES IN CONFORMANCE TO ALL ROUTINE AND EMERGENCY AIR TRAFFIC REQUIREMENTS AND GUIDELINES FOR SAFETY SPECIFIED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL SAFETY DEVICES AS REQUIRED FOR THE PROTECTION OF HIS PERSONNEL.
(2) PROTECTION OF ALL PERSONS SHALL BE PROVIDED THROUGHOUT THE PROGRESS OF THE WORK. THE WORK SHALL BE PERFORMED IN SUCH A MANNER AS TO PROVIDE SAFE CONDITIONS FOR ALL WORKERS AND AGENCY PERSONNEL. THE SEQUENCE OF OPERATIONS SHALL BE SUCH THAT MAXIMUM PROTECTION IS AFFORDED TO INSURE THAT PERSONS AND WORKERS IN THE WORK AREA ARE NOT SUBJECT TO ANY DANGEROUS CONDITIONS.

- (3) DURING PERFORMANCE OF THIS CONTRACT, THE AIRPORT RUNWAYS, TAXIWAYS AND AIRCRAFT PARKING AREAS SHALL REMAIN IN USE BY AIRCRAFT TO THE MAXIMUM EXTENT POSSIBLE. ALL AIRCRAFT TRAFFIC ON THESE AREAS SHALL HAVE PRIORITY OVER CONTRACTOR'S TRAFFIC. THE OWNER RESERVES THE RIGHT TO ORDER THE CONTRACTOR AT ANY TIME TO VACATE ANY AREA NECESSARY TO MAINTAIN SAFE AIRCRAFT OPERATIONS. USE OF AREAS NEAR THE CONTRACTOR'S WORK WILL BE CONTROLLED TO MINIMIZE DISTURBANCE TO THE EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, OR ANY OTHER UNAUTHORIZED PERSON TO ENTER OR REMAIN IN ANY AIRPORT AREA WHICH WOULD BE HAZARDOUS TO PERSONS OR TO AIRCRAFT OPERATIONS.
- (4) ALL WORK TO BE PERFORMED WHICH IS CLOSE TO AN ACTIVE RUNWAY, TAXIWAY OR APRON SHALL BE PERFORMED WHEN THE RUNWAY, TAXIWAY OR APRON IS NOT IN USE. SUCH WORK SHALL BE ACCOMPLISHED ONLY WITH PRIOR PERMISSION FROM THE ENGINEER AND AIRPORT MANAGER. REQUESTED CLOSINGS SHALL BE DIRECTED TO THE ENGINEER AT LEAST 48 HOURS IN ADVANCE.


CONSTRUCTION AND FACILITIES MAINTENANCE

- (1) THE FOLLOWING ARE CONSIDERED SAFETY PROBLEMS AND/OR HAZARDS:
(a) TRENCHES, HOLES, OR EXCAVATION ON OR ADJACENT TO ANY OPEN RUNWAY OR IN RUNWAY OR TAXIWAY SAFETY AREAS.
(b) UNMARKED/UNLIGHTED HOLES OR EXCAVATION IN ANY APRON, OPEN TAXIWAY, OPEN TAXILANE, OR RELATED SAFETY AREA.
(c) MOUNDS OR PILES OF EARTH, CONSTRUCTION MATERIALS, TEMPORARY STRUCTURES, OR OTHER OBJECTS IN THE VICINITY OF ANY OPEN RUNWAY OR IN RUNWAY OR TAXIWAY SAFETY AREAS.
(d) VEHICLES OR EQUIPMENT, WHETHER OPERATING OR IDLE, ON ANY OPEN RUNWAY, TAXIWAY, TAXILANE, OR IN ANY RELATED SAFETY, APPROACH, OR DEPARTURE AREA.
(e) VEHICLES, EQUIPMENT, EXCAVATION, STOCKPILES, OR OTHER MATERIALS WHICH COULD INTERFERE WITH ELECTRONIC SIGNALS FROM RADIOS OR ELECTRONIC NAVIGATIONAL AIDS (NAVDARS).
(f) PAVEMENT DROP-OFFS - LIPS (EITHER PERMANENT OR TEMPORARY, WHICH COULD CAUSE DAMAGE TO AIRCRAFT IF CROSSED AT NORMAL OPERATING SPEEDS, THE NORMAL MAXIMUM DROP-OFF OR LIP IS 1-1/2 INCHES.
(g) UNMARKED UTILITY, NAVAID, WEATHER SERVICE, RUNWAY LIGHTING, OR OTHER POWER OR SIGNAL CABLES THAT COULD BE DAMAGED DURING CONSTRUCTION.
(h) OBJECTS, WHETHER OR NOT MARKED OR FLAGGED, OR ACTIVITIES ANYWHERE ON OR IN THE VICINITY OF THE AIRPORT WHICH COULD BE DISTRACTING, CONFUSING, OR ALARMING TO PILOTS DURING AIRCRAFT OPERATIONS.
(i) UNFLAGGED/UNLIGHTED LOW VISIBILITY ITEMS SUCH AS AREA SURVEILLANCE RADAR, AND THE USE OF LIGHTS IN THE VICINITY OF ACTIVE RUNWAYS, OR IN ANY APPROACH OR DEPARTURE AREA.
(j) MISLEADING OR MALFUNCTIONING OBSTRUCTION LIGHTS OR UNLIGHTED/UNFLAGGED OBSTRUCTIONS IN THE APPROACH TO ANY ACTIVE RUNWAY.
(k) WATER, SNOW, DIRT, DEBRIS, OR OTHER TRANSIENT ACCUMULATION WHICH TEMPORARILY OCCURS PAVEMENT SURFACES OR FAVORS EVIDENT DEGRADATION OF VISIBILITY OF RUNWAY/TAXIWAY MARKINGS OR LIGHTING.
(l) INADEQUATE OR IMPROPER METHODS OF MARKING, BARBICADING, AND LIGHTING OF TEMPORARILY CLOSED PORTIONS OF THE AIRPORT OPERATIONS AREA.
(m) TRASH OR OTHER MATERIALS WITH FOREIGN OBJECT DAMAGE (FOD) POTENTIALS WHETHER ON RUNWAYS, TAXIWAYS, OR APRONS, OR IN RELATED SAFETY AREAS.
(n) INADEQUATE BARBICADING OR OTHER MARKING WHICH IS PLACED TO SEPARATE CONSTRUCTION OR MAINTENANCE AREAS FROM OPEN AIRCRAFT OPERATING AREAS.
(o) FAILURE TO CONTROL UNAUTHORIZED VEHICLES AND HUMAN ACCESS TO ACTIVE AIRCRAFT OPERATING AREAS.
(p) FAILURE TO MAINTAIN RADIO COMMUNICATION BETWEEN CONSTRUCTION/MAINTENANCE VEHICLES AND RUTLAND UNICOM.
(q) CONSTRUCTION/MAINTENANCE ACTIVITIES OR MATERIALS WHICH COULD HAMPER THE RESPONSE OF AIRCRAFT RESCUE AND FIRE FIGHTING VEHICLES OR OTHER AIRCRAFT OR ANY PART OF THE RUNWAY/TAXIWAY SYSTEM, RUNWAY APPROACH AND DEPARTURE AREAS AND AIRCRAFT PARKING LOCATIONS.
(r) BIRD ATTRACTANTS ON AIRPORT SUCH AS, EDIBLES (FOOD SCRAPS, ETC.), MISCELLANEOUS TRASH, OR PONDED WATER.

- (2) THE CONTRACTOR SHALL CONDUCT ACTIVITIES SO AS NOT TO VIOLATE ANY SAFETY STANDARDS CONTAINED HEREIN. THE CONTRACTOR SHALL INSPECT ALL CONSTRUCTION AND STORAGE AREAS AS OFTEN AS NECESSARY AND PROMPTLY TAKE ALL STEPS NECESSARY TO PREVENT/REMEDY ANY UNSAFE OR POTENTIALLY UNSAFE CONDITIONS OR ACTIVITIES DISCOVERED.
- (3) THE VAOT WILL BE RESPONSIBLE FOR ISSUING APPROPRIATE NOTICE TO AIRMEN (NOTAMS) CONCERNING CONSTRUCTION ACTIVITY ON THE AIRFIELD.
- (4) MOTORIZED VEHICLES
THIS PROJECT INCLUDES WORK WITHIN THE AIRCRAFT OPERATIONS AREA (AOA). ALL PERMITTED VEHICLES SHALL BE EQUIPPED WITH A FLASHING AMBER (YELLOW) DOM-TYPE LIGHT MOUNTED ON TOP OF THE VEHICLE AND OF SUCH INTENSITY TO CONFORM TO LOCAL CODES FOR MAINTENANCE AND EMERGENCY VEHICLES. ALL VEHICLES OPERATING WITHIN THE AIRFIELD BOUNDARY SHALL BE IDENTIFIED WITH A SIGN ON EACH SIDE OF THE VEHICLE BEARING THE CONTRACTOR'S NAME IN 12-INCH MINIMUM LETTER HEIGHT.
VEHICLES MAKING ONLY OCCASIONAL VISITS TO THE JOB SITE ARE EXEMPT FROM THE IDENTIFICATION REQUIREMENTS CONTAINED HEREIN ABOVE PROVIDED THAT THEY ARE ESCORTED INTO, THROUGH, AND OUT OF THE AIRPORT AREA BY A PROPERLY IDENTIFIED VEHICLE.
- (5) RADIO COMMUNICATIONS
RADIO COMMUNICATIONS ARE REQUIRED BETWEEN THE CONTRACTOR'S REPRESENTATIVE AND RUTLAND UNICOM. RADIO CONTACT IS REQUIRED AT ALL TIMES WHILE THE CONTRACTOR HAS PERSONNEL AND EQUIPMENT ON THE PROJECT SITE AND WHILE THEY ARE IN AN ACTIVE AIR OPERATIONS AREA (AOA) OF THE AIRPORT. RADIOS SHALL BE FURNISHED BY THE CONTRACTOR AND SHALL BE CAPABLE OF TRANSMITTING AND RECEIVING AT A GROUND CONTINUOUS FREQUENCY OF 122.8 MHz. THIS FREQUENCY IS TO BE UTILIZED WHEN CROSSING ACTIVE FACILITIES. SUFFICIENT RADIOS SHALL BE ON SITE AND OPERATING AT ALL TIMES SO THAT INSTRUCTIONS OR COMMUNICATIONS MAY BE DISPATCHED TO ALL CREW AND/OR EQUIPMENT WORKING IN AN ACTIVE AOA.
- (6) DEBRIS
DEBRIS, WASTE, AND LOOSE MATERIAL (INCLUDING DUST AND DIRT) CAPABLE OF CAUSING DAMAGE TO AIRCRAFT LANDING GEAR OR PROPELLERS, OR BEING INGESTED IN JET ENGINES, SHALL NOT BE ALLOWED ON ACTIVE AIRCRAFT MOVEMENT AREAS OR ADJACENT GRASSED AREAS. MATERIALS OBSERVED TO BE WITHIN THESE AREAS SHALL BE REMOVED IMMEDIATELY BY THE CONTRACTOR. THE CONTRACTOR SHALL BE REQUIRED TO HAVE A SWEEPING MACHINE AND OPERATOR ON SITE AND READY AT ALL TIMES DURING CONSTRUCTION ACTIVITY, WHERE TRAVEL ON OR ACROSS RUNWAYS, RAMP AREAS, TAXIWAYS, OR AIRCRAFT APRONS IS REQUIRED. THE CONTRACTOR SHALL PROVIDE ADEQUATE PERSONNEL AND EQUIPMENT TO KEEP SUCH SURFACES CLEAR OF DEBRIS.
- (7) FLAGMEN
IN ACCORDANCE WITH THE SPECIFICATIONS, THE CONTRACTOR SHALL AT HIS OWN EXPENSE, FURNISH FLAGMEN AS NECESSARY TO CONTROL HIS TRAFFIC (UNLESS OTHERWISE DIRECTED BY THE ENGINEER).
CONTRACTOR VEHICLES THAT ARE REQUIRED TO CROSS ACTIVE RUNWAYS, RUNWAY SAFETY AREAS, TAXIWAYS AND APRONS SHALL DO SO UNDER THE DIRECT CONTROL OF A COMPETENT FLAGMAN WHO IS IN DIRECT RADIO CONTACT WITH GROUND CONTROL. ALL AIRCRAFT TRAFFIC ON RUNWAYS, TAXIWAYS, AND APRONS SHALL HAVE PRIORITY OVER CONTRACTOR'S TRAFFIC. AT NO TIME SHALL THE CONTRACTOR'S VEHICLES OR PERSONNEL BE ALLOWED TO ENTER OR OPERATE IN RUNWAY OR CLEAR ZONES WITHOUT PROPER AUTHORIZATION.

- (8) MISCELLANEOUS
(1) OPEN FLAME, WELDING OR TORCH CUTTING OPERATIONS ARE PROHIBITED UNLESS ADEQUATE FIRE-AND SAFETY PRECAUTIONS HAVE BEEN TAKEN AND THE PROCEDURE PREVIOUSLY APPROVED BY THE ENGINEER.
(2) EQUIPMENT AND STOCKPILED MATERIAL SHALL BE CONFINED IN A MANNER TO PREVENT MOVEMENT RESULTING FROM AIRCRAFT JET BLAST OR WIND CONDITIONS IN EXCESS OF 10 KNOTS.
(3) THE CONTRACTOR SHALL PROVIDE BUCKET TYPE CONSTRUCTION BARBICADES WITH FLASHING YELLOW LIGHTS AS SHOWN ON THE DRAWINGS TO DELINEATE THE WORK AREAS WHICH CLOSED TO AIRCRAFT TRAFFIC. OPEN TRENCHES, EXCAVATIONS AND STOCKPILED MATERIAL LOCATED IN THE AOA SHALL BE PROMINENTLY MARKED WITH ORANGE FLARES AND LIGHTED BY APPROVED LIGHT UNITS DURING HOURS OF LIMITED VISIBILITY AND DARKNESS.
(4) ALL MATERIALS AND EQUIPMENT WHEN NOT IN USE SHALL BE PLACED IN APPROVED AREAS WHERE THEY WILL NOT CONSTITUTE A HAZARD TO AIRCRAFT OPERATIONS AND NOT PENETRATE CLEARANCE SURFACES. EQUIPMENT SHALL BE PARKED AT THE STAGING AREA WHEN NOT IN USE.
(5) MAXIMUM EQUIPMENT HEIGHT SHALL NOT EXCEED 15 FEET UNLESS PRIOR APPROVAL IS OBTAINED FROM THE ENGINEER.
(6) UPON COMPLETION OF ANY STAGE/PHASE OF WORK, THE ENGINEER WILL ARRANGE A PHYSICAL INSPECTION OF THE AREA WITH AIRPORT OPERATIONS PERSONNEL PRIOR TO OPENING ANY PORTION OF A RUNWAY, RAMP AREA OR AIRCRAFT ROADWAY THAT HAS BEEN CLOSED FOR WORK OR USED FOR A CROSSING POINT OR HAZARD ROUTE BY THE CONTRACTOR.
(7) ENTRANCE TO THE AIRFIELD IS SUBJECT TO SECURITY REGULATIONS. ALL PERSONNEL ENTERING THE AIRFIELD MUST OBTAIN AND DISPLAY SECURITY IDENTIFICATION BADGES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ASSURING THAT ALL OF HIS EMPLOYEES WHO HAVE UNRESTRICTED ACCESS TO THE AIRFIELD, HAVE HAD A BACKGROUND CHECK PERFORMED ON THEM DATING BACK FIVE (5) YEARS VERIFYING REPRESENTATIONS MADE BY THE EMPLOYEE RELATIVE TO EMPLOYMENT.
(8) THE CONTRACTOR SHALL PROVIDE THE ENGINEER WITH A CURRENT LIST OF ALL EMPLOYEES WORKING ON THE AIRPORT. THE LIST SHALL BE MAINTAINED CURRENTLY BY THE CONTRACTOR AND APPLIED TO ALL SUBCONTRACTORS.
(9) EXCEPT FOR EMERGENCIES, ALL CONTACT WITH AIRPORT PERSONNEL SHALL BE MADE THROUGH THE RESIDENT ENGINEER. FOR EMERGENCIES INVOLVING SAFETY (INJURIES, FIRES, SECURITY BREACHES, ETC.) THE CONTRACTOR SHALL MAKE DIRECT CONTACT WITH AIRPORT OPERATIONS FOLLOWED BY NOTIFICATION TO THE RESIDENT ENGINEER AS SOON AS POSSIBLE.
(10) THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARBICADES.
(11) IN ACCORDANCE WITH THE SPECIFICATIONS, FEDERAL WAGE RATES SHALL BE POSTED OUTSIDE THE SITE FIELD OFFICE IN A WEATHERPROOF ENCLOSURE.
(12) UTILITIES
(1) UNDERGROUND UTILITIES: THE LOCATIONS OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE CONSIDERED TO BE ONLY ESTIMATED LOCATIONS. ALL UTILITY LOCATIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION. IN THE EVENT ANY UTILITY IS DAMAGED THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING FOR INCURRED COSTS OF REPAIRS.
(2) UTILITIES NOTIFICATION: AT LEAST TWO WORKING DAYS PRIOR TO COMMENCING CONSTRUCTION OPERATIONS IN AN AREA WHICH MAY INVOLVE UNDERGROUND UTILITY FACILITIES, THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER, AND THE OWNER OF EACH UNDERGROUND UTILITY WITHIN AFFECTED UTILITIES.
(3) THE FOLLOWING IS A LIST OF COMPANIES' UTILITY FACILITIES WITHIN THE CONSTRUCTION LIMITS.

| | |
|---------|----------------|
| UTILITY | |
| DISSAFE | 1-800-225-4877 |
| CVPS | 1-800-846-2877 |



RUTLAND STATE AIRPORT
CLASHAM, VERMONT





| | | | | |
|------|------|-------------|-----------------|--------------------|
| REV. | DATE | DESCRIPTION | JOB NO. F002229 | JOB No. 1178700000 |
| | | | | |

SAFETY NOTES



URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | | | |
|--------------|-------------|--------|-------|----------------|
| Designed by: | Checked by: | Scale: | Date: | Sheet No. of # |
| | | | | |

Sheet No. **3**



- NOTES:
1. ELBOWS TO BE ALIGNED TO ALLOW STRAIGHT PULL THROUGH BOX PAD OPENING
 2. USE 90° ELBOWS
 3. PROVIDE SUFFICIENT CLEARANCE SO BOX PAD DOES NOT CONTACT ELBOWS
 4. INSTALL PULL WIRE IN CONDUIT (500# MIN RATING)
 5. SEAL CONDUITS WITH APPROVED DUCT SEAL AFTER CABLES INSTALLED
 6. BOND STEEL CONDUIT TO GROUND GRID. SEE DETAIL (I)
 7. PROVIDE DRAINAGE AWAY FROM TRANSFORMER HOUSING
 8. PLACE 3" MIN SAND IN BOTTOM OF TRANSFORMER HOUSING
 9. SEE DETAIL (I) FOR ADDITIONAL DETAIL



- GENERAL NOTES**
1. ALL DISTURBED AREAS TO BE REGRADED, TOPSOILED (3" MIN.) LIMED, FERTILIZED, AND MULCHED.
 2. CRUSHED AGGREGATE TO CONFORM TO VAOT SPECIFICATION 301.25
 3. INSTALLATION OF UNDERGROUND CONDUIT AND COMMUNICATIONS CABLES TO CONFORM TO REQUIREMENTS OF THE LOCAL UTILITY (CVPS) & TELEPHONE Co. (NYNEX).


RUTLAND STATE AIRPORT
CLARENCE, VERMONT

LOCALIZER SITE DETAILS


URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | | | |
|--------------|-------------|-----------|--------|-------|
| Designed by: | Checked by: | Drawn by: | Scale: | Date: |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Sheet No. **5**




J TELEPHONE STUB-UP
SCALE: NONE





NOTE:
PROVIDE LOOPS IN HANDHOLES WHERE NO SPLICES OCCUR. TERMINATE SPARE COAXIAL CABLE IN HANDHOLE WITH 10 FEET OF EXTRA CABLE COILED AND TAPED.

O POWER & COMMUNICATION HANDHOLE DETAIL
SCALE: 1"=1'-0"




1 - 1/2" HELIAX CABLE IN 2" PVC CONDUIT, SCHEDULE 40


P CONDUIT TRENCH FROM DME TO SHELTER
SCALE: NONE




K PULL BOX DETAILS
SCALE: NONE



Q WIRING DIAGRAM
SCALE: NONE



| | |
|--|--|
| RUTLAND STATE AIRPORT CLAREMONT, VERMONT | LOCALIZER SITE DETAILS |
| URS Greiner, Inc. 3 MARCUS BOULEVARD ALBANY, NEW YORK | |
| Prepared by: Date: _____ Drawn by: _____ Checked by: _____ Approved by: _____ | Scale: 1/8" = 1'-0" Date: 04/04/97 Sheet # of # _____ Sheet No. _____ |
| 6 | |



URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

RUTLAND STATE AIRPORT
CLANDRON, VERMONT

LOCALIZER FOUNDATION DETAILS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

JOB NO. 748248 FILE NO. 748248/01

Designed by: DMB
Checked by: JMB
Approved by: [Signature]

Scale: 1" = 1'-0"

Sheet No. 7

- NOTES**
1. ALL CONCRETE TO CONFORM TO NEW ENGLAND CONCRETE CODE, CLASS C, MINIMUM COVER 2" IS REQUIRED.
 2. REINFORCING STEEL TO BE A603, GRADE 60, EPOXY COATED UNLESS OTHERWISE NOTED.
 3. TOLERANCES - ALL DIMENSIONS SHALL BE LOCATED FROM THE FACE OF THE FOUNDATION UNLESS OTHERWISE NOTED.
 4. CONCRETE TO BE PLACED IN 3" TO 4" LAYERS.
 5. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.
 6. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.
 7. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.
 8. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.
 9. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.
 10. ALL REINFORCING STEEL TO BE PLACED IN THE CENTER OF THE CONCRETE UNLESS OTHERWISE NOTED.





| | |
|-------------|-------------|
| PROJECT NO. | DESCRIPTION |
| DATE | DATE |
| JOB NO. | PROVISION |

RUTLAND STATE AIRPORT
CLARION, VERMONT

SEDIMENTATION / EROSION
CONTROL DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|--------------------------|--------------------------|
| Designed By: [Signature] | Checked By: [Signature] |
| Drawn By: [Signature] | Approved By: [Signature] |
| Scales: HOR. = NONE | VERT. = NONE |
| Date: 04/09/97 | Sheet B Of 9 |

SITE DATA


PROJECT DESCRIPTION:
AIRPORT DEVELOPMENT TO INCLUDE EARTHWORK, STORM DRAINAGE, AND UTILITIES.

TOTAL SITE AREA:
AREA WITHIN LIMITS OF WORK APPROXIMATELY 1 ACRE.


EXISTING SOIL TYPES:
- BROWN SILTY SAND WITH TRACES OF GRAVEL.
- APPROXIMATELY 3% OF TOPSOIL.
- INFORMATION OBTAINED FROM BORINGS DRILLED BY GREEN MOUNTAIN BORINGS DURING NOVEMBER 1996.

SCHEDULE:
CONSTRUCTION TO COMMENCE JUNE 1997, AND TO BE COMPLETED AUGUST, 1997, WITH THE IMPLEMENTATION OF EROSION CONTROL MEASURES TO BE THE FIRST PHASE OF ACTIVITY AND TO CONTINUE THROUGHOUT PROGRESS OF PROJECT.


RECEIVING WATERS:
WILL RIVER, OTTERCREEK.




SEDIMENTATION CONTROL
CONSTRUCTION ENTRANCE



SEDIMENTATION BARRIER - SILT FENCE



SEDIMENTATION BARRIER - HAYBALE




EROSION AND SEDIMENT CONTROL NOTES


- THE CONTRACTOR SHALL CONSTRUCT ALL EROSION AND SEDIMENT CONTROL MEASURES PER THE APPROVED PLAN AND SHALL HAVE THEM INSPECTED BY THE ENGINEER PRIOR TO BEGINNING ANY OTHER LAND DISTURBANCE. WHEN SEDIMENT CONTROL DEVICE ADJUSTMENTS MAY BE MADE IN THE FIELD WITH THE APPROVAL OF THE ENGINEER, THE CONTRACTOR SHALL ENSURE THAT ALL RUNOFF FROM DISTURBED AREAS IS DIRECTED TO THE SEDIMENT CONTROL DEVICES, AND SHALL NOT REMOVE THEM PRIOR TO APPROVAL BY THE ENGINEER. THE CONTRACTOR MUST OBTAIN PRIOR APPROVAL FOR CHANGES TO THE SEDIMENT CONTROL PLAN AND/OR SEQUENCE OF CONSTRUCTION.
- THE CONTRACTOR SHALL MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES UNTIL SUCH TIME AS THEY ARE REMOVED.
- THE CONTRACTOR SHALL APPLY SEED AND MULCH, OR OTHER APPROVED STABILIZATION MEASURES TO ALL DISTURBED AREAS AND STOCKPILES WITHIN FOURTEEN (14) CALENDAR DAYS AFTER STRIPPING AND GRADING ACTIVITIES HAVE CEASED IN THE AREA. MAINTENANCE SHALL BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION. PERMANENT SOIL STABILIZATION SHALL BE PROVIDED WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS ESTABLISHED.
- THIS EROSION CONTROL PLAN SHALL BE IMPLEMENTED ON ALL DISTURBED AREAS WITHIN THE CONSTRUCTION SITE. ALL MEASURES INVOLVING SOIL OR ENVIRONMENT HAZARDOUS FOR SOIL EROSION AND SEDIMENT CONTROL ON CONSTRUCTION SITES AS PUBLISHED BY THE GEOLOGICAL SURVEY.
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE REMOVED AND DIVULGED OF WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY PRACTICES ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE STABILIZED OR REDDED TO PREVENT FURTHER EROSION.
- EROSION CONTROL DEVICES REMOVED DURING GRADING OPERATIONS SHALL BE PUT BACK IN PLACE AT THE END OF THE DAY OR DURING INCLEMENT WEATHER AS DIRECTED BY THE ENGINEER.
- NO SOIL, ROCK, DEBRIS, OR ANY OTHER MATERIAL SHALL BE DUMPED OR PLACED INTO A WATER RESOURCE OR INTO SUCH PROXIMITY THAT IT MAY READILY BLOW, SOIL, OR CODE INTO A WATER RESOURCE UNLESS SUCH DUMPING OR PLACING IS AUTHORIZED BY THE ENGINEER AND APPROVED BY LOCAL, THE U.S. ARMY CORPS OF ENGINEERS, FOR SUCH PURPOSES AS, BUT NOT LIMITED TO, CONSTRUCTION OF BRIDGES, CULVERTS, AND EROSION CONTROL STRUCTURES.
- PERMANENT SEEDING SHALL BE DONE BETWEEN APRIL 30 AND SEPTEMBER 15. IF SEEDING IS DONE AT OTHER TIMES, IT SHALL BE CLASSIFIED AS TEMPORARY SEEDING. PERMANENT SEED SHALL CONFORM TO THE SEEDING MIXTURE STANDARDS IN THE SPECIFICATIONS. TEMPORARY AND PERMANENT SEEDING SHALL CONSIST OF FERTILIZING, WATERING AND SEEDING PLACED AT WATER IN ACCORDANCE WITH THE SPECIFICATIONS. PERMANENT SEEDING AND MULCHING SHALL BE PAID FOR UNDER 881.15 AND 881.16, RESPECTIVELY. TEMPORARY SEED, MULCH, AND FERTILIZER FOR EROSION AND SEDIMENT CONTROL SHALL BE PLACED IN ACCORDANCE WITH THE SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR TEMPORARY SEEDING OR MULCHING.
- SURFACE DRAINAGE FLOW OVER UNSTABILIZED CUT AND FILL SLOPES SHALL BE CONTROLLED BY EITHER PREVENTING DRAINAGE FLOW, TRAPPING AND DIVULGING AT THE TOP OF CUT OR FILL SLOPE OR LOWER THE WATER TABLE WITHOUT CAUSING EROSION. DICES SHALL BE INSTALLED AND MAINTAINED AT THE TOP OF CUT OR FILL SLOPE UNTIL THE SLOPE AND DRAINAGE AREA TO IT ARE FULLY STABILIZED. AT WHICH TIME, THEY MUST BE REMOVED AND FINAL GRADING DONE TO PROMPT SLOPE FLOW DRAINAGE. PROTECTIVE METHODS MUST BE PROVIDED AT POINTS OF CONCENTRATED FLOW WHERE EROSION IS LIKELY TO OCCUR.
- ALL POINTS OF CONSTRUCTION INGRESS AND EGRESS IN UNPAVED AREAS SHALL BE STABILIZED AND PROTECTED TO PREVENT TRACKING OF MUD ONTO PUBLIC OR PRIVATE ROADSWAYS.
- IF PUBLIC OR PRIVATE ROADSWAYS DO ACCUMULATE DEBRIS, THE CONTRACTOR SHALL USE A POWER BROOM TO REMOVE THE SEDIMENT TO THE SATISFACTION OF THE ENGINEER.
- SALVAGED TOPSOIL WILL BE PLACED ON WELL DRAINING LAND AWAY FROM STREAMS IN ACCORDANCE WITH APPROVED EROSION AND SEDIMENT CONTROL MEASURES. IT SHALL BE PLACED IN HEAVY TIE. THE CONTRACTOR WILL PROVIDE AN ADEQUATE QUANTITY OF SILT FENCE TO CONTROL THE PERIMETER OF THE STOCKPILE. THE CONTRACTOR, WITH THE APPROVAL OF THE ENGINEER, MAY CONSTRUCT AN EARTH DIKE IN LIEU OF SILT FENCE.
- ALL DISTURBED AREAS SHALL BE COVERED WITH 3 INCHES OF TOPSOIL, FERTILIZER, LIME, PERMANENT SEEDING AND MULCH SHALL BE APPLIED AT THE FOLLOWING RATES:

| | | |
|------------|----------|--------------|
| FERTILIZER | 10-20-10 | 500 LBS/ACRE |
| LIME | | 2 TONS/ACRE |
| SEED | | 2 TONS/ACRE |
| MULCH | | 2 TONS/ACRE |


| | | |
|------------|----------|--------------|
| TOPSOIL | 3 INCHES | 20 LBS/ACRE |
| FERTILIZER | 10-20-10 | 500 LBS/ACRE |
| LIME | | 2 TONS/ACRE |
| SEED | | 2 TONS/ACRE |
| MULCH | | 2 TONS/ACRE |



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN



NOTE:

- BORINGS AND DRIVE TESTS WERE TAKEN IN NOVEMBER 1995, BY GREEN MOUNTAIN BORING.
 - N - BLOWS PER 8 INCH INCREMENT OF PENETRATION OF SAMPLING SPOON OR PENETRATION IN INCHES FOR THE INDICATED BLOWS OF A 140 LB. HAMMER FALLING 30". WHERE ROCK IS ENCOUNTERED, PERCENT CORE RECOVERY IS SHOWN. R.Q.D. IS SHOWN IN PARENTHESES.
- THE ROCK QUALITY DESIGNATION (R.Q.D.) IS BASED ON A MODIFIED CORE RECOVERY PROCEDURE WHICH, IN TURN, IS BASED INDIRECTLY ON THE NUMBER OF FRACTURES (EXCEPT THOSE DUE DIRECTLY TO DRILLING OPERATIONS) AND THE AMOUNT OF SOFTENING OR ALTERATION IN THE ROCK MASS AS OBSERVED IN THE ROCK CORES FROM A DRILL HOLE. INSTEAD OF COUNTING THE FRACTURES, AN INDIRECT MEASURE IS OBTAINED BY SUMMING THE TOTAL LENGTH OF CORE RECOVERED BY COUNTING ONLY THOSE PIECES OF HARD AND SOUND CORE WHICH ARE 4 INCHES OR GREATER IN LENGTH. THE RATIO OF THIS MODIFIED CORE RECOVERY LENGTH TO THE TOTAL CORE RUN LENGTH IS KNOWN AS THE R.Q.D.
- V - ALTERNATE SHADING INDICATES EXTENT OF SOIL OR ROCK LAYERS.
- WL - WATER LEVEL READING AT COMPLETION OF BORING.



| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |

Job No. _____
 File No. (if different) _____

RUTLAND STATE AIRPORT
CLARENDON, VERMONT

BORING LOGS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | |
|--------------------------|----------------|
| Checked by: [Signature] | Date: 01/26/97 |
| Drawn by: [Signature] | Date: 01/26/97 |
| Checked by: [Signature] | Date: 01/26/97 |
| Approved by: [Signature] | Date: 01/26/97 |

Scale: HOR - AS SHOWN
VERT - NONE

Date: 01/26/97


Sheet # of #

Sheet No. 9




- NOTES:
1. PROVIDE 3 FEET OF SLACK IN CABLES AT TRANSFORMER.
 2. SEAL END OF CONDUIT (DUST SEAL).
 3. PROVIDE 1/2" PER FT. PITCH ON ALL CONDUITS.

BASE MOUNTED UNIT
ELEVATED LIGHT
NO SCALE



- NOTES:
1. PROVIDE 3 FEET OF SLACK IN CABLES AT TRANSFORMER.
 2. 30" METAL STAKE SHALL BE MADE OF GALVANIZED STEEL ANGLE 2" x 2" x 3/16" WITH A SUITABLE TAPPED FITTING BOLTED AT THE TOP TO RECEIVE THE FRANGIBLE COUPLING.

STAKE MOUNTED UNIT
ELEVATED LIGHT
NO SCALE




NOTE 1: FOR ALL OTHER DETAILS, SEE BASE MOUNTED UNIT FOR ELEVATED LIGHT.
BASE MOUNTED UNIT
SEMI-FLUSH LIGHT
NO SCALE

| LIGHT LOCATION | LAMP | | LENS |
|---------------------------|------------------|----------------|--------------------------|
| | MEDIUM INTENSITY | HIGH INTENSITY | |
| RUNWAY EDGE LIGHT | 6.6A, 30W | 6.6A, 150W | 360° CLEAR/180° YELLOW |
| RUNWAY THRESHOLD LIGHT | 6.6A, 45W | 6.6A, 150W | 180° RED/180° GREEN |
| DISPLACED THRESHOLD LIGHT | 6.6A, 30/45W | 6.6A, 150W | 360° RED |
| | | 6.6A, 150W | 180° RED/180° CLEAR |
| TAXIWAY LIGHT | 6.6A, 30W | 6.6A, 150W | 180° OBSCURED/180° GREEN |
| | | 6.6A, 150W | 180° CLEAR/180° GREEN |
| | | | 360° BLUE |


NOTES: 1. SEE PLAN SHEET FOR LENS/LIGHT TYPE.

NOTE 1: AIRPORT LIGHT BASES SHOULD BE CONSTRUCTED TO FAA SPECIFICATIONS, SEE CURRENT ADVISORY CIRCULAR.




NOTES:
HAND LETTERING NOT ALLOWED ON CABLE OR SPLICE MARKERS. LETTERING WILL BE EMBOSSED (V-CUT 1/2" DEEP).

NOTE 1: SEE STANDARD AP-3 FOR UNDERGROUND ELECTRICAL DUCT DETAILS.



ELEVATION VIEW (TYPICAL FOR CABLE AND SPLICE MARKERS)
CABLE AND SPLICE MARKERS
NO SCALE



NOTE 1: FOR MULTIPLE-CABLE INSTALLATIONS, PROVIDE 3" ADDITIONAL TRENCH WIDTH FOR EACH ADDITIONAL CABLE.

NOTE 1: UNDERGROUND ELECTRICAL CABLE SHOULD BE CONSTRUCTED TO FAA SPECIFICATION, SEE CURRENT ADVISORY CIRCULAR.

UNDERGROUND ELECTRICAL CABLE INSTALLATION TRENCH DETAILS
(IN EARTH OR ROCK)
NO SCALE

REVISIONS AND CORRECTIONS

DEC. 15, 1981 - ORIGINAL APPROVAL DATE
MAR. 1, 1990 - SHEET UPDATED
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.

APPROVED

APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION. FINAL APPROVAL PENDING.

DIRECTOR OF RAILROAD AND PUBLIC TRANSIT


LIGHTING & ELECTRICAL DETAILS




STANDARD
AP-2

NOTES


1. THE LOCATION OF THE PORTABLE MARKER UNIT SHALL BE AS ORDERED BY THE ENGINEER.
2. DIRECTIONAL ARMS ARE INSTALLED ONLY ON AIRPORTS WITH A NON-STANDARD TRAFFIC PATTERN (RIGHT-HAND PATTERN). WHEN INSTALLED, DIRECTIONAL ARMS WILL BE MAGNETICALLY ORIENTED TO THE RUNWAY AND WILL SHOW TRAFFIC PATTERN ON EACH RUNWAY.



SEGMENTED CIRCLE LAYOUT WITH DIRECTIONAL ARMS




LEG DETAIL FOR PORTABLE MARKER UNIT
DETAIL 'A'



SEGMENTED CIRCLE MARKER UNIT


MARKER UNIT - STANDARD 55 GALLON METAL DRUM, CUT IN HALF AND WELDED END TO END. MARKER UNITS TO BE PAINTED AVIATION ORANGE.

PORTABLE UNIT HAS LEGS OF 2" Ø GALVANIZED PIPE. STATIONARY UNITS HAVE LEGS OF 2" Ø GALVANIZED PIPE OR 1 1/2" x 3/4" L (CALV.).




ALL DUCTS, EXCEPT STEEL CONDUIT, INSTALLED UNDER RUNWAYS, TAXIWAYS, APRONS, AND OTHER PAVED AREAS SHALL BE ENCASED IN A CONCRETE ENVELOPE.


SEE STANDARD AP-2 FOR DIRECT BURIAL CABLE DETAILS.



AIRCRAFT TIE DOWN ANCHOR




AIRPORT UNDERGROUND ELECTRICAL DUCT (IN EARTH)



DUCT MARKERS

- NOTES**
1. LETTERING ON DUCT MARKERS TO BE EMBOSSED, 1/2" CUT, 1/2" DEEP.
 2. HAND LETTERING NOT ALLOWED



AIRPORT UNDERGROUND ELECTRICAL DUCT (IN ROCK)

REVISIONS AND CORRECTIONS
DEC. 15, 1981 - ORIGINAL APPROVAL DATE
MAR. 5, 1990 - SHEET UPDATED
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.




APPROVED
[Signature]
DIRECTOR OF RAILROAD AND PUBLIC TRANSIT

APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION
FEMA FINAL APPROVAL PENDING.

MISCELLANEOUS AIRPORT DETAILS




STANDARD
AP-3



NOTES

1. FOUR ARROWHEADS ARE PLACED SYMMETRICALLY ACROSS RUNWAY WITH UNIFORM LATERAL SPACING AS INDICATED.
2. ALL MARKINGS IN THE DISPLACED AREA ARE YELLOW EXCEPT THE THRESHOLD BAR WHICH IS WHITE.
3. RUNWAY SIDE STRIPES, WHEN USED ON THE RUNWAY, EXTEND INTO THE DISPLACED AREA.





NOTES

1. ALL LETTERS AND NUMERALS, EXCEPT THE NUMBER ELEVEN AS SHOWN, ARE HORIZONTALLY SPACED 15 FEET APART.
2. DIMENSIONS ARE EXPRESSED IN FEET.
3. THE NUMERAL ONE, WHEN USED ALONE, CONTAINS A HORIZONTAL BAR TO DIFFERENTIATE IT FROM THE RUNWAY CENTERLINE MARKING.

GENERAL NOTES

1. ALL RUNWAY MARKINGS ARE WHITE EXCEPT IN THE DISPLACED THRESHOLD AREA AND NON FULL STRENGTH SHOULDER MARKINGS.
2. FOR RUNWAYS LESS THAN 150' IN WIDTH, THE WIDTH OF THE MARKINGS, SPACES BETWEEN MARKINGS, AND DISTANCE OF MARKINGS FROM THE RUNWAY EDGE ARE CHANGED PROPORTIONALLY.
3. ADJUSTMENTS TO THE LENGTH OF THE CENTERLINE STRIPES AND GAPS, WHERE NECESSARY TO ACCOMMODATE THE RUNWAY LENGTH, ARE MADE NEAR THE RUNWAY MIDPOINT.
4. ALL RUNWAY MARKINGS ARE TO BE STRIATED WITH ALL STRIPES AND SPACES EQUAL IN WIDTH (4" TO 6").

NOTE:
MARKING OF RUNWAY SHOULD BE BASED ON FAA SPECIFICATIONS. SEE CURRENT FAA ADVISORY CIRCULAR.



- TEMPORARY CLOSED RUNWAY MARKER NOTES:**
1. MARKERS TO BE YELLOW PLYWOOD OR SNOW FENCE.
 2. MARKERS TO BE SUBSIDIARY TO OTHER PAVEMENT ITEMS.
 3. MARKERS TO BE PLACED OVER RUNWAY NUMERALS OR OFF THE RUNWAY ENDS AS APPLICABLE.
 4. MARKERS TO BE ANCHORED TO THE SATISFACTION OF THE ENGINEER.

REVISIONS AND CORRECTIONS
JUNE 29, 1982 - ORIGINAL APPROVAL DATE
MAR. 5, 1990 - SHEET UPDATED
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURE.

APPROVED
APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION (THIS FINAL APPROVAL PENDING).
[Signature]
DIRECTOR OF RAIL, AIR AND PUBLIC TRANSIT

RUNWAY MARKING DETAILS



**STANDARD
AP-10**

STATE OF VERMONT
AGENCY OF TRANSPORTATION



PROPOSED IMPROVEMENTS
RUTLAND STATE AIRPORT
CLARENDON, VERMONT
AIP NO. 3-50-0015-11
E.A. 043111


TO INCLUDE: REHABILITATE, LIGHT & MARK RUNWAY 1-19 (100'x5000') &
RELOCATE LOCALIZER AND SHELTER

INDEX OF SHEETS

- 1 TITLE SHEET
- 2 QUANTITY SUMMARY
- 3A&3B DRAINAGE SUMMARY
- 4 GENERAL PROJECT LAYOUT
- 5 GENERAL CONSTRUCTION AND SAFETY NOTES
- 6 PHASING PLAN, NOTES
- 7-9 TYPICAL SECTIONS AND DETAILS
- 10-12 RUNWAY 1-19 PROFILE
- 13 TAXIWAY C,D,E & RUNWAY 13-13 PROFILE
- 14-18 PAVING PLANS AND GEOMETRIC LAYOUT
- 19-23 GRADING & DRAINAGE PLANS
- 24 DRAINAGE DETAILS
- 25 EROSION CONTROL DETAILS
- 26 PAVEMENT MARKING PLAN
- 27-30 RUNWAY LIGHTING PLANS
- 31-33 RUNWAY LIGHTING DETAILS
- 34 VASI MOUNTING DETAILS
- 35-41 ODALS DETAILS
- 42-44 BORING LOGS
- 45 LOCALIZER/DME BUILDING RELOCATION
- 46-57 RUNWAY 1-19 CROSS SECTIONS
- 58-59 TAXIWAY D X-SECTIONS
- 60-65 LOCALIZER REFERENCE DRAWINGS


VAOT STANDARD DRAWINGS

- AP-3 DUCT AND DUCT MARKER DETAILS
- AP-10 RUNWAY MARKING DETAILS
- AP-11 TAXIWAY MARKING DETAILS
- B-5 EMBANKMENTS ON EARTH SLOPE
- D-2 REINFORCED CONCRETE HEADWALL
- D-6 REINFORCED CONCRETE DROP INLET W/ GRATE
- D-11 CAST IRON GRATE-TYPE A
- D-16 ENERGY DISSIPATOR FOR CULVERTS
- E-100 CONSTRUCTION APPROACH SIGNS
- E-121 STANDARD SIGN PLACEMENT



LOCATION MAP

APPROXIMATE SCALE : 1" = 1 MILE



JUL 01 1997
 Date: _____
 J. P. McDonald, Inc. _____
 Contractor
 James McDonald _____
 Signature
 J. P. McDonald _____
 1997
 J. P. McDonald _____
 Secretary of Transportation's Signature

A.A.I.A. OF 1982 SECTION 509(d) ASSURANCES
 IN COMPLIANCE WITH THE AIRPORT AND AIRWAYS IMPROVEMENT ACT OF 1982, SECTION 509 (d) AND THE SPONSOR'S CERTIFICATION, DATED _____, THESE PLANS AND SPECIFICATIONS HAVE BEEN PREPARED IN ACCORDANCE WITH CURRENT FAA STANDARDS IDENTIFIED IN F.A.R. PART 152. ANY DEVIATION FROM THE FAA STANDARD WERE APPROVED IN A LETTER BY THE FAA, DATED _____ AND ARE DISCUSSED IN THE ENGINEERING REPORT ACCOMPANYING THESE PLANS.
 _____ 5/5/97
 DESIGN ENGINEER DATE

URS Greiner, Inc.
 STATE OF VERMONT
 APPROVED: _____ DATE: 5-18-97
 DIRECTOR OF HIGHWAY & PUBLIC TRANSPORTATION
 DEPARTMENT OF TRANSPORTATION
 FEDERAL AVIATION ADMINISTRATION
 APPROVED: _____ DATE: _____
 CHIEF, AIRPORT DIVISION

QUANTITY SHEET

| SUMMARY OF ESTIMATED QUANTITIES | | | | |
|---------------------------------|------|--|---------------|----------|
| QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | ROUNDING |
| 12 | EA | CLEARING - LARGE TREES | 201.16 | |
| 112,000 | CY | COMMON EXCAVATION | 203.15 | |
| 250 | CY | SOLID ROCK EXCAVATION | 203.16 | |
| 23,000 | CY | GRANULAR BORROW | 203.32 | |
| 23,000 | SY | FINE GRADE | 203.40 | |
| 7,000 | CY | TRENCH EXCAVATION OF EARTH | 204.20 | |
| 100 | CY | TRENCH EXCAVATION OF ROCK | 204.21 | |
| 4,000 | SY | COLD PLANING | 210.10 | |
| 350 | CY | SUBBASE OF GRAVEL, COURSE GRADED | 301.25 | |
| 70 | CY | SUBBASE OF GRAVEL, FINE GRADED | 301.26 | |
| 180 | TON | BITUMINOUS CONCRETE PAVEMENT | 408.25 | |
| 13,000 | TON | BIT. CONCRETE PAVEMENT (P-401) (PG 58-34) | 408.25 MOD. 1 | |
| 500 | LF | JOINT SEALER, HOT POURED | 524.11 | |
| 8,500 | LF | CRACK REPAIR, TYPE I (P605) | 524.11 MOD. 1 | |
| 7,000 | LF | CRACK REPAIR, TYPE II (P605) | 524.11 MOD. 2 | |
| 2,000 | LF | CRACK REPAIR, TYPE III (P605) | 524.11 MOD. 3 | |
| 1 | EA | RELOCATE LOCALIZER | 528.20 MOD. 1 | |
| 1,300 | LF | 15" CSP, 0.079" | 601.0011 | |
| 675 | LF | 15" RCP, CLASS IV | 601.0B11 | |
| 5 | EA | 15" CSP, END SECTION | 601.6010 | |
| 1 | EA | 15" RCP, END SECTION | 601.6B10 | |
| 9 | EA | CONCRETE D/CB W/ CAST IRON FRAME & GRATE | 604.10 | |
| 10 | EA | CHANGE ELEVATION OF D.I./C.B. | 604.40 | |
| 9,200 | LF | 6" UNDERDRAIN | 605.10 | |
| 500 | LF | 6" UNDERDRAIN CARRIER PIPE | 605.20 | |
| 38 | EA | UNDERDRAIN FLUSHING BASINS | 605.95 | |
| 24 | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I | 606.25 | |
| 100 | MGal | DUST CONTROL WITH WATER | 609.10 | |
| 40 | CY | STONE FILL, TYPE II | 613.11 | |
| 1,150 | LF | 3" PVC SEWER PIPE | 628.35 | |
| 1 | LS | TRANSFER TO NEW SYSTEM - SANTARY SEWER | 628.42 | |
| 1 | LS | FIELD OFFICE - ENGINEERS | 631.10 | |
| 1 | LS | MOBILIZATION | 635.10 | |
| 58,000 | LF | 6" WHITE LINE (P620) | 646.20 MOD. 1 | |
| 3,600 | LF | 6" YELLOW LINE (P620) | 646.21 MOD. 1 | |
| 2 | EA | SYMBOL (1) (P620) | 646.30 MOD. 1 | |
| 1 | EA | SYMBOL (9) (P620) | 646.30 MOD. 2 | |
| 24,000 | LF | 6" TEMPORARY WHITE LINE (P620) | 646.60 MOD. 1 | |
| 3,000 | LF | 6" TEMPORARY YELLOW LINE (P620) | 646.61 MOD. 1 | |
| 4 | EA | TEMPORARY SYMBOL (1) (P620) | 646.70 MOD. 1 | |
| 2 | EA | TEMPORARY SYMBOL (9) (P620) | 646.70 MOD. 2 | |
| 2,000 | SF | REMOVAL OF EXIST. PAV'T MARKING (P621) | 646.82 | |
| 20,000 | SY | GEOTEXTILE FOR ROADBED SEPARATOR | 649.11 | |
| 10,000 | SY | GEOTEXTILE FOR UNDERDRAIN TRENCH | 649.41 | |
| 600 | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | |
| 2,800 | LB | SEED | 651.15 | |
| 24,000 | LB | FERTILIZER | 651.18 | |
| 95 | TON | AGRICULTURAL LIMESTONE | 651.20 | |
| 500 | EA | HAY BALES FOR EROSION CONTROL | 651.26 | |
| 95 | TON | MULCH | 651.25 | |
| 12,800 | CY | TOPSOIL (2") | 651.35 | |
| 500 | SY | EROSION MATTING | 654.10 | |
| 1 | EA | RELOCATE ODALS #1R & #1L (L-125) | 678.16 MOD. 1 | |
| 1 | EA | RELOCATE ODALS UNIT #3 (L-102) | 678.17 MOD. 1 | |
| 1 | EA | RELOCATE ODALS UNIT #20 (L-102) | 678.17 MOD. 2 | |
| 23,500 | LF | 2" DIA. PVC ELECTRICAL CONDUIT (L-110) | 678.21 MOD. 1 | |
| 1 | EA | TOWER FOR ODALS UNIT #3 (L-103) | 679.45 MOD. 1 | |
| 1 | EA | TOWER FOR ODALS UNIT #20 (L-103) | 679.45 MOD. 2 | |
| 6,100 | CY | CRUSHED AGGREGATE BASE COURSE (P-209) | 854.04 | |
| 16,000 | LF | CABLE TRENCH (L-108) | 864.04 | |
| 29,000 | LF | 1/2" #8, 500 OR 5000V, L-824C (L-108) | 864.05 | |
| 7,000 | LF | 1/2" #4, 500V, L-824C (L-108) | 864.41 | |
| 2,500 | LF | 6 PAIR #19 CONTROL CABLE (L-108) | 864.05 MOD. 2 | |
| 18,500 | LF | #8 OR #6 COUNTERPOISE (L-108) | 864.05 MOD. 3 | |
| 1 | LS | INSTALLATION OF VAULT EQUIPMENT (L-109) | 864.06 MOD. 1 | |
| 180 | LF | 4 WAY x 4" DIA. UG ELECTRICAL DUCT (L-110) | 864.07 | |
| 69 | EA | MIRLS, BASE MOUNTED (L-125) | 864.09 | |
| 3 | EA | MIRLS, BASE MOUNTED, IN PAV'T (L-125) | 864.10 | |
| 13 | EA | MIRLS, BASE MOUNTED (L-125) | 864.11 | |
| 1 | EA | RELOCATE VAS-4 (L-125) | 864.12 MOD. 1 | |
| 1 | EA | TEMPORARY THRESHOLD (L-125 & P-620) | 864.15 MOD. 1 | |
| 20 | EA | RELOCATE AIRFIELD SIGNS (L-125) | 864.14 MOD. 1 | |
| 1 | LS | TESTING EQUIPMENT - CONCRETE | 631.16 | |
| 1 | LS | TESTING EQUIPMENT - BITUMINOUS | 631.17 | |
| 1 | LS | FIELD OFFICE - TELEPHONE (N.A.B.C.) | 631.25 | |

| EARTH WORK SUMMARY | | | |
|-----------------------|---------------------|---------------------|---------------------|
| LOCATION | TOTAL EXCAVATION | TOTAL EMBANKMENT | |
| TAXIWAY "D" | 3,950 cy | 5,572 cy | |
| RUNWAY 1-19 | | | |
| -STA. 96+50 - 111+50 | 18,736 | | |
| -STA. 111+50 - 157+40 | 183,551 | 87,265 | |
| SUBTOTALS | 106,237 | 92,637 | |
| RNDG. (4%) | 5,763 | 13,762 | FACTORED FILL (15%) |
| TOTALS | 112,000 | 106,762 | |
| | cy | cy | |



Job No. 1742119-23
 DESCRIPTION
 REV. DATE
 Job No. 1742119-23

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
QUANTITY SUMMARY

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

Designed by: JWB
 Checked by: JWB
 Drawn by: JWB
 Date: 3/2/97
 Approved by: JWB
 Date: 3/2/97

Scale: HOR. = NONE
 VERT. = NONE

Date: 6/4/97


Sheet 2 Of 93

Sheet No. **2**

DRAINAGE QUANTITY SHEET

| SECTION | STRUCTURE | LOCATION | DRAINAGE STRUCTURES | | PER FOOT | | TOTAL | | CONCRETE | | STEEL | | QUANTITIES | |
|---------|-----------|----------|---------------------|---------|----------|----------|----------|----------|----------|----------|----------|----------|------------|----------|
| | | | TYPE | REMARKS | PER FOOT | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC | FOOT/SEC |
| 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 | 101 |

AIP 2-55-0015-11

| | | | |
|--|--|---|---|
| Designed by: E. STAMBO 2/67 Checked by: W. WICKALL 3/67 Approved by: J. CAMPBELL 5/67 | URS Greiner, Inc. 3 MARCUS BOULEVARD ALBANY, NEW YORK | RUTLAND STATE AIRPORT CLARENDON, VERMONT DRAINAGE SUMMARY |  NY DATE DESCRIPTION Job No. 46222.00 File No. 1-Vermont |
|--|--|---|---|

DRAINAGE QUANTITY SHEET

| CULVERTS AND STORM DRAINS | | | | | | |
|---------------------------|----------------|-------------|--------|-----------|----------------------|----------|
| LOCATION | | SIZE & TYPE | LENGTH | FLOW LINE | TRENCH EXCAVATION CY | REMARKS |
| BEGIN | END | | | INLET | OUTLET | |
| D1 100 | 300' LT 116+55 | 15" CSP | 100' | 778.00 | 777.50 | 45 |
| D1 101 | 430' LT 100+80 | 15" RSP | 230' | 777.04 | 784.20 | 100 |
| D1 102 | D1 103 | 15" CSP | 225' | 777.80 | 775.90 | 140 |
| D1 103 | CB 104 | 15" RCP | 295' | 775.80 | 774.00 | 220 |
| D1 105 | 150' RT 155+93 | 15" CSP | 90' | 755.80 | 728.0 | 35 |
| D1 106 | 168' LT 155+93 | 15" CSP | 80' | 775.80 | 738.0 | 45 |
| CB 107 | CB 108 | 15" CSP | 340' | 778.0 | 774.6 | 230 |
| CB 108 | CB 109 | 15" CSP | 335' | 774.55 | 771.80 | 225 |
| 202' LT 121+40 | 202' LT 121+88 | 15" CSP | 48' | 782.34 | 782.28 | N.A. |
| | | | | | 1040 cy | SUBTOTAL |

| UNDERDRAIN | | | | | | |
|------------|----------------|-------------|--------|-----------|----------------------|---|
| LOCATION | | SIZE & TYPE | LENGTH | FLOW LINE | TRENCH EXCAVATION CY | REMARKS |
| | | | | INLET | OUTLET | |
| M32 | 78' RT 100+72 | 6" UD | 220 LF | | 774.7 | |
| FB1 | 55' RT 102+80 | 6" UD | 220 LF | 776.02 | | 163 |
| FB2 | 55' RT 105+30 | 6" UD | 250 LF | 776.84 | | 185 |
| FB3 | 55' RT 107+80 | 6" UD | 250 LF | 777.23 | | 185 |
| FB4 | 55' RT 108+55 | 6" UD | 175 LF | 777.94 | | 130 |
| FB5 | 55' RT 112+88 | 6" UD | 170 LF | 778.68 | | 126 |
| FB6 | 55' RT 114+80 | 6" UD | 250 LF | 779.12 | | 185 |
| FB7 | 55' RT 117+10 | 6" UD | 250 LF | 779.34 | | 185 |
| FB8 | 55' RT 119+80 | 6" UD | 250 LF | 780.08 | | 185 |
| FB9 | 55' RT 121+00 | 6" UD | 360 LF | 781.34 | | 266 |
| FB10 | 55' RT 124+80 | 6" UD | 250 LF | 780.67 | | 50 |
| FB11 | 55' RT 127+10 | 6" UD | 250 LF | 780.24 | | 50 |
| FB12 | 55' RT 128+80 | 6" UD | 250 LF | 779.80 | | 50 |
| FB13 | 55' RT 132+10 | 6" UD | 250 LF | 778.64 | | 50 |
| FB14 | 55' RT 134+80 | 6" UD | 250 LF | 777.43 | | 50 |
| FB15 | 55' RT 137+10 | 6" UD | 250 LF | 778.21 | | 50 |
| FB16 | 55' RT 139+80 | 6" UD | 250 LF | 774.98 | | 50 |
| FB17 | 55' RT 142+10 | 6" UD | 250 LF | 773.77 | | 185 |
| FB18 | 55' RT 144+80 | 6" UD | 250 LF | 772.50 | | 185 |
| FB19 | 55' RT 147+10 | 6" UD | 175 LF | 771.20 | | 130 |
| M788 | 81' RT 148+75 | | | 770.20 | | |
| | 140' RT 150+00 | | | 771.3 | | |
| | | | | | 2275 cy | CONNECT TO EXISTING PVC UNDERDRAIN SUBTOTAL |

| LOCATION | SIZE & TYPE | LENGTH | FLOW LINE | | TRENCH EXCAVATION CY | REMARKS |
|----------|----------------|------------|-----------|--------|----------------------|--|
| | | | INLET | OUTLET | | |
| | 150' RT 151+80 | 150 LF | | 757.50 | 104 | |
| | | | | 774.70 | | OUTLET TO DAYLIGHT, STONE FILL, TYPE II OUTLET |
| M33 | 79' LT 100+74 | 6" UD | 220 LF | | 163 | |
| FB20 | 55' LT 102+80 | 6" UD | 250 LF | 776.02 | | 185 |
| FB21 | 55' LT 105+30 | 6" UD | 250 LF | 776.84 | | 185 |
| FB22 | 55' LT 107+80 | 6" UD | 240 LF | 777.23 | | 177 |
| FB23 | 55' LT 110+20 | 6" UD | 184 LF | 778.09 | | 144 |
| FB24 | 55' LY 112+88 | 6" UD | 250 LF | 779.10 | | 185 |
| FB25 | 55' LY 114+80 | 6" UD | 250 LF | 779.34 | | 185 |
| FB26 | 55' LY 117+10 | 6" UD | 250 LF | 780.06 | | 185 |
| FB27 | 55' LY 119+80 | 6" UD | 250 LF | 780.55 | | 185 |
| FB28 | 55' LY 122+10 | 6" UD | 250 LF | 780.86 | | 50 |
| FB29 | 55' LY 124+80 | 6" UD | 250 LF | 780.63 | | 50 |
| FB30 | 55' LY 127+10 | 6" UD | 250 LF | 779.81 | | 50 |
| FB31 | 55' LY 128+80 | 6" UD | 250 LF | 778.64 | | 50 |
| FB32 | 55' LY 132+10 | 6" UD | 250 LF | 777.43 | | 50 |
| FB33 | 55' LY 134+80 | 6" UD | 250 LF | 778.21 | | 50 |
| FB34 | 55' LY 137+10 | 6" UD | 250 LF | 774.98 | | 50 |
| FB35 | 55' LY 139+80 | 6" UD | 250 LF | 773.77 | | 185 |
| FB36 | 55' LY 142+10 | 6" UD | 250 LF | 772.50 | | 185 |
| FB37 | 55' LY 144+80 | 6" UD | 250 LF | 771.20 | | 208 |
| FB38 | 55' LY 147+10 | 6" UD | 281 LF | 789.50 | | |
| M73 | 78' LY 148+91 | | | | | |
| FB25 | 55' LT 114+80 | 6" CARRIER | 240 LF | 779.00 | 112 | |
| D1 100 | 202' LT 116+50 | | | 778.00 | | |
| FB5 | 55' RT 112+88 | 6" CARRIER | 158 LF | | 115 | |
| D1 102 | 202' LT 113+48 | | | 778.0 | | 2853 cy SUBTOTAL |
| TOTALS | | | | | | TOTAL |
| | | | 1280 LF | | 332 | RNDC |
| | | | 1590 LF | | 8500 cy | TOTAL |
| | | | 9200 LF | | | |
| | | | 400 LF | | | |
| | | | 1 EA. | | | |
| | | | 5 EA. | | | |



Job No. 11/21/2010
 Description
 Date
 Rev.

RUTLAND STATE AIRPORT
 CLAYBOROUGH, VERMONT
DRAINAGE SUMMARY

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

Drawn by: [Name]
 Checked by: [Name]
 Date: 6/9/07
 Scale: 1" = 100'
 Sheet 3 of 88
 Sheet No. 38

GENERAL CONSTRUCTION AND SAFETY NOTES

GENERAL NOTES

1. THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT PLANS AND SPECIFICATIONS AND ANY RULES, REGULATIONS, STANDARDS OR SPECIFICATIONS REFERENCED THEREIN. THE PROJECT IS SUBJECT TO INSPECTION BY REPRESENTATIVES OF THE VERMONT AGENCY OF TRANSPORTATION (VADT), AND THE FEDERAL AVIATION ADMINISTRATION (FAA).
2. THE PROJECT IS TO BE COMPLETED IN CONFORMANCE WITH THE "CONSTRUCTION PHASING PLANS AND NOTES" AS CONTAINED IN THE PLANS, AND SHALL BE CONSTRUCTED IN A TIMELY MANNER IN ACCORDANCE WITH THE CONTRACTOR'S APPROVED PROJECT SCHEDULE. THE SCHEDULE SHALL PROVIDE FOR COMPLETION OF THE PHASES AS SHOWN ON THE PLANS AND DESCRIBED IN THE CONTRACT SPECIFICATIONS.
3. THE CONTRACTOR IS EXPECTED TO MEET COMPLETION OF CRITICAL PORTIONS OF THE PROJECT AND OPEN THOSE SEGMENTS TO TRAFFIC BY THE SPECIFIED TIMES AND TO COMPLETE THE ENTIRE PROJECT BY THE SPECIFIED TIMES AND TO COMPLETE THE ENTIRE PROJECT BY THE SPECIFIED TIMES AND TO COMPLETE THE ENTIRE PROJECT BY THE SPECIFIED TIMES.
4. RUTLAND STATE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF ALL WORK WITH THE AIRPORT MANAGER & THE PROJECT RESIDENT ENGINEER IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
5. CONSTRUCTION AND MAINTENANCE OPERATIONS BY OTHERS MAY OCCUR CONCURRENTLY AND AT TIMES IN THE VICINITY OF CONSTRUCTION ASSOCIATED WITH THIS PROJECT. THE CONTRACTOR SHALL COORDINATE HIS OPERATIONS AND COOPERATE WITH MAINTENANCE CREWS AND OTHER CONTRACTORS WORKING ON THE AIRPORT.
6. ACCESS TO THE SITE - THE CONTRACTOR'S ACCESS POINTS TO THE SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT PLAN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL VEHICLES AND PERSONNEL WHO ENTER THROUGH THESE ACCESS POINTS. THE CONTRACTOR SHALL MAINTAIN A SECURITY GUARD AT EACH GATE BEING USED AT ALL TIMES WHILE CONSTRUCTION IS UNDERWAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING ALL ACCESS POINTS BEING USED AT THE END OF EACH CONSTRUCTION DAY OR WHEN ACCESS POINTS ARE UNATTENDED.
7. HAUL ROUTES - APPROXIMATE LOCATION OF HAUL ROUTES FROM THE AIRPORT SITE ARE SHOWN ON THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS) WITH THE APPROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO COMMENCING THE WORK. EXISTING ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
8. CONTRACTOR'S STAGING AREAS - AN AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE. THIS AREA IS SHOWN ON THE GENERAL PROJECT LAYOUT. THE CONTRACTOR'S STAGING AREA SHALL BE GRADED, UNDOGGED, SEEDS, AND MULCHED UPON COMPLETION OF USE, AT THE CONTRACTOR'S EXPENSE.
9. DISPOSAL AREA - WASTE AREAS WILL BE MADE AVAILABLE FOR THE DISPOSAL OF THE CONTRACTOR'S SPILL MATERIALS. THE MANNER IN WHICH MATERIALS ARE PLACED IN EMBANKMENTS SHALL BE AS SPECIFIED AND APPROVED BY THE ENGINEER. WASTE MATERIALS INCLUDING TRUCKS AND OTHER DEBRIS WHICH ARE A DIRECT RESULT OF CONSTRUCTION, TRASH (I.E. CUPS, CANS, ETC.) SHALL BE DISPOSED OF THROUGH PROPER SANITARY METHODS.
10. SAFETY - THE CONTRACTOR SHALL CONDUCT HIS ACTIVITIES IN A SAFE MANNER AS SPECIFIED IN THE SECTION TITLED "SAFETY REQUIREMENTS DURING CONSTRUCTION" ON THIS SHEET.
11. PROTECTION OF AND REPAIR OF DAMAGE TO EXISTING CABLES - LOCATION OF ANY EXISTING AIRPORT UNDERGROUND CABLES IS AS SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF CABLES DAMAGED DUE TO CONTRACTOR'S OPERATIONS MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND SHALL BE AT THE CONTRACTOR'S EXPENSE. WHEN FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF AN FAA REPRESENTATIVE. THE FAA MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHER PERSONNEL IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.
12. EXISTING AIRFIELD LIGHTING SYSTEMS - INTERRUPTION OF EXISTING AIRFIELD LIGHTING SYSTEMS NOT INCLUDED IN THIS PROJECT SHALL NOT BE PERMITTED. ALL AIRFIELD LIGHTING CIRCUITS AFFECTED BY THIS PROJECT SHALL BE MAINTAINED BY THE CONTRACTOR DURING OPERATIONAL PERIODS IN ACCORDANCE WITH THE SPECIFICATIONS AND/OR AS DIRECTED BY THE ENGINEER.
13. CONSTRUCTION LIMITS - ALL CONTRACTOR VEHICLES AND TRAFFIC (UNLESS OTHERWISE AUTHORIZED) SHALL REMAIN WITHIN THE DESIGNATED CONSTRUCTION LIMITS OR HAUL ROUTES. CONSTRUCTION, STORAGE AND STOCKPILING UNITS ARE FURTHER DEFINED IN THE SECTION TITLED "SAFETY REQUIREMENTS DURING CONSTRUCTION" ON THIS SHEET.

14. PORTABLE FLOODLIGHTING - THE CONTRACTOR SHALL PROVIDE PORTABLE FLOODLIGHTING WHEN REQUIRED FOR CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL PROVIDE SUFFICIENT UNITS SO THAT ALL WORK AREAS ARE ILLUMINATED TO A LEVEL OF 5 HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY.
15. THE CONTRACTOR SHALL OBTAIN ALL THE PERMITS AND LICENSES REQUIRED FOR THE PROJECT WORK AT HIS OWN EXPENSE.
16. EXISTING TOPOGRAPHIC FIELD SURVEYS FOR THIS PROJECT AREA WERE PERFORMED BY LITTLE RIVER SURVEY CO. IN 1985.
17. THE HORIZONTAL CONTROL ON THIS PROJECT IS TIED TO THE 1883 AND 1898 NATIONAL GEODETIC HORIZONTAL AND VERTICAL DATUM, RESPECTIVELY.

SAFETY REQUIREMENTS DURING CONSTRUCTION

(A) FEDERAL AVIATION ADMINISTRATION (FAA) ADVISORY CIRCULARS (AC), ORDERS AND FEDERAL AVIATION REGULATIONS (FAR).

THE FOLLOWING PUBLICATIONS CONTAIN DEFINITIONS/DESCRIPTIONS OF CRITICAL AIRPORT OPERATING AREAS. THE AREAS DEFINED BELOW PERTAIN TO AIRFIELD SAFETY REQUIREMENTS AND ARE REFERENCED THROUGHOUT THE CONTRACT DOCUMENTS. COPIES OF THESE PUBLICATIONS ARE AVAILABLE THROUGH THE FAA OR CAN BE ORDERED BY MAIL FROM:

U.S. DEPARTMENT OF TRANSPORTATION
SUBSEQUENT DISTRIBUTION OFFICE
ARMONIE EAST BUSINESS CENTER
3341 G 75TH AVE.
LANDOVER, MD. 20785

AND CAN BE REVIEWED AT THE OFFICES OF THE VERMONT AGENCY OF TRANSPORTATION.

- (1) AC 150/5370-2, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", CURRENT EDITION.
- (2) FAR PART 77 "OBJECTS AFFECTING NAVIGABLE AIRSPACE, CURRENT EDITION."
- (3) AC 150/5300-13, "AIRPORT DESIGN", CURRENT EDITION, ESTABLISHES DESIGN, OPERATIONAL, AND MAINTENANCE STANDARDS FOR AIRPORTS. STANDARD TERMS USED IN THE CONTRACT PLANS AND SPECIFICATIONS ARE DEFINED BELOW.
 - (a) OBSTACLE FREE ZONE (OFZ) - A VOLUME OF SPACE WHICH IS FREE OF ALL FIXED OBJECTS AND CLEAR OF VEHICLES IN THE PROXIMITY OF AN AIRPLANE CONDUCTING AN APPROACH, MISSED APPROACH, LANDING, TAKEOFF, OR DEPARTURE. AN OFZ TYPICAL SECTION IS SHOWN ON THE GENERAL PROJECT LAYOUT PLAN.
 - (b) RUNWAY PROTECTION ZONE (RPZ) - A TRAPEZOIDAL AREA CENTERED ON THE RUNWAY BEGINNING AT A POINT 200 FEET BEYOND THE END OF THE AREA USABLE FOR TAKEOFF OR LANDING.
 - (c) OBJECT FREE AREA (OFA) - A TWO DIMENSIONAL GROUND AREA SURROUNDING RUNWAYS, TAXIWAYS, AND TAXILANES WHICH IS CLEAR OF OBJECTS EXCEPT FOR OBJECTS WHOSE LOCATION IS FIXED BY FUNCTION.
 - (d) SAFETY AREA - THE SURFACE ADJACENT TO RUNWAYS, TAXIWAYS, AND TAXILANES OVER WHICH AIRCRAFT SHOULD, IN DRY WEATHER, BE ABLE TO CROSS AT NORMAL SPEEDS WITHOUT INCURRING SIGNIFICANT DAMAGE. A SAFETY AREA IS GRADED, DRAINED AND CONTRACTED. IT IS FREE OF ANY HOLES, TRENCHES, BUMPS OR OTHER SIGNIFICANT SURFACE IRREGULARITIES OR OBJECTS OTHER THAN THOSE WHICH MUST BE THERE BECAUSE OF THEIR ESSENTIAL AERONAUTICAL FUNCTION. THE SAFETY AREA REQUIRES THE CAPABILITY OF SUPPORTING MAINTENANCE VEHICLES AND AIRCRAFT RESCUE AND THE FIGHTING VEHICLES UNDER NORMAL (NOT) CONDITIONS.

(B) GENERAL SAFETY REQUIREMENTS

- (1) THE CONTRACTOR SHALL ACCOUNT HIS SUPERVISORS AND EMPLOYEES WITH THE AIRPORT ACTIVITY AND OPERATIONS THAT ARE INHERENT TO RUTLAND STATE AIRPORT AND SHALL CONDUCT HIS CONSTRUCTION ACTIVITIES TO CONFORM TO ALL ROUTINE AND EMERGENCY AIR TRAFFIC REQUIREMENTS AND GUIDELINES SPECIFIED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY DEVICES AS REQUIRED FOR THE PROTECTION OF HIS PERSONNEL.
 - (a) PROTECTION OF ALL PERSONS SHALL BE PROVIDED THROUGHOUT THE PROGRESS OF THE WORK. THE WORK SHALL PROCEED IN SUCH A MANNER AS TO PROVIDE SAFE CONDITIONS FOR ALL PERSONS AND AGENCY AND CONTRACTOR PERSONNEL. CONSTRUCTION OPERATIONS SHALL BE SUCH THAT MAXIMUM PROTECTION IS PROVIDED TO INSURE PERSONS FROM DANGEROUS CONDITIONS IN THE WORK AREA ARE NOT SUBJECT TO ANY DANGEROUS CONDITIONS.

- (3) DURING PERFORMANCE OF THIS CONTRACT, THE AIRPORT RUNWAYS, TAXIWAYS, AND AIRCRAFT PARKING APRONS SHALL REMAIN IN USE BY AIRCRAFT TO THE MAXIMUM EXTENT POSSIBLE. ALL AIRCRAFT TRAFFIC IN THESE AREAS SHALL HAVE PRIORITY OVER CONTRACTOR'S TRAFFIC. THE OWNER RESERVES THE RIGHT TO ORDER THE CONTRACTOR AT ANY TIME TO VACATE ANY AREA NECESSARY TO MAINTAIN SAFE AIRCRAFT OPERATIONS. USE OF AREAS NEAR THE CONTRACTOR'S WORK WILL BE CONTROLLED TO MINIMIZE DISTURBANCE TO THE CONTRACTOR'S OPERATION. THE CONTRACTOR SHALL NOT ALLOW EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, OR ANY OTHER UNAUTHORIZED PERSON TO ENTER OR REMAIN IN ANY AIRPORT AREA WHICH WOULD BE HAZARDOUS TO PERSONS OR TO AIRCRAFT OPERATIONS.
- (4) ALL WORK TO BE PERFORMED WHICH IS CLOSE TO AN ACTIVE RUNWAY, TAXIWAY OR APRON SHALL BE PERFORMED WHEN THE RUNWAY, TAXIWAY OR APRON IS NOT IN USE. SUCH WORK SHALL BE ACCOMPISHED ONLY WITH PRIOR PERMISSION FROM THE ENGINEER AND AIRPORT MANAGER. REQUESTED CLOSINGS SHALL BE DIRECTED TO THE ENGINEER AT LEAST 48 HOURS IN ADVANCE.

CONSTRUCTION AND FACILITIES MAINTENANCE

(1) THE FOLLOWING ARE CONSIDERED SAFETY PROBLEMS AND/OR HAZARDS:

- (a) TRENCHES, HOLES, OR EXCAVATION ON OR ADJACENT TO ANY OPEN RUNWAY, TAXIWAY, TAXILANE, OR IN ANY RELATED SAFETY, APPROACH, OR DEPARTURE AREA.
- (b) UNMARKED/UNLIGHTED HOLES OR EXCAVATION IN ANY APRON, OPEN TAXIWAY, OPEN TAXILANE, OR RELATED SAFETY AREA.
- (c) MOUNDS OR PILES OF EARTH, CONSTRUCTION MATERIALS, TEMPORARY STRUCTURES OR OTHER OBJECTS IN THE VICINITY OF ANY OPEN RUNWAY, TAXIWAY, TAXILANE, OR IN ANY RELATED SAFETY, APPROACH, OR DEPARTURE AREA.
- (d) VEHICLES OR EQUIPMENT, WHETHER OPERATING OR IDLE, ON ANY OPEN RUNWAY, TAXIWAY, TAXILANE, OR IN ANY RELATED SAFETY, APPROACH, OR DEPARTURE AREA.
- (e) VEHICLES, EQUIPMENT, EXCAVATION, STOCKPILES, OR OTHER MATERIALS WHICH COULD INTERFERE WITH ELECTRONIC SIGNALS FROM RADIOS OR ELECTRONIC NAVIGATIONAL AIDS (NAV AIDS).
- (f) PAVEMENT DROP-OFFS - LIPS (OTHER PERMANENT TEMPORARY WHICH COULD CAUSE DAMAGE TO AIRCRAFT IF CROSSED AT NORMAL OPERATING SPEEDS. THE NORMAL MAXIMUM DROP-OFF OR LIP IS 1-1/2" INCHES.
- (g) UNMARKED UTILITY, NAV AID, WEATHER SERVICE, RUNWAY LIGHTING, OR OTHER POWER OR SIGNAL CABLES THAT COULD BE DAMAGED DURING CONSTRUCTION.
- (h) OBJECTS, WHETHER OR NOT MARKED OR FLAGGED, OR ACTIVITIES ANYWHERE ON OR IN THE VICINITY OF THE AIRPORT WHICH COULD BE DISTRACTING, CONFUSING, OR ALARMING TO PILOTS DURING AIRCRAFT OPERATIONS.
- (i) UNLARGED/UNLIGHTED LOW VISIBILITY TOWERS SUCH AS TALL CRANES, DRILLS, AND THE LIKE ANYWHERE IN THE VICINITY OF ACTIVE RUNWAYS, OR IN ANY APPROACH OR DEPARTURE AREA.
- (j) MISLEADING OR MALFUNCTIONING OBSTRUCTION LIGHTS OR UNLIGHTED/UNMARKED OBSTRUCTIONS IN THE APPROACH TO ANY ACTIVE RUNWAY.
- (k) WATER, SNOW, DIRT, DEBRIS, OR OTHER TRANSIENT OBSTRUCTION WHICH TEMPORARILY OBSCURES PAVEMENT MARKINGS OR PAVEMENT EDGES, OR DEGRADATES VISIBILITY TO AIRCRAFT OPERATING ON RUNWAYS, TAXIWAYS, AND APRONS. SHALL HAVE PRIORITY OVER CONTRACTOR'S TRAFFIC. AT NO TIME SHALL THE CONTRACTOR'S VEHICLES OR PERSONNEL BE ALLOWED TO ENTER OR CROSS ACTIVE RUNWAYS OR CLEAR ZONES WITHOUT PROPER AUTHORIZATION.

- (2) THE CONTRACTOR SHALL CONDUCT ACTIVITIES SO AS NOT TO VIOLATE ANY SAFETY STANDARDS CONTAINED HEREIN. THE CONTRACTOR SHALL NOTIFY ALL CONSTRUCTION AND STORAGE AREAS AS OFTEN AS NECESSARY AND PROMPTLY TAKE ALL STEPS NECESSARY TO PREVENT/HENRY ANY UNSAFE OR POTENTIALLY UNSAFE CONDITIONS OR ACTIVITIES DISCOVERED.
- (3) THE VAOT WILL BE RESPONSIBLE FOR ISSUING APPROPRIATE NOTICE TO AIRMEN (NOTAM) CONCERNING CONSTRUCTION ACTIVITY ON THE AIRFIELD.
- (4) MOTORIZED VEHICLES
THIS PROJECT INCLUDES WORK WITHIN THE AIRCRAFT OPERATIONS AREA (AOA). ALL PERMITTED VEHICLES SHALL BE EQUIPPED WITH A FLASHING AMBER (YELLOW) DOME-TYPE LIGHT, MOUNTED ON TOP OF THE VEHICLE AND OF SUCH INTENSITY TO CONFORM TO LOCAL CODES FOR MAINTENANCE AND EMERGENCY VEHICLES. ALL VEHICLES OPERATING WITHIN THE AIRFIELD SHALL BE IDENTIFIED WITH A SIGN ON EACH SIDE OF THE VEHICLE BEARING THE CONTRACTOR'S NAME IN 12-INCH MINIMUM LETTER HEIGHT.

VEHICLES MAKING ONLY OCCASIONAL VISITS TO THE JOB SITE ARE EXEMPT FROM THE IDENTIFICATION REQUIREMENTS CONTAINED HEREIN ABOVE PROVIDED THAT THEY ARE ESCORTED INTO, THROUGH, AND OUT OF THE AIRPORT AREA BY A PROPERLY IDENTIFIED VEHICLE.

(E) RADIO COMMUNICATIONS

RADIO COMMUNICATIONS ARE REQUIRED BETWEEN THE CONTRACTOR'S REPRESENTATIVE AND RUTLAND UNCOM. RADIO CONTACT IS REQUIRED AT ALL TIMES WHILE THE CONTRACTOR HAS PERSONNEL AND EQUIPMENT ON THE PROJECT SITE AND WHILE THEY ARE IN AN ACTIVE AIR OPERATIONS AREA (AOA) OF THE AIRPORT. RADIOS SHALL BE FURNISHED BY THE CONTRACTOR AND SHALL BE CAPABLE OF TRANSMITTING AND RECEIVING AT A GROUND CONTROL FREQUENCY OF 122.8 MHz. THIS FREQUENCY IS TO BE UTILIZED WHEN CROSSING ACTIVE FACILITIES. SUPPORT RADIOS SHALL BE ON SITE AND OPERATING AT ALL TIMES SO THAT INSTRUCTIONS OR COMMUNICATIONS MAY BE DISPATCHED TO ALL CREWS AND/OR EQUIPMENT WORKING IN AN ACTIVE AOA.

(F) DEBRIS

DEBRIS, WASTE, AND LOOSE MATERIAL (INCLUDING DUST AND DIRT) CAPABLE OF CAUSING DAMAGE TO AIRCRAFT LANDING GEAR OR PROPELLERS, OR BEING INGESTED IN JET ENGINES, SHALL NOT BE ALLOWED ON ACTIVE AIRCRAFT MOVEMENT AREAS OR ADJACENT GRASSED AREAS. MATERIALS OBSERVED TO BE WITHIN THESE AREAS SHALL BE REMOVED IMMEDIATELY BY THE CONTRACTOR. THE CONTRACTOR SHALL BE REQUIRED TO HAVE A SLEEPING MACHINE AND OPERATOR ON SITE AND READY AT ALL TIMES DURING CONSTRUCTION ACTIVITY WHERE TRAVEL ON OR ACROSS RUNWAYS, RAMP AREAS, TAXIWAYS, OR AIRCRAFT APRONS IS REQUIRED. THE CONTRACTOR SHALL PROVIDE SUFFICIENT PERSONNEL AND EQUIPMENT TO KEEP SUCH SURFACES CLEAR OF DEBRIS.

(G) FLAMMABLE

IN ACCORDANCE WITH THE SPECIFICATIONS, THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, FURNISH FLAMMABLE AS DIRECTED TO CONTROL HIS TRAFFIC (UNLESS OTHERWISE SPECIFIED BY THE ENGINEER).

(H) LIMITS

- (1) UNDERGROUND UTILITIES: THE LOCATIONS OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE CONSIDERED TO BE ONLY ESTIMATED LOCATIONS. ALL UTILITIES LOCATIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION. ALL UTILITIES LOCATIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING FOR INCURRED COSTS OF REPAIRS.
- (2) UTILITIES NOTIFICATION: AT LEAST TWO WORKING DAYS PRIOR TO COMMENCING CONSTRUCTION OPERATIONS IN AN AREA WHICH MAY INVOLVE UNDERGROUND UTILITY FACILITIES, THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER, AND THE OWNER OF EACH UNDERGROUND UTILITY FACILITY AFFECTED.
- (3) THE FOLLOWING IS A LIST OF COMPANIES WITH POSSIBLE UTILITIES WITHIN THE CONSTRUCTION LIMITS.

| UTILITY | 1-800-225-4877 |
|---------|----------------|
| DISSAFE | 1-800-848-2877 |
| CVPS | |

(4) MISCELLANEOUS

- (1) OPEN FLAME, WELDING OR TORCH CUTTING OPERATIONS ARE PROHIBITED UNLESS ADEQUATE FIRE AND SAFETY PRECAUTIONS HAVE BEEN TAKEN AND THE PROCEDURE PREVIOUSLY APPROVED BY THE ENGINEER.
- (2) EQUIPMENT AND STOCKPILED MATERIAL SHALL BE CONFINED IN A MANNER TO PREVENT MOVEMENT RESULTING FROM AIRCRAFT JET BLAST OR WIND CONDITIONS IN EXCESS OF 10 KNOTS.
- (3) THE CONTRACTOR SHALL PROVIDE BUCKET TYPE CONSTRUCTION BARRICADES WITH FLASHING YELLOW LIGHTS AS SHOWN ON THE DRAWINGS TO DELINEATE THE WORK AREAS WHEN CLOSED TO AIRCRAFT TRAFFIC. OPEN TRENCHES, EXCAVATIONS AND STOCKPILED MATERIAL LOCATED IN THE AOA SHALL BE PROMINENTLY MARKED WITH ORANGE FLAGS AND LIGHTED BY APPROVED LIGHT UNITS DURING HOURS OF LIMITED VISIBILITY AND DARKNESS.
- (4) ALL MATERIALS AND EQUIPMENT WHEN NOT IN USE SHALL BE PLACED IN APPROVED AREAS WHERE THEY WILL NOT CONSTITUTE A HAZARD TO AIRCRAFT OPERATIONS AND NOT PENETRATE CLEARANCE SURFACES. EQUIPMENT SHALL BE PARKED AT THE STAGING AREA WHEN NOT IN USE.
- (5) MAXIMUM EQUIPMENT HEIGHT SHALL NOT EXCEED 18 FEET UNLESS PRIOR APPROVAL IS OBTAINED FROM THE ENGINEER.
- (6) UPON COMPLETION OF ANY STAGE/PHASE OF WORK, THE ENGINEER WILL ARRANGE A PHYSICAL INSPECTION OF THE AREA WITH AIRPORT OPERATIONS PERSONNEL PRIOR TO OPENING ANY PORTION OF A RUNWAY, RAMP AREA OR AIRCRAFT ROADWAY THAT HAS BEEN CLOSED FOR WORK OR USED FOR A CROSSING POINT OR HAUL ROUTE BY THE CONTRACTOR.
- (7) ENTRANCE TO THE AIRFIELD IS SUBJECT TO SECURITY REGULATIONS. ALL PERSONNEL ENTERING THE AIRFIELD MUST OBTAIN AND DISPLAY SECURITY IDENTIFICATION BADGES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ASSURING THAT ALL OF HIS EMPLOYEES WHO HAVE UNSORTED ACCESS TO THE AIRFIELD, HAVE HAD BACKGROUND CHECK PERFORMED ON THEM DATING BACK FIVE (5) YEARS VERIFYING REPRESENTATIONS MADE BY THE EMPLOYEE RELATING TO EMPLOYMENT.
- (8) THE CONTRACTOR SHALL PROVIDE THE ENGINEER WITH A CURRENT LIST OF ALL EMPLOYEES WORKING ON THE AIRPORT. THE LIST SHALL BE MAINTAINED CURRENT BY THE CONTRACTOR AND APPLIED TO ALL SUBCONTRACTORS.
- (9) EXCEPT FOR EMERGENCIES, ALL CONTACT WITH AIRPORT PERSONNEL SHALL BE MADE THROUGH THE RESIDENT ENGINEER. FOR EMERGENCIES INVOLVING SAFETY (HAZARDS, FIRE, SECURITY BREACHES, ETC.) THE CONTRACTOR SHALL MAKE DIRECT CONTACT WITH AIRPORT OPERATIONS FOLLOWED BY NOTIFICATION TO THE RESIDENT ENGINEER AS SOON AS POSSIBLE.
- (10) THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERVISOR, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- (11) IN ACCORDANCE WITH THE SPECIFICATIONS, FEDERAL WAGE RATES SHALL BE POSTED OUTSIDE THE SITE FIELD OFFICE IN A WEATHERPROOF ENCLOSURE.




| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

RUTLAND STATE AIRPORT
CLAREMONT, VERMONT


GENERAL CONSTRUCTION & SAFETY NOTES

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | | | |
|--------------------------------|------------------------------|--------------------------------|--------------------------------|
| Checked by: <i>[Signature]</i> | Drawn by: <i>[Signature]</i> | Checked by: <i>[Signature]</i> | Checked by: <i>[Signature]</i> |
| Scale: N/A | Scale: N/A | Scale: N/A | Scale: N/A |
| Date: 6/17/87 | Date: 6/17/87 | Date: 6/17/87 | Date: 6/17/87 |
| Sheet 8 of 88 | Sheet 8 of 88 | Sheet 8 of 88 | Sheet 8 of 88 |




A
7
PROPOSED TYPICAL SECTION R/W 1-19
STA 125+00 TO 142+00
SCALE = NONE




B
7
PROPOSED TYPICAL SECTION R/W 1-19
STA 103+00 TO 124+00
SCALE = NONE




C
7
PROPOSED TYPICAL SECTION R/W 1-19
STA 160+00 TO 163+00
SCALE = NONE



E
7
EXISTING TYPICAL SECTION
RUNWAY 1-19
SCALE = NONE



D
7
RUNWAY SAFETY AREA BEYOND RUNWAY
THRESHOLD - TYPICAL SECTIONS
STA 100+00 TO 103+00
STA 153+00 TO 156+00
SCALE = NONE



G
7
EXISTING RUNWAY PAVEMENT CRACK REPAIRS
SCALE = NONE

NOTES: 1. PRIOR TO PLACING NEW BITUMINOUS CONCRETE PAVEMENT OVERLAY, PAVEMENT CRACKS TO BE REPAIRED OR REINFORCED, AS FOLLOWS:

TYPE I CRACK REPAIR: CRACKS LESS THAN 3/4" IN WIDTH TO BE ROUTED AND SEALED WITH HOT POURED JOINT SEALING FILLER. PAVEMENT TO BE MADE UNDER ITEM 524.11 MOD. 1, TYPE I CRACK REPAIR (P-805).

TYPE II CRACK REPAIR: CRACKS BETWEEN 3/4" AND 1 1/4" IN WIDTH TO BE ROUTED SEALED WITH HOT POURED JOINT SEALING FILLER. PRIOR TO PLACING OVERLAY CRACKS BETWEEN 1/2" AND 1 1/4" SHALL BE COVERED WITH A PAVEMENT REINFORCEMENT MATERIAL SUCH AS PAVE-REPAIR TM OR APPROVED EQUAL. PAYMENT TO BE MADE UNDER ITEM 524.11 MOD. 2 (P-805), TYPE II CRACK REPAIR.

TYPE III CRACK REPAIR: CRACKS OVER 1 1/4" IN WIDTH TO BE CUT OUT, EXISTING BIT. CONC. PAVEMENT (8") ON EITHER SIDE OF THE CRACK TO BE REMOVED, BASE MATERIAL RE-COMPACTED, AND NEW BITUMINOUS CONCRETE PAVEMENT (CONFORMING TO ITEM 408.25 MOD. 1 P-401) REPLACED. PAYMENT TO BE MADE UNDER ITEM 524.11, MOD. 3 (P-805).

2. DETERMINATION OF USE OF TYPE I, TYPE II, OR TYPE III CRACK REPAIR WILL BE AS DIRECTED BY THE ENGINEER.

3. CRACK SURVEY IN DEC. 1988 REVEALED APPROXIMATELY 17,000 LF OF CRACKS WHICH NEEDED REPAIR, APPROXIMATELY 10% TYPE III, APPROXIMATELY 50% TYPE II AND APPROXIMATELY 40% TYPE I.

GENERAL NOTES

- SUBGRADE UNDER AREAS TO BE PAVED TO BE COMPACTED TO 100% DENSITY AS PER AASHTO T-180.
- BITUMINOUS TACK COAT (EMULSIFIED ASPHALT, RS-1) TO BE APPLIED BETWEEN LIFTS OF BITUMINOUS CONCRETE PAVEMENT AT A RATE OF 0.01 TO 0.03 GAL / SY WHEN DIRECTED BY THE ENGINEER. (NOT A SEPARATE PAY ITEM.)
- REMOVAL OF EXISTING MANHOLES AND DROP INLETS, TO BE PAID UNDER ITEM 203.18 SOLID ROCK EXCAVATION. (3 CY PER EACH UNIT REMOVED). EXISTING DRAINAGE LINES TO BE ABANDONED IN PLACE. PIPES TO BE PLUGGED EACH END WITH CONCRETE BEFORE BACKFILLING. PAYMENT TO BE SUBSIDIARY TO REMOVAL OF MANHOLES AND DROP INLETS.
- EXISTING BITUMINOUS PAVEMENT 80'-75' EACH SIDE OF CENTERLINE TO BE REMOVED. PAYMENT TO BE MADE UNDER ITEM 203.15, COMMON EXCAVATION. AREA TO BE GRADED, TOPSOILED AND SEEDED.
- ALL EXCAVATION TO BE PAID FOR UNDER ITEM 203.15, COMMON EXCAVATION OR 203.16 SOLID ROCK EXCAVATION.
- SEED, ITEM 851.16 TO BE APPLIED AS DIRECTED BY ENGINEER.

| QTY | UNIT | NAME | EST. QTY | EST. PRICE |
|--------|------|-----------------------|----------|------------|
| 3.53 | 2 | CROWN VETCH | 97 | 75 |
| 50.00 | 30 | CREeping RED FESCUE | 98 | 85 |
| 8.33 | 5 | TYMOTHY | 99 | 85 |
| 18.67 | 10 | PERN. RYE GRASS | 99 | 85 |
| 18.34 | 5 | ALPACA (WAR. SARAGUO) | 99 | 85 |
| 8.33 | 5 | BIROFOOT TROFOIL | 99 | 85 |
| 5.00 | 3 | (VAR. EMPIRE) | 92 | 85 |
| | | HIGHLAND BENT GRASS | 92 | 85 |
| 100.00 | 80 | | | |

THE SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS WEED SEED.

FERTILIZER, ITEM 851.15, FORMULA 10-20-10 TO BE USED WITH SEED, ITEM 851.15, APPLIED AT THE RATE OF 500 LBS / ACRE.

AGRICULTURAL LIMESTONE, ITEM 851.20, TO BE APPLIED AT RATE OF 2 TONS / ACRE OR AS DIRECTED BY ENGINEER.

HAY MULCH, ITEM 851.25, TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS / ACRE.

TOPSOIL, ITEM 851.35, TO BE USED WITH SEED, ITEM 851.15, AS DIRECTED BY THE ENGINEER.

ALLOWABLE THICKNESS TOLERANCES:
SUBGRADE ± 1"
CONTROLLED MATERIAL ± 1"
PAVEMENT ± 3/16"
BASE COURSE ± 1/2"

- BITUMINOUS CONCRETE PAVEMENT DESIGN BASED ON PERFORMANCE GRADED ASPHALT - USE PG 66-34 IN ACCORDANCE WITH AASHTO DESIGNATION 8P1.
- MINIMUM OVERLAY DEPTH IS 2 INCHES - EXISTING PAVEMENT GRADED ASPHALT - WHEN NECESSARY TO ACHIEVE MINIMAL THICKNESS.

RUTLAND STATE AIRPORT
CLAREMONT, VERMONT

TYPICAL SECTIONS & DETAILS


Checked by: []
Drawn by: []
Checked by: []
In Charge: []
As Noted: []

Scale: []
Date: 6/14/87
Sheet 7 of 8
Sheet No: []


3 MARCUS BOULEVARD
ALBANY, NEW YORK

AIP 3-50-0015-11


7



A
B 6" DIA UNDERDRAIN AND 6" DIA UNDERDRAIN CARRIER PIPE
SCALE = NONE




B
B PROPOSED TAXIWAY TYPICAL SECTION
SCALE = NONE




C
B PAVEMENT OVERLAY TRANSITIONS
SCALE = NONE


1. OVERLAY OPERATION TO PROCEED FROM SOUTH TO NORTH
2. OVERLAY TO BE COMPLETED FULL WIDTH OF RUNWAY ON EACH EVENINGS WORK.
3. PLACEMENT OF PAVEMENT OVERLAY TO TERMINATE EACH NIGHT TO ALLOW SUFFICIENT TIME FOR PLACEMENT OF TEMPORARY MARKING AND CLEANUP PRIOR TO RE-OPENING THE RUNWAY.
4. AT THE END OF EACH NIGHT'S WORK, TRANSITION RAMPS TO BE CONSTRUCTED TO PROVIDE TRANSITION FROM COMPLETED COURSE OF THE OVERLAY TO THE EXISTING PAVEMENT.




D
B BUTT JOINT DETAIL
SCALE = NONE




E
B SAWCUT DETAIL
SCALE = NONE




F
B EXISTING TYPICAL SECTION TAXIWAY 'C'
SCALE = NONE



G
B PAVEMENT SECTION EDGE (TYP.)
SCALE = NONE



H
B OVERLAY BUTT JOINT DETAIL
SCALE = NONE



I
B MAINTENANCE DRIVEWAY PROFILE
STA 145+03E LEFT
SCALE = NONE




| REV. | DATE | DESCRIPTION | JOB NO. |
|------|------|-------------|---------|
| | | | |
| | | | |
| | | | |

ROUTLAND STATE AIRPORT
CLARENDON, VERMONT


TYPICAL SECTIONS & DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | | |
|------------------|------------------|-----------------|
| Drawn by: JCP | Checked by: JCP | Scale: AS NOTED |
| Checked by: JCP | Checked by: JCP | Date: 5/9/97 |
| Approved by: JCP | Approved by: JCP | Sheet 9 of 93 |
| | | Sheet No. 8 |




C
9
PROPOSED SUBGRADE TRANSITION
R/W STA 124+50 TO 125+00
T/W D STA 501+00 TO 500+50
SCALE = NONE




D
9
PROPOSED SUBGRADE TRANSITION
STA 142+00 TO 142+10
STA 149+90 TO 150+00
SCALE = NONE




E
9
TYPICAL DRIVEWAY SECTION
SCALE = NONE
(DRIVE AT 508+60: RT IS 10' WIDE)
(DRIVE AT 121+60: LT REMAINS 11' WIDE)



F
9
EXISTING MANHOLE DETAIL
TYPICAL
SCALE = NONE




G
9
EXISTING DROP INLETS DETAIL
TYPICAL
SCALE = NONE



- BERMS SHALL BE COMPACTED BY EARTH-MOVING EQUIPMENT.
- TOP MAY BE WIDER AND SIDE SLOPES MAY BE FLATTER
- BERMS TO BE CONSTRUCTED ALONG TOP OF SLOPE OUTSIDE RUNWAY SAFETY AREA OVERRUN.

I
9
EARTH BERM
SCALE = NONE



J
9
TRENCH DETAIL
SCALE = NONE



| | |
|-------------|------|
| DESIGNED BY | DATE |
| CHECKED BY | DATE |
| APPROVED BY | DATE |
| PROJECT NO. | |
| JOB NO. | |


RUTLAND STATE AIRPORT
CLARENDON, VERMONT

TYPICAL SECTIONS & DETAILS


URS *Greiner, Inc.*
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|----------|
| DESIGNED BY | DATE |
| CHECKED BY | DATE |
| APPROVED BY | DATE |
| PROJECT NO. | |
| JOB NO. | |
| SCALE | AS SHOWN |
| DATE | 5/8/97 |
| SHEET # | OF 45 |
| SHEET NO. | 9 |

**RUNWAY 1-18 PROFILE
STA 108+00 TO 121+00**



**RUNWAY 1-18 PROFILE
STA 121+00 TO 134+00**



AIRP 3-50-01-5-11

| | |
|--|--|
| | Designed by S. CHASE 3/97 Drawn by M. MICHELLA 3/97 Checked by C. FRENCH 3/97 Approved by M. CHASE 3/97 |
|--|--|

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

**RUTLAND STATE AIRPORT
CLARENDON, VERMONT**

RUNWAY 1-19 PROFILE


| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. 00000 File No. 19000000




DATE: 04-04-84
 DRAWN BY: J. J. FERRER
 CHECKED BY: J. J. FERRER

A 10 3-50-013-11



DATE: 04-04-84
 DRAWN BY: J. J. FERRER
 CHECKED BY: J. J. FERRER



100' OVERLAY
 NEW CONSTRUCTION

| | |
|-------------|------|
| DESIGNED BY | DATE |
| DRAWN BY | DATE |
| CHECKED BY | DATE |
| APPROVED BY | DATE |


URS Greiner, Inc.
 5 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
 RUNWAY 1-19 PROFILE


| | | |
|------|------|-------------|
| REV. | DATE | DESCRIPTION |
| | | |
| | | |




**RUNWAY INTERSECTION
FINISHED GRADING PLAN**
SCALE: 1" = 50'




RUNWAY 13-31 PROFILE




TAXIWAY 'F' - FINISHED GRADING PLAN
SCALE: 1" = 50'



TAXIWAY 'C' PROFILE



TAXIWAY 'F' PROFILE




AIP 3-30-2011-11

| | | | | | | |
|--------------------|---------------------------------------|--|---|-------------------------------------|-----------------------|------------------------|
| Sheet No. 3 | Designed by: SP C. J. BATES | URS Greiner, Inc. 3 MARCUS BOULEVARD ALBANY, NEW YORK | RUTLAND STATE AIRPORT CLANDON, VERMONT | TAXIWAYS - RUNWAY 13-31 PROFILES | REV. DATE DESCRIPTION | |
| | Drawn by: W W. WICKS | | | | Job No. 100233.00 | File No. 11-010233-01P |
| | Checked by: SP S. P. BATES | | | | | |
| | Approved by: SP S. P. BATES | | | | | |

SCALE
 1" = 40' HORIZONTAL
 1" = 10' VERTICAL

| NO. | DATE | DESCRIPTION | BY |
|-----|----------|--------------------|-----|
| 1 | 10/05/09 | ISSUED FOR PERMITS | WJG |
| 2 | 10/05/09 | ISSUED FOR PERMITS | WJG |

LEGEND
 3 1/4" DUCTILE IRON
 CONDUIT FOR FUTURE SECTION
 12" DIA. MANHOLE
 18" DIA. MANHOLE
 30" DIA. MANHOLE
 48" DIA. MANHOLE
 60" DIA. MANHOLE
 72" DIA. MANHOLE
 84" DIA. MANHOLE
 96" DIA. MANHOLE
 108" DIA. MANHOLE
 120" DIA. MANHOLE
 132" DIA. MANHOLE
 144" DIA. MANHOLE
 156" DIA. MANHOLE
 168" DIA. MANHOLE
 180" DIA. MANHOLE
 192" DIA. MANHOLE
 204" DIA. MANHOLE
 216" DIA. MANHOLE
 228" DIA. MANHOLE
 240" DIA. MANHOLE
 252" DIA. MANHOLE
 264" DIA. MANHOLE
 276" DIA. MANHOLE
 288" DIA. MANHOLE
 300" DIA. MANHOLE



MATCH LINE SHEET 15

Developed by: [Signature]
 Drawn by: [Signature]
 Checked by: [Signature]
 Approved by: [Signature]

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
 PAVING PLAN &
 GEOMETRIC LAYOUT

| REV | DATE | DESCRIPTION |
|-----|------|-------------|
| | | |
| | | |




AIP 2-50-015-11

Sheet No. 14

MATCH LINE SHEET 14

LEGEND

| | |
|--|---|
| | 3 1/4" ORBITAL CONCRETE AND SANDING SECTION |
| | PROPOSED LIMIT LINES OF PAVEMENT |
| | EXISTING LIMIT LINES OF PAVEMENT |
| | EXISTING CURB |
| | EXISTING MANHOLE |
| | EXISTING MANHOLE (TO BE REMOVED) |
| | EXISTING MANHOLE (TO BE RELOCATED) |



MATCH LINE SHEET 16


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARNDON, VERMONT
**PAVING PLAN &
 GEOMETRIC LAYOUT**

| | |
|---------------------------|-----------------|
| DESIGNED BY C. W. WOOD | DATE 1/15/00 |
| DRAWN BY J. WOOD | DATE 2/1/00 |
| CHECKED BY C. W. WOOD | DATE 2/1/00 |
| APPROVED BY C. W. WOOD | DATE 2/1/00 |



ALP 3-50-015-11



- NOTES:**
1. (NON-REPRESENTATIVE SHEET TO BEYOND SHEET 19)
 2. CONSTRUCTION OF THE SILT FENCE, SAND BARRIER AND SAND BAG BARRIER SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS AND DETAILS SHOWN ON SHEET 19.
 3. THE SILT FENCE SHALL BE CONSTRUCTED AS SHOWN ON SHEET 19.
 4. THE SAND BARRIER SHALL BE CONSTRUCTED AS SHOWN ON SHEET 19.
 5. THE SAND BAG BARRIER SHALL BE CONSTRUCTED AS SHOWN ON SHEET 19.

PROJECT MATERIALS & LABOR QUANTITIES

GRAVEL: 100,000 CY
 SAND: 100,000 CY
 SAND BAGS: 100,000
 SILT FENCE: 100,000
 SAND BARRIER: 100,000
 SAND BAG BARRIER: 100,000

CONSTRUCTION SPECIAL NOTES:

1. EXISTING 24" DIA. MANHOLE SHALL BE REPAIRED AND SET TO CORRECT ELEVATION.
2. ALL EXISTING UTILITY LINES SHALL BE PROTECTED AND MARKED AS SHOWN ON SHEET 19.

| LEGEND | |
|--------|--------------------------------|
| ○ | MANHOLE #33 |
| □ | MANHOLE #33 |
| — | 6" UNDERDRAIN & FILTERING SAND |
| — | FLOW LINE |
| — | SILT FENCE |
| — | SAND BARRIER |
| — | SAND BAG BARRIER |

MATCH LINE SHEET 20

| | |
|-------------|------|
| Designed by | DATE |
| Drawn by | DATE |
| Checked by | DATE |
| Approved by | DATE |

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLAREMONT, VERMONT
 GRADING AND DRAINAGE PLAN

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. 74013.00 File No. V100000003






| | | |
|------|------|-------------|
| REV. | DATE | DESCRIPTION |
| | | |
| | | |

RUTLAND STATE AIRPORT
CLASHOOK, VERMONT
GRADING AND DRAINAGE PLAN

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|------|
| DESIGNED BY | DATE |
| CHECKED BY | DATE |
| APPROVED BY | DATE |

Sheet No. 20
AIP 3-50-001-1



MATCH LINE SHEET 21

MATCH LINE SHEET 19

- EXCISE**
1. ALL EXISTING GRADE SHALL BE MAINTAINED TO MATCH THE ADJACENT AREAS.
 2. CONSTRUCTION TO INSTALL SILT FENCE, WEIR, AND CURB SHALL BE COMPLETED PRIOR TO THE START OF CONSTRUCTION OF THE DRAINAGE CHANNEL.
 3. DRAINAGE CHANNEL SHALL BE CONSTRUCTED IN LONG SECTIONS TO ALLOW PROGRESSIVE CONSTRUCTION TO BE COMPLETED UNDER THE BEST AVAILABLE CONDITIONS.
 4. CONSTRUCTION SHALL BE TO THE CENTERLINE OF THE CHANNEL TO THE CENTERLINE OF THE CHANNEL.
 5. ALL EXISTING AREAS SUBJECT TO CONSTRUCTION SHALL BE REGRADED TO MATCH THE ADJACENT AREAS.


LEGEND

| | |
|---|-------------------------------|
| ○ | MANHOLE |
| □ | DROP INLET |
| — | 6" UNDERDRAIN & FLUSHING BASH |
| — | FLOW LINE |
| — | SILT FENCE |
| — | EARTH BERM |

- NOTES**
1. ALL ELEVATIONS REFER TO MEAN SEA LEVEL, M.A.S.L. (NAD 83)
 2. CONSTRUCTION TO BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS IN THE AREA.
 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE STATE OF VERMONT AND THE FEDERAL AVIATION ADMINISTRATION (FAA) PRIOR TO COMMENCING CONSTRUCTION.
 4. PROTECT EXISTING UTILITIES AND STRUCTURES TO REMAIN FROM DAMAGE DURING CONSTRUCTION.
 5. ALL WORK SHALL BE SUBJECT TO INSPECTION BY THE FAA AND AS SOON AS PRACTICABLE IN THE AREA OF CONSTRUCTION.

PROPOSED MAINTENANCE & REPAIR AREAS
 101 - 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.

EXISTING ELEVATIONS OF MAINTENANCE AREAS
 101 - 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.



LEGEND

- 6" DIA. MANHOLE
- 6" DIA. MANHOLE
- 6" FLOW LINE
- 6" SILT FENCE
- 6" CATCH BASIN

11/15/2010 3:30:00 PM

| | |
|---------------------------|------------------------|
| Designed by C. G. MANN | Scale AS SHOWN |
| Drawn by M. J. MANN | Check by C. G. MANN |
| Approved by C. G. MANN | Date 5/8/07 |


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT

GRADING AND DRAINAGE PLAN


| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |






EXCAVATION TO BE PAID UNDER ITEM 204.20
TRENCH EXCAVATION OF EARTH OR ITEM 204.21
EXCAVATION OF ROCK

A
24 CULVERT IN TRENCH - TYPICAL
SCALE = NONE




EXCAVATION TO BE PAID UNDER
ITEM 203.19 COMMON EXCAVATION OR
ITEM 203.16 ROCK EXCAVATION

B
24 DROP INLET/MANHOLE PLACEMENT
(TYPICAL)
SCALE = NONE



C
24 CHANGE ELEVATION OF MANHOLE
OR DROP INLET
SCALE = NONE



D
24 CULVERT/UNDERDRAIN INSTALLATION IN
EXISTING MANHOLE OR DROP INLET
SCALE = NONE



| | | | |
|------|------|-------------|----------|
| DATE | REV. | DESCRIPTION | FILE NO. |
| | | | |
| | | | |
| | | | |


RUTLAND STATE AIRPORT
CLARENDON, VERMONT
DRAINAGE DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

Designed by: Date: 8/2/97
Checked by: M. MICHALA 3/97
Approved by: J. P. MOORE 8/2/97

Scale: HS - AS SHOWN
VS - AS SHOWN
Date: 8/2/97
Sheet 24 Of 83

Sheet No. **24**







| | |
|-----------|-------------|
| DATE | DESCRIPTION |
| REV. DATE | DESCRIPTION |
| Job No. | Revision |

RUTLAND STATE AIRPORT
CLARNDON, VERMONT

SEDIMENTATION / EROSION
CONTROL DETAILS

URS Colner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|---------------------------------|----------------------------|
| Checked By: DAV | Date: 5/2/97 |
| Drawn By: W. MCDONALD | Date: 5/2/97 |
| Checked By: W. MCDONALD | Date: 5/2/97 |
| Approved By: W. MCDONALD | Date: 5/2/97 |
| Scale: HORIZ. - NONE | Scale: VERT. - NONE |
| Date: 5/2/97 | |
| Sheet 25 of 60 | |
| Sheet No. 25 | |



EROSION AND SEDIMENT CONTROL NOTES

- THE CONTRACTOR SHALL CONSTRUCT ALL EROSION AND SEDIMENT CONTROL MEASURES PER THE APPROVED PLAN AND CONSTRUCTION SEQUENCE AND SHALL MAINTAIN THEM UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL MAINTAIN THEM UNTIL THE REMOVAL OF THE EROSION OR SEDIMENT CONTROL MEASURES BY THE ENGINEER. THE CONTRACTOR SHALL MAINTAIN THEM UNTIL THE REMOVAL OF THE EROSION OR SEDIMENT CONTROL MEASURES BY THE ENGINEER. THE CONTRACTOR SHALL MAINTAIN THEM UNTIL THE REMOVAL OF THE EROSION OR SEDIMENT CONTROL MEASURES BY THE ENGINEER.
- THE CONTRACTOR SHALL MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES UNTIL SUCH TIMES AS THEY ARE REMOVED.
- THE CONTRACTOR SHALL APPLY SEED AND MULCH, OR OTHER APPROVED STABILIZATION MEASURES TO ALL DISTURBED AREAS AND STOCKPILES WITHIN FOURTEEN (14) CALENDAR DAYS AFTER STRIPPING AND GRADING ACTIVITIES HAVE CEASED IN THE AREA. MAINTENANCE SHALL BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION. PERMANENT SOIL STABILIZATION SHALL BE PROVIDED WITHIN SEVEN (7) DAYS OF ESTABLISHMENT OF FINAL GRADE.
- THIS EROSION CONTROL PLAN SHALL BE IMPLEMENTED ON ALL DISTURBED AREAS WITHIN THE CONSTRUCTION SITE. ALL MEASURES INVOLVING EROSION CONTROL PRACTICES SHALL BE INSTALLED IN CONFORMANCE WITH THE VERMONT HANDBOOK FOR SOIL EROSION AND SEDIMENT CONTROL, OR CONSTRUCTION SITES AS PUBLISHED BY THE VT. GEOLOGICAL SURVEY.
- DURING THE PERIOD OF CONSTRUCTION ACTIVITY, ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED BY THE CONTRACTOR. AT THE COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL COMPLY WITH THE VERMONT HANDBOOK FOR SOIL EROSION AND SEDIMENT CONTROL, OR CONSTRUCTION SITES AS PUBLISHED BY THE VT. GEOLOGICAL SURVEY.
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE REMOVED AND DISPOSED OF WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY PRACTICES ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE STABILIZED OR REMOVED TO PREVENT FURTHER EROSION.
- EROSION CONTROL DEVICES REMOVED DURING GRADING OPERATIONS SHALL BE PUT BACK IN PLACE AT THE END OF THE DAY OR DURING INCLEMENT WEATHER AS DIRECTED BY THE ENGINEER.
- STREAMS INCLUDING BEE AND BANKS SHALL BE REESTABLISHED IMMEDIATELY AFTER CHANNEL WORK IS COMPLETED, INTERRUPTED, OR STOPPED.
- NO NEW EROSION DEVICES OR ANY OTHER MATERIAL SHALL BE DAMAGED OR PLACED INTO A WATER COURSE OR INTO SUCH PROXIMITY THAT IT MAY BEADILY SLOUGH, SLIP, OR ERODE INTO WATER COURSES. THE EROSION DEVICES OR PLACING IS AUTHORIZED BY THE ENGINEER AND WHEN APPLICABLE, THE U.S. ARMY CORPS OF ENGINEERS, FOR SUCH PURPOSES AS, BUT NOT LIMITED TO, CONSTRUCTION OF BRIDGES, DAMS, AND EROSION CONTROL STRUCTURES.
- PERMANENT SEEDING SHALL BE DONE BETWEEN APRIL 30 AND SEPTEMBER 15. IF SEEDING IS DONE AT OTHER TIMES, IT SHALL BE CLASSIFIED AS "TEMPORARY SEEDING." PERMANENT SEED SHALL CONFORM TO THE SEEDING MIXTURE STATED ON SHEET 7. TEMPORARY SEEDING SHALL CONSIST OF FERTILIZING, WATERING AND SEEDING PLACED AT RATES IN ACCORDANCE WITH THE SPECIFICATIONS. PERMANENT SEEDING AND MULCHING SHALL BE PAID FOR UNDER 651-15 AND 651-25 RESPECTIVELY. TEMPORARY SEED, MULCH, AND FERTILIZER FOR EROSION AND SEDIMENT CONTROL SHALL BE PLACED IN ACCORDANCE WITH THE SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR TEMPORARY SEEDING OR MULCHING.
- SURFACE DRAINAGE FLOWS OVER UNSTABILIZED CUTS AND FILL SLOPES SHALL BE CONTROLLED BY EITHER PREVENTING DRAINAGE FLOWS TRAVELING THE SLOPES OR BY INSTALLING PROTECTIVE DEVICES TO LIMIT THE WATER CONCENTRATION BY THE SLOPES. SILES SHALL BE INSTALLED AND MAINTAINED AT THE TOP OF CUTS OR FILL SLOPES UNTIL THE SLOPE AND DRAINAGE AREA TO IT IS FULLY STABILIZED. EROSION CONTROL DEVICES SHALL BE REMOVED AND FINAL GRADING DONE TO PROMOTE SHEET FLOW DRAINAGE. PROTECTIVE MEASURES MUST BE PROVIDED AT POINTS OF CONCENTRATED FLOW WHERE EROSION IS LIKELY TO OCCUR.
- ALL POINTS OF CONSTRUCTION INGRESS AND EGRESS IN UNPAVED AREAS SHALL BE STABILIZED AND PROTECTED TO PREVENT TRACKING OF MUD ONTO PUBLIC OR PRIVATE ROADWAYS.
- IF ROADWAYS ACCUMULATE DEBRIS, THE CONTRACTOR SHALL USE A POWER BROOM TO REMOVE THE SEDIMENT TO THE SATISFACTION OF THE ENGINEER.
- SALVAGED TOPSOIL WILL BE PLACED ON WELL DRAINED LAND AWAY FROM STREAMS IN ACCORDANCE WITH APPROVED EROSION AND SEDIMENT CONTROL MEASURES. IT SHALL BE PLACED IN NEAT PILES. THE CONTRACTOR WILL PROVIDE AN ADEQUATE QUANTITY OF SILT FENCE TO CONTROL THE PERIMETER OF THE STOCKPILE. THE CONTRACTOR, WITH THE APPROVAL OF THE ENGINEER, MAY CONSTRUCT AN EARTH DICE IN LIEU OF SILT FENCE.

SITE DATA

PROJECT DESCRIPTION:
AIRPORT DEVELOPMENT TO INCLUDE PAVING, CLEARING AND GRUBBING, EARTHWORK, STORM DRAINAGE, AND UTILITIES.

TOTAL SITE AREA:
AREA WITHIN LIMITS OF WORK APPROX. 48 ACRES.



EXISTING SOILS:
SOME SILTY SAND WITH TRACES OF GRAVEL.

EROSION CONTROL MEASURES TO BE INSTALLED:
- INFORMATION OBTAINED FROM BORINGS DRILLED BY GREEN MOUNTAIN BORING DURING NOVEMBER 1996

REMARKS:
CONSTRUCTION TO COMMENCE SUMMER 1997, AND TO BE COMPLETED FALL, 1997, WITH THE IMPLEMENTATION OF EROSION CONTROL MEASURES TO BE THE FINEST PHASE OF ACTIVITY AND TO CONTINUE THROUGHOUT PROGRESS OF PROJECT.

RECEIVED BY:
MILL, RIVER, OTHER CREEK

MATCH LINE SHEET



- MARKING NOTES**
1. BARRI MARKING: MARKING TO BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG. MARKING TO BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG.
 2. CENTERLINE: MARKING TO BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG.
 3. LANE MARKING: MARKING TO BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG.
 4. SET VERT STAKING MARKING AT - 10' & 11' DETAILS.
 5. THRESHOLD MARKING SHALL BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG.
 6. THRESHOLD MARKING SHALL BE WHITE, 18" HIGH, 4" WIDE AND 12" LONG.
 7. IN THE EVENT OF A CHANGE IN THE MARKING, THE CONTRACTOR SHALL BE AT THE DIRECTION OF THE CONTRACTOR.
 8. CONTRACTOR TO REMOVE 2 1/2" HIGH LINES AT TALKING SIGN 200' & 200' ON THE R.

A/P 3-30-012-11

| | |
|------------------------------|--------------|
| Designed by S. G. GARDNER | Date 2/97 |
| Drawn by K. MICHALA | Date 2/97 |
| Checked by S. GARDNER | Date 3/97 |
| Approved by K. MICHALA | Date 3/97 |

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
PAVEMENT MARKING
PLAN

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. 98122.00 File No. 1/98122.00




NOTES:

1. ALL RUNWAY & THRESHOLD LIGHTS (MIRLS) AND TAXIWAY LIGHTS (MITLS) TO BE MEDIUM INTENSITY (0.5 AMP, 3 STEP).
2. EXISTING RUNWAY 1-19 MIRLS INCLUDING BASE AND CONDUIT (TO THE EXTENT POSSIBLE) TO BE REMOVED AND STORED ON THE AIRPORT AT THE AIRPORT AT THE DIRECTION OF THE ENGINEER.
3. ALL RUNWAY, THRESHOLD, & TAXIWAY LIGHTS AND CABLES TO BE PLACED 10' OFF EDGE OF PAVEMENT.
4. ALL RUNWAY AND TAXIWAY LIGHTS TO BE NUMBERED CONSECUTIVELY AS SHOWN.
5. MULTIPLE CONDUCTOR RUNS SHALL BE IN SAME CONDUIT AND/OR TRENCH WHERE POSSIBLE.
6. RUNWAY EDGE LIGHTS, TO BE L-801 (30W) QUARTZ (EITHER CLEAR LENS OR CLEAR/AMBER LENS), EXCEPT R45, R46 & R86 A TO BE IN PAVEMENT EDGE LIGHTS, L-800C (40W).
7. ALL TAXIWAY LIGHTS TO BE L-801T (30W) INCANDESCENT. (BLUE FILTER)
8. RUNWAY THRESHOLD LIGHTS TH1 THRU TH3 TO BE L-801 SE (120W) QUARTZ (RED/GREEN FILTER).
9. RUNWAY THRESHOLD LIGHTS TH38 THRU TH43 TO BE L-801 E (40W) QUARTZ (RED/GREEN FILTER).
10. CONCRETE BASES FOR EXISTING SIGNS TO BE REMOVED DURING CONSTRUCTION/ GRADING OF RUNWAY SAFETY AREAS.
11. R #116, #119, #147, #148 TO REMAIN IN PLACE.

NOTE:
 RUNWAY 1-19 WIRING CIRCUIT
 ...R12 - R13 - T018A - T018 - R14
 - DM #4 - R15...
 RUNWAY 13-31 WIRING CIRCUIT
 ...R116 - T04 - T03 - R116..."


NOTE:
 RUNWAY 1-19 WIRING CIRCUIT
 HOMERUN - R85 - R84...
 TAXIWAY "B" WIRING CIRCUIT
 ...T313 - T314 - T318 - T08 - T05...
 RUNWAY 13-31 WIRING CIRCUIT
 ...R148 - T07 - T09 - R147..."

NOTE:
 RUNWAY 1-19 WIRING CIRCUIT
 VAULT R86A - T014A - T014 - R88..."



NOTE:
 RUNWAY 1-19 WIRING CIRCUIT
 ... R19 - R20 - DM #3 - R21 ..."

MATCH LINE SHEET 27



LEGEND

- EXISTING RUNWAY AND TAXIWAY LIGHTS
- EXISTING TAXIWAY SIGNS
- NEW THRESHOLD LIGHTS (180° GREEN / 180° RED LENS)
- NEW TAXIWAY LIGHTS (BLUE FILTER)
- NEW RUNWAY LIGHTS (CLEAR LENS)
- NEW RUNWAY LIGHTS (180° CLEAR / 180° AMBER LENS)
- TO #1 RELOCATED TAXIWAY SIGN
- UNDERGROUND CONCRETE ENCASED DUCT & MARKERS
- ▲ 8" Ø X 8" COPPERCLAD GROUND ROD
- RELOCATED GOALS

- NOTE:**
- 1 REMOVE EXISTING TAXIWAY LIGHTS T19, T20, T23, T24
 - 2 TAXIWAY C WIRING CIRCUIT ... T25 - T424 - T423 - T422 T010 - T011 - T421 - T420 - T419 - T18 ...
 - 3 TR/W 1-19 WIRING CIRCUIT ... R81 - R80 ...

MATCH LINE SHEET 29




| REV. | DATE | DESCRIPTION | DATE | NO. |
|------|------|-------------|------|-----|
| | | | | |

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
 RUNWAY LIGHTING PLAN

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK





| | |
|--------------------------|-------------------------|
| Prepared By: [Signature] | Checked By: [Signature] |
| Scale: HOR. = 1" = 50' | VERT. = NONE |
| Date: 8/18/97 | Sheet 28 Of 43 |
| Sheet No | 28 |



- LEGEND**
- EXISTING POWER AND TRAVEL LIGHTS
 - EXISTING TRAVEL SIGN
 - NEW TRIPPOLE LIGHTS (140' SPACING / 140' RISE LIGHT)
 - NEW TRAVEL LIGHTS (140' SPACING)
 - NEW TRAVEL LIGHTS (140' RISE LIGHT)
 - NEW TRAVEL LIGHTS (140' SPACING / 140' RISE LIGHT)
- If relocated TRAVEL SIGN
- PROPOSED CONCRETE PADDED MARK & NUMBER
- ▲ 4" x 4" x 1" CONCRETE MARK NO.
 - RELOCATED MARK

NOTES
 1. SEE SHEET 28 FOR THE "EXISTING" PLAN.

- NOTES**
1. TO BE REMOVED: EXISTING LIGHTS (140' SPACING) AND TRAVEL LIGHTS (140' RISE LIGHT).
 2. EXISTING TRAVEL SIGN TO BE REMOVED AND STAMPED ON.
 3. NEW TRIPPOLE LIGHTS AND TRAVEL LIGHTS AND MARKS TO BE INSTALLED AS SHOWN.
 4. ALL TRIPPOLE LIGHTS AND TRAVEL LIGHTS TO BE MARKED CONSPICUOUSLY.
 5. AS SHOWN.
 6. TRIPPOLE LIGHTS AND TRAVEL LIGHTS TO BE MARKED CONSPICUOUSLY.
 7. TRIPPOLE LIGHTS AND TRAVEL LIGHTS TO BE MARKED CONSPICUOUSLY.
 8. TRIPPOLE LIGHTS AND TRAVEL LIGHTS TO BE MARKED CONSPICUOUSLY.
 9. TRIPPOLE LIGHTS AND TRAVEL LIGHTS TO BE MARKED CONSPICUOUSLY.
 10. CONCRETE MARKS FOR EXISTING SIGN TO BE REMOVED DURING CONSTRUCTION.



AP 3-50-015-11

| | | | | |
|---|--|--|--|--|
| <p>URS Greiner, Inc. 3 MARCUS BOULEVARD ALBANY, NEW YORK</p> | | <p>RUTLAND STATE AIRPORT CLARENDON, VERMONT</p> | | |
| <p>Runway Lighting Plans</p> | | <p>REV. DATE DESCRIPTION</p> | | |
| <p>Job No. 100123</p> | | <p>The No. 100123</p> | | |

MATCH LINE SHEET 29


NOTES:

- ALL RUNWAY & THRESHOLD LIGHTS (MIRLS) AND TAXIWAY LIGHTS (MITLS) TO BE MEDIUM INTENSITY (0.8 AMP, 3 STEP).
- EXISTING RUNWAY 1-19 MIRLS TO BE REMOVED AND STORED ON THE AIRPORT AT THE DIRECTION OF THE ENGINEER.
- ALL RUNWAY, THRESHOLD, & TAXIWAY LIGHTS AND CABLES TO BE PLACED 10' OFF EDGE OF PAVEMENT.
- ALL RUNWAY AND TAXIWAY LIGHTS TO BE NUMBERED CONSECUTIVELY AS SHOWN.
- MULTIPLE CONDUCTOR RUNS SHALL BE IN SAME CONDUIT AND/OR TRENCH WHERE POSSIBLE.
- RUNWAY EDGE LIGHTS, TO BE L-861 (30W) QUARTZ (EITHER CLEAR LENS OR CLEAR/AMBER LENS), EXCEPT R46, R48 & R68 A TO BE IN PAVEMENT EDGE LIGHTS, L-860C (45W).
- ALL TAXIWAY LIGHTS TO BE L-861T (30W) INCANDESCENT. (BLUE FILTER)
- RUNWAY THRESHOLD LIGHTS TH1 THRU TH3 TO BE L-861 SE (120W) QUARTZ (RED/GREEN FILTER).
- RUNWAY THRESHOLD LIGHTS TH38 THRU TH43 TO BE L-861 E (45W) QUARTZ (RED/GREEN FILTER).
- CONCRETE BASES FOR EXISTING SIGNS TO BE REMOVED DURING CONSTRUCTION/ GRADING OF RUNWAY SAFETY AREAS.
- EXISTING GOALS AND VASI FOUNDATIONS TO BE REMOVED. PAYMENT TO BE MADE UNDER ITEM 204-21, TRENCH EXCAVATION OF ROCK @ 2 CY/EACH FOUNDATION.
- SEE SHEETS 39-41 FOR ODALS DETAILS.
- SEE SHEET 34 FOR VASI DETAILS.
- EXISTING ODALS & VASI CABLES ARE DIRECT BURIAL. HAND DIGGING WILL BE REQUIRED AROUND THESE CABLES. POWER TO ODALS AND VASI ARE SUPPLIED FROM FAA EQUIPMENT BUILDING NORTH OF RUNWAY ON VT 103. CONTRACTOR TO COORDINATE WITH FAA MAINTENANCE AT 802-881-8723.

NOTE:
 RUNWAY 1-19 WIRING CIRCUIT
 ...R30 - DM #1 - R31 - T012 - R32 ..."

NOTE:
 TAXIWAY "E" WIRING CIRCUIT
 ... T338 - T339A - T340A - T340B - T340C - T013 - T341A - T341 ..."

| ODAL SCHEDULE | | |
|---------------|-------------------|--|
| UNIT # | EXISTING LOCATION | REMARKS |
| R | 150' RT 150+208 | RELOCATE TO 125' RT 183+10 |
| 1L | 150' LT 150+208 | RELOCATE TO 125' LT 183+10 |
| 2 | € 183+008 | REMOVE EXISTING ODAL & TOWER |
| 3 | € 186+000 | MODIFY TOWER AND L.I.R MAST TO ELEVATION 732.0 RE-USE ODAL UNIT #3. |
| 20 | € 186+008 | INSTALL NEW TUBULAR STEEL TOWER AND L.I.R MAST. RE-USE ODAL UNIT #2. |



- LEGEND**
- EXISTING RUNWAY AND TAXIWAY LIGHTS
 - EXISTING TAXIWAY SIGNS
 - ◐ NEW THRESHOLD LIGHTS (180° GREEN / 180° RED LENS)
 - ◑ NEW TAXIWAY LIGHTS (BLUE FILTER)
 - NEW RUNWAY LIGHTS (CLEAR LENS)
 - ◐ NEW RUNWAY LIGHTS (180° CLEAR / 180° AMBER LENS)
 - ◑ To #1 RELOCATED TAXIWAY SIGN
 - ◓ UNDERGROUND CONCRETE ENCASED DUCT & MARKERS
 - ▲ 8/8" x 8' COPPERCLAD GROUND ROD
 - RELOCATED ODALS



| REV. | DATE | DESCRIPTION | FILE NO. (IF APPLICABLE) |
|------|------|-------------|--------------------------|
| | | | |
| | | | |
| | | | |

RUTLAND STATE AIRPORT
 CLAREMONT, VERMONT

RUNWAY LIGHTING PLANS


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

Scale: HOR. - 1" = 30'
 VERT. - NONE

Date: 8/6/97

Sheet 30 of 33

Sheet No. **30**




NOTE:
ADDITIONAL CONDUITS MAY BE
PLACED IN SAME TRENCH @ 3"
SPACING. MAX. NUMBER OF
CABLES / CONDUIT PER M.F.C.

* FINE BORROW MATERIAL REASONABLY FREE FROM
LOAM, CLAY OR ORGANIC MATERIAL.
MAXIMUM SIZE = 1/2"

CONDUIT TRENCH DETAIL (TYP)

NOT TO SCALE




NOTE:
1. PLACE 2" PVC CONDUIT & COUNTERPOISE
IN EXISTING 4" PCC ENCASED DUCT.
FULL LENGTH. USE EXISTING SPARE
(EMPTY) DUCT IF AVAILABLE.
2. HAND EXCAVATE AROUND EXISTING DUCT.
EXISTING CABLES MAY BE DIRECT BURIAL.
3. REPLACE EXISTING PCC DUCT MARKERS,
AS SHOWN.

CONDUIT/DUCT DETAIL (TYP)

NOT TO SCALE


LETTER & NUMBER
TO BE PERMANENT
PART OF TAG.
R = RUNWAY
T = TAXIWAY
TH = THRESHOLD
TO = TAXIWAY SIGNS
DM = DISTANCE SIGNS



*SEE LIGHTING PLAN FOR
FIXTURE DELINEATION

FIXTURE IDENTIFICATION TAG (TYP)

NOT TO SCALE



ELECTRICAL HANDHOLE (TYP)

NOT TO SCALE






| | | |
|------|-------------|---------------------|
| DATE | DESCRIPTION | FILE NO. 11/21/2008 |
| DATE | DESCRIPTION | FILE NO. 11/21/2008 |
| DATE | DESCRIPTION | FILE NO. 11/21/2008 |
| DATE | DESCRIPTION | FILE NO. 11/21/2008 |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT

RUNWAY LIGHTING DETAILS





URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|------------------|-------------------|
| Designed by: CJK | Checked by: J/07 |
| Drawn by: J/07 | Reviewed by: J/07 |
| Scale: HS = N/A | VS = N/A |
| Date: 6/8/07 | |
| Sheet 22 Of 25 | |
| Sheet No. | 32 |



GENERAL NOTES:

1. VIBRATE CONCRETE BACKFILL TO ENSURE THERE ARE NO VOIDS.
2. CONCRETE TO CONFORM TO VAOT SPECIFICATIONS SECTION 501, CLASS B, 3/4" MAX SIZE AGGREGATE
3. PRIOR TO ASPHALT PAVING, COVER MUD PLATE WITH A SHINGLE OR ANOTHER THIN ARTICLE WHEN TACK COAT IS APPLIED PRIOR TO PAVING. BEFORE PAVING COMMENCES, REMOVE SHINGLE AND LIGHTLY WIPE DOWN MUD PLATE WITH VEGETABLE OIL.
4. TIGHTEN ALL BOLTS TO THE TORQUE SPECIFIED BY THE MANUFACTURER. DO NOT REUSE SHIPPING BOLTS TO INSTALL COVERS.



INSTALLATION OF IN PAVEMENT LIGHTING (L-850-C)



| | | |
|------|-------------|------|
| DATE | DESCRIPTION | REV. |
| | | |
| | | |
| | | |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
RUNWAY LIGHTING DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | |
|-----------------------|------------------|--------------------|
| Checked by: S. P. ... | Drawn by: M. ... | Checked by: J. ... |
| | | |

Date: 6/19/87
Sheet 23 of 65
Sheet No: 33




| | |
|-------------|-------------|
| PROJECT NO. | 14-0000-003 |
| DATE | |
| JOB NO. | 14-0000-003 |
| DESCRIPTION | |




RUTLAND STATE AIRPORT
CLARENDON, VERMONT
ELECTRICAL PLANS
VASI MOUNTING DETAILS


Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|--------------------------|
| Checked by | DATE |
| C. J. White | 2/27 |
| Drawn by | DATE |
| J. J. White | 2/27 |
| Checked by | DATE |
| J. J. White | 2/27 |
| Approved by | DATE |
| R. J. White | 2/27 |
| Scale | AS NOTED VERT. - NONE |
| Date | 5/9/77 |
| Sheet No. | 34 of 66 |
| Sheet No. | 34 |




- NOTES:**
1. RELOCATE EXISTING VASI-4 UNITS FROM EXISTING FOUNDATIONS TO NEW LOCATION.
 2. REMOVE EXISTING VASI FOUNDATIONS.
 3. ABANDON OLD CABLES IN PLACE.
 4. SEE SHEETS 38-41 FOR ODALS RELOCATION DETAILS.
 5. COORDINATE POWER SHUT-OFF AND SYSTEM FLIGHT CHECK WITH FAA/FAE MAINTENANCE. TEL 802-851-8733.
 6. ALL CABLES TO BE PLACED IN SAME TRENCH WHERE POSSIBLE.






D WALKWAY DETAIL
N.T.S.





A ODAL UNIT 20
SCALE: 1" = 50'

- NOTES:**
1. ALL EXCAVATION, BACKFILL AND RESTORATION FOR UNDERGROUND CABLES FROM UNIT 8 TO UNIT 20 TO BE COMPLETED IN ONE (1) WORK DAY TO MINIMIZE EROSION/RUNOFF.
 2. ALL DISTURBED AREAS TO BE TOPSOILED & SEEDING USING THE FOLLOWING SEED MIX:
85% FOOT TROPICAL 35% RED TOP
15% RED CANARY GRASS 50% SEED TO BE SPREAD @ A RATE OF 0.75LBS/1000 SF.
 3. TEMPORARY ACCESS ROAD SEE EROSION CONTROL DETAILS SHEET 25.
 4. PLACE 2 12" P. 6" SLEEVES APPROX. 2' BELOW GRADE PARALLEL TO EXISTING WATERLINE TO EXISTING WATERLINE. NOT A SEPARATE PAY ITEM.



C ODAL UNIT PLAN
N.T.S.



B ODAL TOWERS - PROFILE
N.T.S.

- GENERAL NOTES:**
1. CONTRACTOR TO KEEP ALL GATES CLOSED WHEN NOT IN USE, TO KEEP LIVESTOCK FROM ESCAPING.
 2. RELOCATE EXISTING 1/2 FARM GATES TO ALIGN WITH WATERLINE EASEMENTS AS DIRECTED BY THE ENGINEER. NOT A SEPARATE PAY ITEM.





| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

RUTLAND STATE AIRPORT
CLAREMONT, VERMONT


ODALS - PLAN & PROFILE

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | |
|------------------------------|------------------------------|
| Designed by: <i>W. L. C.</i> | Checked by: <i>W. L. C.</i> |
| Drawn by: <i>W. L. C.</i> | Approved by: <i>W. L. C.</i> |
| Scale: HORIZ. - 1" = 100' | VERT. - 1" = 50' |
| Date: 6/2/77 | Sheet 30 OF 35 |




DETAIL 2




DETAIL 3




DETAIL 4



DETAIL 5




DETAIL 6




DETAIL 7

ODALS FOUNDATION DETAILS
ODALS UNITS #1R & #1L
125' LT & RT OF STA. 153+20

- NOTES:**
- EXISTING FOUNDATIONS UNITS #2 & #3 TO BE ABANDONED IN PLACE.
 - ODALS ELECTRICAL CABLES TO BE RE-ROUTED TO NEW LOCATION.
 - EXISTING ODALS UNITS TO BE REMOVED FROM EXISTING FOUNDATIONS AND PLACED ON NEW FOUNDATIONS.
 - ALL CONCRETE TO BE CLASS B, CONFORMING TO SECTION 501. STRUCTURAL CONCRETE, VAOT SPECIFICATIONS.
 - EXISTING UNDERGROUND (DIRECT BURIAL CABLES) 3-1/2" Ø ØB, SOON. 1-Ø ØR Ø1Ø - TELEPHONE CABLE, & ØØ BARE COPPER BETWEEN UNITS. SEE UNIT WIRING DIAGRAM.
 - USE ANTI-SEIZE COMPOUND ON ALL THREADS.
 - ALL ANCHOR BOLTS, NUTS & WASHERS SHALL BE HOT DIP GALVANIZED PER ASTM - 13 & ASTM - 325.



ANCHOR BOLT PLAN
 DETAIL 8



ANCHOR BOLTS
 DETAIL 9

ODALS FOUNDATION DETAILS
UNIT #3
STATION 168+00



| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

Job No. 11579(168+00)
 Job No. 11579(168+00)

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
ODALS FOUNDATION DETAILS

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK


| | |
|-----------------------|------|
| Checked by: J. J. ... | 3/27 |
| Drawn by: ... | 3/27 |
| Created by: ... | 3/27 |
| | |

Scale: NS - AS SHOWN
 VS - AS SHOWN

Date: 4/1/07


Sheet 26 Of 63

Sheet No




PLAN

NOTE:
A 36" DIAMETER PIER MAY BE USED, AT THE CONTRACTOR'S OPTION IN LIEU OF THE SQUARE PIER.



36" DIA. FOUNDATION PIER



SECTION

FOUNDATION NOTES

- CONCRETE TO CONFORM TO VAOT SPECIFICATIONS SECTION 501 - STRUCTURE CONCRETE, CLASS A.
- REINFORCING STEEL TO CONFORM TO VAOT SPECIFICATIONS SECTION 507 - REINFORCING STEEL. STEEL TO BE ASTM A615, GRADE 60, EXCEPT STIRRUPS AND TIES TO BE GRADE 40.
- REINFORCEMENT SHALL BE TIED SECURELY IN PLACE BEFORE PLACING CONCRETE USING APPROVED CHAIRS AND SPACERS. NO BARS SHALL BE CUT OR OMITTED IN THE FIELD WITHOUT THE APPROVAL OF THE ENGINEER. USE PLASTIC TIPPED ACCESSORIES IN CONCRETE EXPOSED TO WEATHER, WATER OR VIEW.
- THE CONTRACTOR SHALL INSTALL ALL ANCHORS, BOLTS, PLATES, WAILERS, SLOTS, CHASES, PIPE SLEEVES, ETC., AS REQUIRED BY OTHER TRADES. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS BEFORE SETTING SCREEDS AND FORMS.
- FOOTINGS SHALL REST ON SUITABLE UNDISTURBED SOIL OR COMPACTED GRANULAR FILL HAVING A MINIMUM BEARING CAPACITY OF 3000 PSF. THE ENGINEER SHALL BE NOTED PROMPTLY OF ANY WEAK STRATA, WATER CONDITIONS OR OTHER POOR BEARING CONDITIONS.
- UNLESS OTHERWISE NOTED, ALL FOOTINGS AND PIERS SHALL BE CENTERED UNDER SUPPORT MEMBERS.
- CONCRETE TEMPERATURES DURING THE FIRST SEVEN DAYS SHALL BE MAINTAINED BETWEEN 50 F AND 90 F. RAPID DRYING MUST BE PREVENTED. ALL SURFACES SHALL BE KEPT CONTINUOUSLY MOIST FOR A MINIMUM OF SEVEN DAYS.
- BACKFILLING AGAINST PIERS SHALL BE DONE BY PLACING LEVEL LAYERS ALL AROUND THE PIER. PIERS MUST BE AT LEAST SEVEN DAYS OLD BEFORE BACKFILLING.
- SELECT BACKFILL SHALL:
 - CONFORM TO VAOT 704.04.
 - BE PLACED IN MAXIMUM 6" LEVEL LIFTS AND COMPACTED TO 90% MAXIMUM DENSITY AT OPTIMUM MOISTURE CONTENT AS DEFINED BY ASTM D-1557.
- CONTRACTOR TO DESIGN, FURNISH AND INSTALL ALL TEMPORARY SHEETING, SHORING AND BRACING NECESSARY TO COMPLETE THE CONSTRUCTION.
- THE CONTRACTOR SHALL PROVIDE THE NECESSARY EQUIPMENT AND Dewater THE SITE TO FACILITATE CONSTRUCTION AND SAFE WORKING CONDITIONS.
- SHOP DRAWINGS PREPARED IN ACCORDANCE WITH ACI STANDARDS SHALL BE REQUIRED FROM THE CONTRACTOR FOR REINFORCING STEEL PRIOR TO CONSTRUCTION.
- DESIGN LOADS:

MOMENT = 228 K-FT.
VERTICAL SHEAR = 6250 LBS.
HORIZONTAL SHEAR = 4380 LBS.




| | | |
|------|----------|-------------|
| DATE | REVISION | DESCRIPTION |
| | | |
| | | |
| | | |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT


ODALS TOWER FOUNDATION DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | |
|-----------------------|----------------------|
| Checked by: <i>JS</i> | Scale: VS - AS SHOWN |
| D. P. ANDERSON 7/97 | VS - AS SHOWN |
| Drawn by: <i>JS</i> | Date: 6/9/07 |
| Checked by: <i>JS</i> | Sheet 27 Of 60 |
| Checked by: <i>JS</i> | Sheet No |




PLAN
N.T.S.




PLAN
N.T.S.



ELEVATION
ODALS UNIT 1R & 1L
N.T.S.




STRUCTURAL LEG-DETAIL 'B'
N.T.S.




ELEVATION
N.T.S.


ODAL UNIT #3
* REUSE EXISTING TOWER-
ADJUST TO HEIGHT



ELEVATION
N.T.S.



PLAN
EQUIPMENT PAD FOUNDATION DETAILS



STRUCTURAL LEG-DETAIL 'A'
N.T.S.

- NOTES:**
1. REFER TO FACILITY LAYOUT PLAN FOR LIGHT FIXTURE ELEVATIONS.
 2. REFER TO SHEET 35' FOR TOP ELEVATION OF CONCRETE FOUNDATION.
 3. REFER TO CABLE LAYOUT PLAN FOR ROUTING.
 4. USE ANTI-SEIZE COMPOUND ON ALL PIPE THREADS.
 5. RELOCATE ALL EXISTING EQUIPMENT. RE-USE TO THE EXTENT POSSIBLE. CONTRACTOR TO SUPPLY NEW PCC FOUNDATIONS AND ALL CONDUIT, FITTINGS, CABLES, ETC.
 6. CONTRACTOR TO INSPECT ALL EQUIPMENT PRIOR TO RELOCATING. EXISTING DAMAGE TO BE NOTED. CONTRACTOR WILL BE RESPONSIBLE FOR REPLACING OR REPAIRING ALL DAMAGE CAUSED BY HIS FORCES DURING RELOCATION & RE-INSTALLATION.
 7. CONTRACTOR TO VERIFY NEW ODAL UNIT ELEVATION AND TOWER HEIGHT PRIOR TO INSTALLATION.



| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

JOB NO. - F49322-09
E.T. No. P-16647/10/07

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
ODALS - FLASHER MOUNTING
DETAILS

URS Greiner, Inc
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|------------------|--------------------|
| Drawn by: JRM | Scale: N.T.S. |
| Checked by: JRM | Date: 5/5/07 |
| Approved by: JRM | Sheet No. 38 of 68 |
| | Sheet No. 38 |



| |
|---------------------|
| FILE NO. P-16030004 |
| DESCRIPTION |
| REV. DATE |
| JOB NO. P-160323-00 |


RUTLAND STATE AIRPORT
CLARENDON, VERMONT

ODALS UNIT #20
WIRING AND EQUIPMENT MOUNTING

URS Greiner, Inc
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|------------------|---------------|
| DESIGNED BY: RVT | DATE: 1/11/85 |
| DRAWN BY: RVT | DATE: 1/11/85 |
| CHECKED BY: RVT | DATE: 1/11/85 |
| APPROVED BY: RVT | DATE: 1/11/85 |
| SCALE: N.T.S. | |
| DATE: 1/11/85 | |
| SHEET 39 OF 45 | |
| SHEET NO. | 39 |

RE-USE EXISTING ODALS FLASHING FROM UNIT #2




LOW IMPACT RESISTANCE ASSEMBLY

ELEVATION
N.T.S.

* CONTRACTOR TO VERIFY ELEVATIONS
SEE NOTES SHEET 30


NOTES:

1. MAKE ALL TERMINATIONS IN HANDHOLE USING WIRE NUTS OR BURNDY CONNECTORS AND LEAVE 3' OF SLACK. TAG ALL CONTROL CABLES IN HANDHOLES OR JUNCTION BOXES SHALL BE TAGGED AS TO ORIGIN OR DESTINATION AND COLOR CODED (POWER) OR NUMBERED (CONTROL).
2. TIE CABLE HARNESS EVERY 3' TO TOWER OR GUIDE CAGE FROM CONTROL BOX TO BOTTOM OF CAGE USING BLACK WEATHER RESISTANT CABLE TIES TYPE PLT. FROM BOTTOM OF GUIDE CAGE TO LIR TUBE LEAVE LOOSE. SEE DETAIL 'A' FOR CONNECTION AT LIR TUBE.
3. FOR LAMP HEAD LEVELING PROCEDURE SEE MANUFACTURE INSTRUCTION MANUAL (TI 6350.47).
4. HIGH MAST TOWER FOR ODAL UNIT 20 ONLY.





CABLE CLAMP (TYP.)
ACTUAL SIZE CLAMP REQ'D
MAY BE DIFFERENT

DETAIL 'A'
N.T.S.






DETAIL 'B'
N.T.S.




CABLE CLAMP
ACTUAL SIZE
CLAMP REQ'D
MAY BE DIFFERENT



GUIDE CAGE MOUNTING DETAIL
SCALE: 3" = 1'-0"



GUIDE CAGE
N.T.S.



GUIDE CAGE MOUNTING BRACKET
N.T.S.

STATE OF VERMONT
DEPARTMENT OF TRANSPORTATION
RUTLAND STATE AIRPORT
CLARENDON, VERMONT

| | | | | |
|------|------|-------------|--------------------|--|
| | | | | |
| REV. | DATE | DESCRIPTION | FILE NO. P/PROJECT | |
| | | | | |
| | | | | |
| | | | | |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT

GOALS UNIT #6
L.I.R. GUIDE CAGE DETAILS

URS Greiner, Inc
3 MARCUS BOULEVARD
ALBANY, NEW YORK


| | | | | |
|--------------|----|------------|------|-------|
| DATE PLOTTED | BY | CHECKED BY | DATE | SCALE |
| | | | | |

SOCIETY AS NOTED


DATE: 8/5/97

SHEET 40 OF 65

SHEET NO
40



ODALS - WIRING DIAGRAM
DETAIL A & B




| | | | |
|------|------|-------------|---------------------|
| REV. | DATE | DESCRIPTION | JOB NO. 11457200000 |
| | | | |
| | | | |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT


ODALS WIRING DIAGRAM

Grainer, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | | |
|--------------------------------|--------------------------------|--------------------------------|--------------------------------|
| Checked by: <i>[Signature]</i> | Checked by: <i>[Signature]</i> | Checked by: <i>[Signature]</i> | Checked by: <i>[Signature]</i> |
| Scale: N.O.R. - AS NOTED | Scale: N.O.R. - AS NOTED | Scale: N.O.R. - AS NOTED | Scale: N.O.R. - AS NOTED |
| Date: 6/8/97 | | | |
| Sheet of 05 | | | |
| Sheet No | | | |



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN





BORINGS AND DRIVE TESTS
SCALE: AS SHOWN

NOTE:

- BORINGS AND DRIVE TESTS WERE TAKEN IN NOVEMBER 1995, AND JAN 97 BY GREEN MOUNTAIN BORING.
- N-BLOWS PER 6 INCH INCREMENT OF PENETRATION OF SAMPLING SPOON OR PENETRATION IN INCHES FOR THE INDICATED BLOWS OF A 140 LB HAMMER FALLING 30". WHERE ROCK IS ENCOUNTERED, PERCENT CORE RECOVERY IS SHOWN. R.Q.D. IS SHOWN IN PARENTHESES.

THE ROCK QUALITY DESIGNATION (R.Q.D.) IS BASED ON A MODIFIED CORE RECOVERY PROCEDURE WHICH, IN TURN, IS BASED INDIRECTLY ON THE NUMBER OF FRACTURES (EXCEPT THOSE DUE DIRECTLY TO DRILLING OPERATIONS) AND THE AMOUNT OF SOFTENING OR ALTERATION IN THE ROCK MASS AS OBSERVED IN THE ROCK CORES FROM A DRILL HOLE. INSTEAD OF COUNTING THE FRACTURES, AN INDIRECT MEASURE IS OBTAINED BY SUMMING THE TOTAL LENGTH OF CORE RECOVERED BY COUNTING ONLY THOSE PIECES OF HARD AND SOUND CORE WHICH ARE 4 INCHES OR GREATER IN LENGTH. THE RATIO OF THIS MODIFIED CORE RECOVERY LENGTH TO THE TOTAL CORE RUN LENGTH IS KNOWN AS THE R.Q.D.

V-ALTERNATE SHADING INDICATES EXTENT OF SOIL OR ROCK LAYERS.
WL-WATER LEVEL READING AT COMPLETION OF BORING.



BORINGS AND DRIVE TESTS LOCATION PLAN
SCALE: 1" = 500'

STATE OF VERMONT
DEPARTMENT OF TRANSPORTATION
RUTLAND STATE AIRPORT
CLAREMONT, VERMONT

| | | | |
|------|------|-------------|-------------------|
| REV. | DATE | DESCRIPTION | JOB No. 114200000 |
| | | | |
| | | | |
| | | | |

BORING LOGS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | | | |
|----------------------|------------------------|-------------------------|-------------------------|-----------------------|
| Drawn by: [initials] | Checked by: [initials] | Reviewed by: [initials] | Approved by: [initials] | Project No. 114200000 |
| | | | | |

Scale: HOR. - AS SHOWN
VERT. - NONE

Date: 6/8/97

Sheet 42 OF 65

Sheet No. **42**

AIP 3-50-0015-11



| | | | | |
|------|------|-------------|----|------|
| REV. | DATE | DESCRIPTION | BY | CHK. |
| | | | | |
| | | | | |
| | | | | |
| | | | | |


RUTLAND STATE AIRPORT
CLARENDON, VERMONT

BORING LOGS


Job No. 11478-2-00

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|----------|
| Designed by | WLG |
| Checked by | WLG |
| Drawn by | WLG |
| Scale | AS SHOWN |
| Date | 5/8/97 |
| Sheet | 43 OF 48 |
| Sheet No. | 43 |



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN

NOTE


1.) BORINGS AND DRIVE TESTS WERE TAKEN IN NOVEMBER 1995, BY GREEN MOUNTAIN BORING.


2.) N- BLOWS PER 6 INCH INCREMENT OF PENETRATION OF SAMPLING SPOON OR PENETRATION IN INCHES FOR THE INDICATED BLOWS OF A 140 LB. HAMMER FALLING 30". WHERE ROCK IS ENCOUNTERED, PERCENT CORE RECOVERY IS SHOWN. R.Q.D. IS SHOWN IN PARENTHESES.

THE ROCK QUALITY DESIGNATION (R.Q.D.) IS BASED ON A MODIFIED CORE RECOVERY PROCEDURE WHICH, IN TURN, IS BASED INDIRECTLY ON THE NUMBER OF FRACTURES (EXCEPT THOSE DUE DIRECTLY TO DRILLING OPERATIONS) AND THE AMOUNT OF SOFTENING OR ALTERATION IN THE ROCK MASS AS OBSERVED IN THE ROCK CORES FROM A DRILL HOLE. INSTEAD OF COUNTING THE FRACTURES, AN INDIRECT MEASURE IS OBTAINED BY SUMMING THE TOTAL LENGTH OF CORE RECOVERED BY COUNTING ONLY THOSE PIECES OF HARD AND SOUND CORE WHICH ARE 4 INCHES OR GREATER IN LENGTH. THE RATIO OF THIS MODIFIED CORE RECOVERY LENGTH TO THE TOTAL CORE RUN LENGTH IS KNOWN AS THE R.Q.D.


V- ALTERNATE SHADING INDICATES EXTENT OF SOIL OR ROCK LAYERS.

WL- WATER LEVEL READING AT COMPLETION OF BORING.







BORINGS AND DRIVE TESTS
SCALE: AS SHOWN



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN



BORINGS AND DRIVE TESTS
SCALE: AS SHOWN




NOTE:

- 1.) BORINGS AND DRIVE TESTS WERE TAKEN IN NOVEMBER 1995, BY GREEN MOUNTAIN BORING.
- 2.) N-BLOWS PER 8 INCH INCREMENT OF PENETRATION OF SAMPLING SPOON OR PENETRATION IN INCHES FOR THE INDICATED BLOWS OF A 140 LB. HAMMER FALLING 30". WHERE ROCK IS ENCOUNTERED, PERCENT CORE RECOVERY IS SHOWN. R.Q.D. IS SHOWN IN PARENTHESES.

THE ROCK QUALITY DESIGNATION (R.Q.D.) IS BASED ON A MODIFIED CORE RECOVERY PROCEDURE WHICH, IN TURN, IS BASED INDIRECTLY ON THE NUMBER OF FRACTURES (EXCEPT THOSE DUE DIRECTLY TO DRILLING OPERATIONS) AND THE AMOUNT OF SOFTENING OR ALTERATION IN THE ROCK MASS AS OBSERVED IN THE ROCK CORES FROM A DRILL HOLE. INSTEAD OF COUNTING THE FRACTURES, AN INDIRECT MEASURE IS OBTAINED BY SUMMING THE TOTAL LENGTH OF CORE RECOVERED BY COUNTING ONLY THOSE PIECES OF HARD AND SOUND CORE WHICH ARE 4 INCHES OR GREATER IN LENGTH. THE RATIO OF THIS MODIFIED CORE RECOVERY LENGTH TO THE TOTAL CORE RUN LENGTH IS KNOWN AS THE R.Q.D.

V-ALTERNATE SHADING INDICATES EXTENT OF SOIL OR ROCK LAYERS.

WL-WATER LEVEL READING AT COMPLETION OF BORING.



| | | | |
|---------|-------------|-------------|----------|
| NO. | DATE | DESCRIPTION | FILE NO. |
| 1 | 8/4/97 | ADD | 11428-00 |
| REV. | DATE | | |
| JOB NO. | PROJECT NO. | | |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT

BORING LOGS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|-------|
| Prepared by | Scale |
| Checked by | Scale |
| Reviewed by | Scale |
| Approved by | Scale |


Scale: HOR. - AS SHOWN
VERT. - NONE

Date: 8/4/97


Sheet 44 Of 68

Sheet No


44



EXISTING LOCALIZER BLDG. EQUIPMENT LAYOUT
SCALE: NONE




SECTION "A-A"
SCALE: NONE



SECTION "B-B"
SCALE: NONE

NOTES:


1. NEMA 1 ENCLOSURE, FUSED 2 POLE, SOLID NEUTRAL, DEAD FRONT, 400 AMP DISCONNECT SWITCH.
2. NEMA 1 ENCLOSURE, 1 PHASE, 3-WIRE, 5/N, 120/240 VOLT, ADD AMP MAIN BREAKER WITH NEUTRAL ALL BOLT ON BREAKERS.
3. FLUORESCENT LIGHT FIXTURE.
4. AIR CONDITIONER - WALL MOUNTED.
5. EXTERIOR DOOR.
6. HEAVY DUTY, WEATHER PROOF, EXTERIOR WALL LIGHT MOUNTED ABOVE DOOR.
7. 3/4 IN. PLYWOOD BOLTED TO WALL.
8. PAINTED DRYWALL INTERIOR.
9. EXISTING SHELTER IS A PRE-CAST CONCRETE UNIT COMPLETE WITH WALLS, FLOOR & CEILING EXISTING BUILDING ON A PEASTONE BASE. CONTRACTOR TO DISCONNECT ALL CABLES & CONDUIT AT EXISTING LOCATION BEFORE RELOCATING SHELTER.
10. ALL LOOSE MATERIALS TO BE PACKAGED AND MOVED SEPARATELY. SECURE ALL EQUIPMENT PRIOR TO RELOCATING SHELTER. REMOVE ROOF MOUNTED ANTENNAS.
11. BUILDING/SHELTER TO BE LIFTED AND TRANSPORTED TO NEW SITE AS A COMPLETE UNIT.
12. BUILDING/SHELTER TO BE POSITIONED AT NEW LOCATION AS SHOWN ON SITE PLAN OR AS DIRECTED BY THE ENGINEER. CONNECT NEW CABLES AND CONDUITS AT NEW SITE. NEW CABLES AND CONDUITS BY OTHERS. COORDINATE TELEPHONE AND POWER CABLES WITH LOCAL PHONE AND UTILITY COMPANIES. COORDINATE FAA CABLE CONNECTIONS WITH FAA/F&E CONTACT JAMES CAULFIELD, ☎ (817) 238-7482.
13. CONTRACTOR TO REMOVE ELECTRICAL CABLING, & PEASTONE FOUNDATION FROM EXISTING SITE. CONTRACTOR TO REMOVE EXISTING FOUNDATION FOR LOCALIZER & DME. AREA TO BE REGRADED, TOPSOILED AND SEEDED. COST OF THIS WORK TO BE INCLUDED IN COST OF ITEM 529.20 MOD 11.



LIGHTNING PROTECTION DETAILS
SCALE: NONE

LEGEND

- Ⓢ LIGHT SWITCH, 4'-8" ABOVE FLOOR
- Ⓛ DUPLEX RECEPTACLE, 4' ABOVE FLOOR
- Ⓡ 240 VOLT RECEPTACLE, 4' ABOVE FLOOR
- Ⓣ 240 VOLT LINE THERMOSTAT




| | |
|-------------|----------------------------------|
| DESIGNED BY | JAG |
| CHECKED BY | JAG |
| DATE | 5/8/97 |
| DESCRIPTION | LOCALIZER BLDG. EQUIPMENT LAYOUT |
| PROJECT NO. | 11542 |
| DATE | 5/8/97 |
| JOB NO. | 11542 |
| PROJECT NO. | 11542 |

RUTLAND STATE AIRPORT
CLARENDON, VERMONT
LOCALIZER/DME RUNWAY 19
POWER AND CONTROL BUILDING

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|-------------|----------------------------------|
| DESIGNED BY | JAG |
| CHECKED BY | JAG |
| DATE | 5/8/97 |
| DESCRIPTION | LOCALIZER BLDG. EQUIPMENT LAYOUT |
| PROJECT NO. | 11542 |
| DATE | 5/8/97 |
| JOB NO. | 11542 |
| PROJECT NO. | 11542 |



Designed by: **URS**
 Drawn by: **W. B. GARDNER**
 Checked by: **J. J. GARDNER**
 Approved by: **J. J. GARDNER**


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |


Job No. **FR102R** File No. **KR102R-10**





ARP 3-50-001-11

| | | | |
|--|-------------------------------------|---|----------------------------|
| URS CONSULTING ENGINEERS, INC. 3 MARCUS BOULEVARD ALBANY, NEW YORK | Designed by: DM C. Franko | RUTLAND STATE AIRPORT CLARENDON, VERMONT | |
| | Drawn by: DM C. Franko | RUNWAY CROSS SECTIONS | |
| Checked by: DM C. Franko | REV. DATE DESCRIPTION | Job No. 98233 | File No. 98233-03-0 |
| Approved by: DM C. Franko | Job No. 98233 | File No. 98233-03-0 | |



113+50

114+00

114+50

115+00

115+50

116+00

116+50

117+00

117+50

118+00

118+00

AIP 3-50-00B-11


| | |
|-----------------------------|-------------------------------|
| Designed by: Doherty | Checked by: W. J. ... |
| Drawn by: W. J. ... | Approved by: W. J. ... |
| Scale: 1" = 100' | File No. 3-50-00B-11 |

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |





AP 3-50-2012-11

Sheet No. 60

Drawn by: J. W. [unreadable]

Checked by: [unreadable]

Approved by: [unreadable]

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARNDON, VERMONT


RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. 1000000000

File No. 1000000000





AIR 3-50-015-11

Designed by
 Drawn by
 Checked by
 Approved by


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. Title No.





11/23/00 3-50-012-11

23
 Drawn by: J. W. GARDNER
 Checked by: J. W. GARDNER
 Approved by: J. W. GARDNER
 Date: 11/23/00

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK


RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
 RUNWAY CROSS SECTIONS

| | | |
|------|------|-------------|
| REV. | DATE | DESCRIPTION |
| | | |
| | | |
| | | |

Job No. 992020 File No. 99R0102-01



ALP 3-50-0015-11



Drawn by: **W. MICHAL** 2/87
 Checked by: **C. FRAGO** 1/2/87
 Approved by: **W. MICHAL** 3/87


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARION, VERMONT
 RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

Job No. VERM-01 File No. 67020LRD-0





ARP 3-50-015-11


Sheet No. **54**
 of 58
 Date: 5/1/57
 Scale: 1" = 40'

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
 RUNWAY CROSS SECTIONS

| | |
|---------------------------|----------------------|
| DESIGNED BY C. F. WOOD | DATE 2/27/57 |
| DRAWN BY W. W. WOOD | DATE 2/27/57 |
| CHECKED BY C. F. WOOD | DATE 5/1/57 |
| APPROVED BY C. F. WOOD | DATE 5/1/57 |
| REV. DATE DESCRIPTION | |
| JOB NO. 54-10015 | FILE NO. 54-10015-54 |





AIP 3-50-015-11

Drawn by: **W. HODGINS** 2/27
 Checked by: **C. MARCO** 5/1/27
 Approved by: **C. MARCO** 5/1/27


URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLAREMONT, VERMONT
RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. **PROJUS** File No. **01500100-01**





Designed by
 E. J. FRENCH
 1/27
 Drawn by
 M. MICHAEL
 3/27
 Checked by
 S. W. FRENCH
 5/27
 Approved by
 M. MICHAEL
 5/27

URS Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARNDON, VERMONT


RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

Job No. 15400000 (The No. 15400000)



AIR 3-00-0013-11



Drawn by: **W. W. W.**
 Checked by: **W. W. W.**
 Approved by: **W. W. W.**
 Date: **2/97**


URS Creder, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

RUTLAND STATE AIRPORT
 CLARENDON, VERMONT
RUNWAY CROSS SECTIONS

| REV. | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |


Job No. **98010** File No. **AVR001/03-03**






A.P. 345-0013-11

| | | | | |
|--|--|---|----------------------|--|
| 88 SHEET NO. TOTAL NO. OF SHEETS | DESIGNER URS CORNER, INC. 3 MARCUS BOULEVARD ALBANY, NEW YORK | RUTLAND STATE AIRPORT CLANDON, VERMONT | | |
| | | CHECKED BY W. J. MURPHY | DATE 1/1/2010 | |
| DRAWN BY W. J. MURPHY | APPROVED BY W. J. MURPHY | JOB NO. 10000000 | FILE NO. 10000000 | |




A GRAVEL DRIVE
SCALE: NONE



NOTE: PROVIDE 20' CABLE SLACK - EACH END OF ALL CABLES. SEAL CONDUITS WITH APPROVED DUCT SEAL AFTER INSTALLATION OF CABLES OR PULL WIRES.



B LOCALIZER SHELTER FOUNDATION
SCALE: NONE



C SITE DETAIL - LOCALIZER SHELTER
SCALE: NONE

- NOTES:
- CONTRACTOR TO RELOCATE EXISTING LOCALIZER SHELTER ONTO EXISTING PEASTONE FOUNDATION IN ACCORDANCE WITH SPECIFICATION SECTION L-200.
 - CONTRACTOR TO MAKE FINAL ELECTRICAL CONNECTIONS AT TRANSFORMER TO SECONDARY POWER CABLES, FROM SECONDARY POWER CABLES TO THE POWER PANEL INSIDE THE LOCALIZER SHELTER, AND FROM THE POWER PANEL TO THE LOCALIZER ANTENNA ARRAY.
 - CONTRACTOR TO MAKE FINAL COMMUNICATIONS (TELEPHONE) CONNECTIONS FROM TELEPHONE CABINET ADJACENT TO LOCALIZER SHELTER TO THE CONTROL INTERFACE BOX MOUNTED ON EXTERIOR OF BUILDING.
 - FAA TO MAKE ALL COAXIAL CABLE CONNECTIONS.
 - CONTRACTOR TO EXTEND SHELTER DRIVEWAY AS SHOWN ON SHEET 14. CONTRACTOR TO PAVE SHELTER DRIVEWAY.

- NOTES:
- SITE PREPARATION: EXCAVATE TOPSOIL TO GOOD BEARING SOIL. COMPACT SUBGRADE, AND CRUSHED AGGREGATE TO 95% AASHTO T99.
 - PEASTONE LAYER TO BE LEVEL.
 - SHELTER RELOCATION BY OTHERS.
 - SEE DETAIL (C) FOR BUILDING GROUNDING DETAILS.





| | |
|-------------|------------|
| FILE NO. | 11/10/2018 |
| REV. | DATE |
| DESCRIPTION | |

RUTLAND STATE AIRPORT
CLAREMONT, VERMONT
LOCALIZER RELOCATION - SITE PLAN

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|--------------------------|------|
| Checked by | DATE |
| Drawn by | DATE |
| Checked by | DATE |
| Checked by | DATE |
| Scale: HORIZ. - 1" = 60' | |
| Scale: VERT. - NONE | |
| Date: 6/9/97 | |
| Sheet 40 OF 60 | |
| Sheet No. | 60 |







GENERAL NOTES

1. ALL DISTURBED AREAS TO BE REGRADED, TOPSOIL REPLACED, LIMED, FERTILIZED, & MULCHED.
2. CRUSHED AGGREGATE TO CONFORM TO SPECIFICATION 307.25
3. INSTALLATION OF UNDERGROUND CONDUIT AND COMMUNICATIONS CABLES TO CONFORM TO REQUIREMENTS OF THE LOCAL UTILITY (CVS) & TELEPHONE Co. (NYNEK).

PROJECT: RUTLAND STATE AIRPORT
 CLARENCE, VERMONT
 LOCALIZER SITE DETAILS

DATE: 6/9/07
 SHEET: 01 OF 00



PROJECT: RUTLAND STATE AIRPORT
 CLARENCE, VERMONT
 LOCALIZER SITE DETAILS






DATE: 6/9/07
 SHEET: 01 OF 00

Scale: HORIZ. - NONE
 VERT. - NONE

Sheet No. 01

W&S Greiner, Inc.
 3 MARCUS BOULEVARD
 ALBANY, NEW YORK

61



| | | |
|------|------|-------------|
| REV. | DATE | DESCRIPTION |
| | | |
| | | |
| | | |


Job No. 1100000000-4
Job No. 100000000

RUTLAND STATE AIRPORT
CLARENDON, VERMONT

LOCALIZER SITE DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | | | |
|--------------|-----------|-------------|--------------|
| Designed By: | Drawn By: | Checked By: | Approved By: |
| 0/0/00 | 0/0/00 | 0/0/00 | 0/0/00 |
| Scale: | | | |
| Date: | 0/0/00 | | |
| Sheet of: | 00 | | |
| Sheet No. | | | |



NOTES

1. ALL CONCRETE TO CONFORM TO VADT SPECIFICATIONS, DIVISION 501, CLASS C, MAXIMUM AGGREGATE SIZE SHALL BE 3/4".
2. ROCK SIZE IN AND AROUND THE ARRAY SHOULD NOT EXCEED 1" IF FILL OR GRADING IS REQUIRED, IT SHALL BE BUILT UP IN LAYERS NOT EXCEEDING 8" AND EACH LAYER SHALL BE TAMPED AND COMPACTED TO 95% OF MAXIMUM DENSITY AT OPTIMUM WATER CONTENT. GRADING OF ROCK AND SOIL SHOULD BE SUCH THAT ALL DRAINAGE IS AWAY FROM FOUNDATIONS.
3. TOLERANCES - ALL ANCHOR BOLTS MUST BE LOCATED ± 1/8" OF DIMENSIONS GIVEN ON DETAIL L. ALL CONCRETE PIER FOUNDATIONS MUST BE LOCATED FRONT TO REAR ± 1/2" AND SIDE TO SIDE ± 1/4" PER DIMENSIONS GIVEN. LOCATE ALL CONDUITS ± 1/4" OF DIMENSIONS GIVEN.
4. CONCRETE FOUNDATIONS BASED ON 3000-PSF SOIL BEARING PRESSURE, CONCRETE PIER FOUNDATIONS BASED ON 200 LB. PER SQ. FT. LATERAL SOIL PRESSURE PER FT. OF PIER DEPTH BELOW FINISHED GROUND LEVEL.
5. REFERENCE LINES FOR POSITIONING ARRAY ON SITE PLAN.
6. ANTENNA ARRAY TO BE SALVAGED FROM EXISTING LOCATION BY OTHERS.
7. ANCHOR BOLTS, NUTS, AND WASHERS SHALL BE HOT DIP GALV. STEEL PER ASTM-A193 AND ASTM-A325.
8. EXOTHERMIC WELD ALL GROUND CONNECTIONS.
9. GROUND WIRE CONDUIT DETAIL IS TYPICAL FOR ALL SIDES OF THE FOUNDATIONS. FOUNDATION GROUND RODS SHALL BE CONNECTED TOGETHER BY #4/O BARE WIRE, EXOTHERMICALLY WELD #8 BARE TO #4/O BARE AT END OF FOUNDATION.

LOCALIZER FOUNDATION PLAN AND LONGITUDINAL SECTION
SCALE: 1" = 2'

L TYPICAL ANCHOR BOLT (NOTE 7)
SCALE: NONE

M DIST. UNIT CONDUIT DETAILS
SCALE: NONE
NOTE: PROVIDE EXPANSION COUPLING ON ABOVE GRADE CONDUITS.

N LOCALIZER FOUNDATION TRANSVERSE SECTION
SCALE: 1" = 2'

| REV. | DATE | DESCRIPTION | FILE NO. / REVISION NUMBER |
|------|------|-------------|----------------------------|
| | | | |
| | | | |
| | | | |


RUTLAND STATE AIRPORT
CLAREMONT, VERMONT

LOCALIZER FOUNDATION DETAILS

URS Greiner, Inc.
3 MARCUS BOULEVARD
ALBANY, NEW YORK

| | |
|--------------------------|------------------|
| Checked by: [Signature] | Date: 6/9/97 |
| Drawn by: [Signature] | Scale: VERY NEAR |
| Checked by: [Signature] | Date: 6/9/97 |
| Approved by: [Signature] | Scale: 1" = 2' |

Sheet No. **63**



| ITEM | QTY | DESCRIPTION | WPN |
|------|-----|---|-------------|
| 71 | 12 | WASHER, LOCK #10 | 826001-0081 |
| 72 | 12 | NUT, HEX #10-32 | 830001-0304 |
| 73 | 18 | CONN, SPLIT BOLT (KS17) | 228911-0004 |
| 74 | 3 | GND ROD 3/4" X 10" | * |
| 75 | 1 | EL. SWEEP 1-1/4" PVC 90° | * |
| 76 | 1 | CABLE, RF 1/4" HELIAX 1700' L | 111588-1700 |
| 77 | 70 | CONN, RF TYPE N MALE | 230181-0001 |
| 78 | 28 | CONN, RF ADPTR TYPE N RT ANGLE | 875004-0001 |
| 79 | 4 | CONN, RF ADPTR STR TNC M-NFE | 228913-0001 |
| 80 | 1 | KIT, IDENT CBL SLEEVE | 088209-0001 |
| 81 | 24 | BOLT, HEX NYLON 1/4"-20 X 1" L (NOTE 6) | 502644-0053 |
| 82 | 24 | NUT, HEX NYLON 1/4"-20 | 300858-0007 |
| 83 | 2 | CONN, SPLIT BOLT (KS23) | 228911-0012 |


| ITEM | QTY | DESCRIPTION | WPN |
|------|-----|-------------------------------------|-------------|
| 70 | 12 | WASHER, FLAT #10 | 825000-0898 |
| 69 | 12 | SCREW, MACH. #10-32 X 1/2" | 818012-0012 |
| 68 | 12 | LUG, GND SOLDERLESS | 025478-0001 |
| 67 | 250 | WIRE, #8 BARE | 110041-0001 |
| 66 | 8 | SCREW, MACH. 1/4"-20 X 3/2" | 815018-0039 |
| 65 | 4 | HANGER, CND 2-1/2" | 270708-8677 |
| 64 | 4 | HANGER, CND 3/4" | 033788-0008 |
| 63 | 4 | BULB, LIGHT | 033788-0002 |
| 62 | 2 | LIGHT, OSS | 033707-0001 |
| 61 | 2 | CND, 3/4" X 48' L | 033871-0001 |
| 60 | 2 | CND, 3/4" X 3' L | 033754-0002 |
| 59 | 2 | NIPPLE, CND 3/4" X 10' L | 033588-0005 |
| 58 | 2 | NIPPLE, CND 3/4" X 3' L | 033588-0001 |
| 57 | 2 | GASKET, COVER | 033871-0004 |
| 56 | 2 | GASKET, COVER | 033728-0003 |
| 55 | 2 | BUSHING, INSULATED 3/4" | 033588-0001 |
| 54 | 2 | NUT, LOCK 3/4" | 033588-0001 |
| 53 | 2 | NUT, LOCK 3/4" | 033518-0000 |
| 52 | 2 | CABLE, POWER #12-2 UF | 033588-0008 |
| 51 | 1 | BUSHING, INSULATED 1-1/4" | 111456-0002 |
| 50 | 1 | LOCK NUT, CND 1-1/4" | * |
| 49 | 1 | ADAPTER, PVC MALE 1-1/4" | * |
| 48 | 1 | CND, PVC RIGID 1-1/2" X 2" | * |
| 47 | 1 | BUSHING, INSULATED 3" | * |
| 46 | 1 | ADAPTER, PVC MALE 3" | * |
| 45 | 1 | CND, PVC RIGID 3" X 24" | * |
| 44 | 1 | EL. SWEEP 5" PVC 90° | * |
| 43 | 1 | COVER, ADAPTER RACEWAY END | 489114-0001 |
| 42 | 1 | RACEWAY, CABLE ADAPTER END (RT) | 282218-0002 |
| 41 | 1 | RACEWAY, CABLE ADAPTER END (LT) | 282218-0001 |
| 40 | 1 | GASKET, CHAIN WEATHERCAP (NOTE 2) | 285047-0001 |
| 39 | 1 | WASHER, FLAT 1/4"-20 (NOTE 2) | 830000-0030 |
| 38 | 1 | BOLT, HEX 1/4"-20 X 4-1/2" (NOTE 2) | 825000-0810 |
| 37 | 1 | CAP. WEATHER SHIELD (NOTE 2) | 918070-0024 |
| 36 | 1 | COVER WRAPPER RACEWAY (CTR) | 285048-0000 |
| 35 | 1 | CAP. END RACEWAY | 489043-0001 |
| 34 | 1 | COVER, WRAPPER RACEWAY (DU) | 281821-0001 |
| 33 | 1 | NUT, SELF-LOCKING #8-32 | 489113-0001 |
| 32 | 1 | WASHER, FLAT #8 | 100688-0001 |
| 31 | 1 | WASHER, MACH. #8-32 X 1/2" PHPHMS | 925000-0807 |
| 30 | 1 | RACEWAY, CABLE SECT BOT 94" L | 815014-0045 |
| 29 | 1 | RACEWAY, CABLE SECT TOP 94" L | 282218-0001 |
| 28 | 1 | BOLT, HEX 5/16" X 18 X 1" | 282217-0001 |
| 27 | 1 | RACEWAY, CABLE WRAPPER (CTR) 28" | 918065-0030 |
| 26 | 1 | GASKET, RACEWAY ADAPTER (DU) | 282173-0001 |
| 25 | 1 | RACEWAY, CABLE ADAPTER (LT) | 285050-0001 |
| 24 | 1 | RACEWAY, CABLE ADAPTER (RT) | 282220-0002 |
| 23 | 1 | UNIT, DISTR ASSY | 282220-0001 |
| 22 | 1 | NUT, HEX 1/4"-20 | 830000-2254 |
| 21 | 1 | WASHER, LOCK 1/4" | 826001-0082 |
| 20 | 1 | WASHER, FLAT 1/4" X 3/4" | 825001-0005 |
| 19 | 1 | BOLT, HEX 1/4"-20 X 3/4" | 918085-0007 |
| 18 | 1 | BRACKET, MTO DISTR UNIT, LEFT | 093431-0002 |
| 17 | 1 | BRACKET, MTO DISTR UNIT, RIGHT | 093431-0001 |
| 16 | 1 | ELEMENT, ANT | 489043-0100 |
| 15 | 1 | NUT, HEX 5/16" X 18 | 830000-2314 |
| 14 | 1 | WASHER, LOCK 5/16" | 828001-0083 |
| 13 | 1 | WASHER, FLAT 5/16" X 1-1/2" | 918085-0008 |
| 12 | 1 | BOLT, HEX 5/16" X 1-1/2" | 918065-0032 |
| 11 | 1 | SUPPORT ASSY, FRONT | 118907-0001 |
| 10 | 1 | SUPPORT ASSY, REAR | 118908-0001 |
| 9 | 1 | NUT, SO GALV 5/8"-11 | * |
| 8 | 1 | WASHER, FLAT, SO GALV 5/8" | * |
| 7 | 1 | BOLT, ANCHOR GALV 5/8"-11 X 12" | * |

- NOTES:
1. CONNECTIONS TO ITEM 67 AND #2 BARE ARE MADE WITH ITEMS 73 AND 83, RESPECTIVELY, INSIDE CABLE TROUGH.
 2. PART OF LOC. ANT. ELEMENT AND IS FACTORY ASSEMBLED.
 3. RF FEED & MONITOR CABLES TO ANT. VIA REAR ANT. MAST.
 4. ITEMS MARKED WITH AN ASTERISK (*) ARE FURNISHED BY GOVERNMENT CIVIL CONTRACTOR.
 5. GFM-GOVERNMENT FURNISHED MATERIAL.
 6. NOTED ITEMS ARE TO BE USED AS SPARE HARDWARE FOR THE ANTENNA RADOME ASSEMBLES.


| | | | |
|---|---|-------------|-----------|
| DATE | DESCRIPTION | DESIGNED | APPROVED |
| | REPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WASHINGTON, D.C. 20590 | | |
| INSTRUMENT LANDING SYSTEM CAPTURE EFFECT LOCALIZER ANTENNA ARRAY INSTALLATION DETAILS TYPE NO. FA-10582 | | | |
| REVISED BY | DESIGNED BY | APPROVED BY | |
| | | | |
| ISSUED BY | ISSUED BY | DATE | |
| | AVIATION FACILITIES SERVICE | 7-1-84 | |
| | | | D-6288-18 |

NOTES


1. THE LOCATION OF THE PORTABLE MARKER UNIT SHALL BE AS ORDERED BY THE ENGINEER.
2. DIRECTIONAL ARMS ARE INSTALLED ONLY ON AIRPORTS WITH A NON-STANDARD TRAFFIC PATTERN (RIGHT-HAND PATTERN). WHEN INSTALLED, DIRECTIONAL ARMS WILL BE MAGNETICALLY ORIENTED TO THE RUNWAY AND WILL SHOW TRAFFIC PATTERN ON EACH RUNWAY.



SEGMENTED CIRCLE LAYOUT WITH DIRECTIONAL ARMS




LEG DETAIL FOR PORTABLE MARKER UNIT
DETAIL 'A'




SEGMENTED CIRCLE MARKER UNIT

MARKER UNIT - STANDARD 55 GALLON METAL DRUM, CUT IN HALF AND WELDED END TO END, MARKER UNITS TO BE PAINTED AVIATION ORANGE.
PORTABLE UNIT HAS LEGS OF 2" Ø GALVANIZED PIPE OR 1 1/2" x 3/8" L 1 GALV. I.




ALL DUCTS, EXCEPT STEEL CONDUIT, INSTALLED UNDER RUNWAYS, TAXIWAYS, APRONS, AND OTHER PAVED AREAS SHALL BE ENCASED IN A CONCRETE ENVELOPE


SEE STANDARD AP-2 FOR DIRECT BURIAL CABLE DETAILS.




AIRCRAFT TIE DOWN ANCHOR



AIRPORT UNDERGROUND ELECTRICAL DUCT (IN EARTH)



DUCT MARKERS



AIRPORT UNDERGROUND ELECTRICAL DUCT (IN ROCK)

- NOTES**
1. LETTERING ON DUCT MARKERS TO BE EMBOSSED, 1/4" CUT, 1/2" DEEP.
 2. HAND LETTERING NOT ALLOWED.

REVISIONS AND CORRECTIONS

DEC. 15, 1981 - ORIGINAL APPROVAL DATE
MAR. 5, 1990 - SHEET UPDATED
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.

APPROVED


W.B. [Signature]
DIRECTOR OF RAIL, AIR AND PUBLIC TRANSIT

APPROVED FOR THIS PROJECT, AND/OR DESIGN IMPLEMENTATION, FROM FINAL APPROVAL PERIOD.

MISCELLANEOUS AIRPORT DETAILS




**STANDARD
AP-3**




PRECISION INSTRUMENT RUNWAY

NOT TO SCALE



NONPRECISION INSTRUMENT RUNWAY

NOT TO SCALE




DISPLACED THRESHOLD MARKINGS

NOT TO SCALE

NOTES

- FOUR ARROWHEADS ARE PLACED SYMMETRICALLY ACROSS RUNWAY WITH UNIFORM LATERAL SPACING AS INDICATED.
- ALL MARKINGS IN THE DISPLACED AREA ARE YELLOW EXCEPT THE THRESHOLD BAR WHICH IS WHITE.
- RUNWAY SIDE STRIPES, WHEN USED ON THE RUNWAY, EXTEND INTO THE DISPLACED AREA.



RUNWAY NUMERALS AND LETTERS


NOTES

- ALL LETTERS AND NUMERALS, EXCEPT THE NUMBER ELEVEN AS SHOWN, ARE HORIZONTALLY SPACED 15 FEET APART.
- DIMENSIONS ARE EXPRESSED IN FEET.
- THE NUMERAL ONE, WHEN USED ALONE, CONTAINS A HORIZONTAL BAR TO DIFFERENTIATE IT FROM THE RUNWAY CENTERLINE MARKING.

GENERAL NOTES


- ALL RUNWAY MARKINGS ARE WHITE EXCEPT IN THE DISPLACED THRESHOLD AREA AND NON FULL STRENGTH SHOULDER MARKINGS.
- FOR RUNWAYS LESS THAN 150' IN WIDTH, THE WIDTH OF THE MARKINGS, SPACES BETWEEN MARKINGS, AND DISTANCE OF MARKINGS FROM THE RUNWAY EDGE ARE CHANGED PROPORTIONALLY.
- ADJUSTMENTS TO THE LENGTH OF THE CENTERLINE STRIPES AND GAPS, WHERE NECESSARY TO ACCOMMODATE THE RUNWAY LENGTH, ARE MADE NEAR THE RUNWAY MIDPOINT.
- ALL RUNWAY MARKINGS ARE TO BE STRIATED WITH ALL STRIPES AND SPACES EQUAL IN WIDTH (4" TO 6").

NOTE : MARKING OF RUNWAY SHOULD BE BASED ON FAA SPECIFICATIONS. SEE CURRENT FAA ADVISORY CIRCULAR.



VISUAL RUNWAY

NOT TO SCALE



TEMPORARY CLOSED RUNWAY MARKER

TEMPORARY CLOSED RUNWAY MARKER NOTES :

- MARKERS TO BE YELLOW PLYWOOD OR SNOW FENCE.
- MARKERS TO BE SUBSIDIARY TO OTHER PAY ITEMS.
- MARKERS TO BE PLACED OVER RUNWAY NUMERALS OR OFF THE RUNWAY ENDS AS APPLICABLE.
- MARKERS TO BE ANCHORED TO THE SATISFACTION OF THE ENGINEER.

REVISIONS AND CORRECTIONS

JUNE 29, 1982 - ORIGINAL APPROVAL DATE
 MAR. 5, 1990 - SHEET UPDATED
 JUNE 1, 1994 - RE-ISSUED, WITHOUT CHANGE,
 UNDER NEW SIGNATURE.

APPROVED

APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION FROM FINAL APPROVAL PENDING.

[Signature]
 DIRECTOR OF RAIL, AIR AND PUBLIC TRANSIT





RUNWAY MARKING DETAILS



STANDARD
 AP-10

NOTE 1
ON LIGHT COLORED PAVEMENTS THE CONTRAST OF THE MARKINGS IS
TO BE INCREASED BY OUTLINING ALL MARKINGS WITH A 6" BLACK BORDER.

SEE STANDARD AP-10 FOR RUNWAY MARKING DETAILS



REVISIONS AND CORRECTIONS

MAR. 1, 1990 - SHEET UPDATED
JUNE 1, 1994 - REISSUED WITHOUT CHANGE,
UNDER NEW SIGNATURE.


APPROVED

APPROVED FOR THIS PROJECT
AND/OR DESIGN IMPLEMENTATION.
(AREA FINAL APPROVAL REQUIRED)
[Signature]
DIRECTOR OF RAIL, AIR AND PUBLIC TRANSIT


TAXIWAY AND APRON
MARKING DETAILS



STANDARD
AP-11





METHOD FOR CONSTRUCTING AN EMBANKMENT ON EARTH SLOPE




GENERAL NOTES:
 THE MUCK OR UNSUITABLE MATERIAL SHALL BE EXCAVATED TO THE NEAT LINES SHOWN ON THE PLANS OR AS DETERMINED BY THE ENGINEER.
 EXCAVATION AND PAYMENT LIMIT WILL BE DETERMINED FROM EITHER PLAN 'A' OR PLAN 'B', WHICHEVER PRODUCES THE GREATER WIDTH IN A GIVEN MUCK AREA.
 BACKFILL MATERIAL MUST MEET THE REQUIREMENTS SET FORTH UNDER MUCK EXCAVATION, SECTION 203

TYPICAL NEAT PAY LINES FOR MUCK EXCAVATION



DRILLING AND BLASTING OF SOLID ROCK.
 PROCEDURE TO BE FOLLOWED WHEN LEDGE SLOPE ON OLD GROUND IS BETWEEN A 1-1 AND A 1-5 SLOPE.
 ALL HOLES TO BE APPROXIMATELY 5'-0" DEEP, HOLES TO BE IN ROWS, SPACED AND STAGGERED AS SHOWN IN DRILL PATTERN, OR AS DIRECTED BY THE ENGINEER, SEE SECTION 205

A METHOD FOR PREPARING LEDGE SLOPE BEFORE CONSTRUCTING AN EMBANKMENT



SLOPES TO BE ROUNDED AS SHOWN IN ORDER TO ALLOW FOR PERSPECTIVE FORESHORTENING AS SEEN FROM THE ROAD AND SO THAT FINISHED SLOPES WILL BETTER SUPPORT VEGETATIVE COVER.
 ROUNDED TO MERGE WITH EXISTING GROUND SURFACE SO THAT NO HARD GRADE LINE WILL REMAIN WITHIN THE LINE OF SIGHT
 WHEN STEEPNESS OF EXISTING GROUND OR PRESENCE OF EXISTING VEGETATION IS CONSIDERED A FACTOR PREVENTING NORMAL ROUNDING, THE EXTENT OF THE ROUNDING SHOULD BE MODIFIED TO MEET CONDITIONS.

TYPICAL SLOPE ROUNDING






REVISIONS AND CORRECTIONS
 DEC. 6, 1971 - ORIGINAL APPROVAL DATE
 JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.

APPROVED
 APPROVED FOR THIS PROJECT (AND/OR DESIGN IMPLEMENTATION, FINAL FINAL APPROVAL PENDING).
 [Signature]
 DIRECTOR OF ENGINEERING
 [Signature]
 DESIGN ENGINEER

EMBANKMENT ON EARTH SLOPE
 EMBANKMENT ON ROCK SLOPE
 MUCK EXCAVATION
 TYPICAL SLOPE ROUNDING






STANDARD
 B-5



GENERAL NOTES - HEADWALLS:

1. THE HEIGHT OF HEADWALLS ON DRIVEWAY PIPES IS TO BE REDUCED TO 6" ABOVE THE TOP OF PIPE.
2. BELL AND SPOOT PIPE IS TO BE LAID WITH THE BELL UPSTREAM.
3. HEADWALL QUANTITIES, FOR THE SAME TYPE HEADWALLS ON PIPES OF EQUAL DIAMETER, ARE THE SAME FOR BOTH CONCRETE AND METAL PIPE. LENGTH OF HEADWALLS ARE BASED ON INSIDE DIAMETER OF PIPES.
4. THE NECESSITY OF CONSTRUCTING A FLOOR AT THE ENTRANCE TO AN L TYPE HEADWALL SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER AND ANY INSTALLATION THEREOF SHALL BE AT HIS DIRECTION.



REVISIONS AND CORRECTIONS

DEC. 6, 1971 - ORIGINAL APPROVAL DATE

MAR. 8, 1972 - CHANGED ANCHOR BOLTS FROM 10" L TO 8" CARRIAGE

DEC. 16, 1976 - NOTE ADDED ON REINFORCING STEEL FOR CRADLE HEADWALLS

OCT. 30, 1985 - REVISED TO CONFORM TO 1986 SPECIFICATIONS

JUNE 1, 1994 - REISSUED WITHOUT CHANGE. UNDER NEW SIGNATURES.

APPROVED FOR THIS PROJECT AND/OR DESIGN REPRESENTATION:


Stanley D. McArthur, Jr.
DIRECTOR OF ENGINEERING

John D. Murphy, PE
DESIGN ENGINEER



CEMENT RUBBLE MASONRY HEADWALLS & RETAINING WALL
RIPRAP LIGHT TYPE SLOPE HEADWALL
REINFORCED CONCRETE HEADWALL
UNDERDRAIN & CARRIER PIPE CONSTRUCTION DETAILS

VERMONT AGENCY OF TRANSPORTATION

STANDARD D-2



NOTE 1 FRAME SHOWN IS FOR TYPE A GRATE, SEE SHEET D-11. FOR TYPE B GRATE AND FRAME, SEE SHEET D-16 (EXCEPT THE FRAME DEPTH DIMENSION SHALL BE 6" H. TOP FOR REINFORCED CONCRETE DROP INLET WITH GRATE FOR USE IN DITCHES)





REINFORCED CONCRETE DROP INLET FOR USE IN DITCHES

| STEEL SCHEDULE | | | | | | | | | | | | | | | | | |
|------------------|----|--------|----|--------|---|----------------------------------|----|--------|----|--------|----|---|----|--------|---|--------|-------|
| 4'x4' DROP INLET | | | | | | 4'x6' DROP INLET WITH TWO GRATES | | | | | | TYPE C 4'x6' DROP INLET WITH ONE GRATE WITH 4'x6' TOP | | | | | |
| DEPTH | C | LENGTH | H | LENGTH | C | LENGTH | G | LENGTH | H | LENGTH | J | LENGTH | C | LENGTH | D | LENGTH | DEPTH |
| 3'-0" | 15 | 2'-0" | 22 | 3'-8" | 8 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 3'-0" |
| 4'-0" | 15 | 3'-0" | 22 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 3'-6" |
| 4'-0" | 15 | 3'-0" | 29 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 4'-0" |
| 4'-0" | 15 | 3'-0" | 29 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 4'-6" |
| 4'-0" | 15 | 3'-0" | 35 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 5'-0" |
| 5'-0" | 15 | 4'-0" | 35 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 5'-6" |
| 5'-0" | 15 | 4'-0" | 41 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 6'-0" |
| 6'-0" | 15 | 4'-0" | 41 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 6'-6" |
| 6'-0" | 15 | 4'-0" | 47 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 7'-0" |
| 7'-0" | 15 | 5'-0" | 47 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 7'-6" |
| 8'-0" | 15 | 5'-0" | 53 | 3'-8" | 8 | 3'-8" | 17 | 3'-8" | 19 | 3'-8" | 10 | 3'-8" | 4 | 3'-8" | 4 | 3'-8" | 8'-0" |



| STEEL AND CONCRETE QUANTITIES | | | | | | | | | | | | | | | | | |
|-------------------------------|------------|-----------|------------|-----------|------------|----------------------------------|-------|------------|-----------|------------|-----------|--|------------|-----------|------------|-----------|-------|
| 4'x4' DROP INLET | | | | | | 4'x6' DROP INLET WITH TWO GRATES | | | | | | 4'x6' DROP INLET WITH ONE GRATE WITH 4'x4' TOP | | | | | |
| DEPTH | CONC. C.Y. | STEEL LBS | CONC. C.Y. | STEEL LBS | CONC. C.Y. | STEEL LBS | DEPTH | CONC. C.Y. | STEEL LBS | CONC. C.Y. | STEEL LBS | DEPTH | CONC. C.Y. | STEEL LBS | CONC. C.Y. | STEEL LBS | DEPTH |
| 3'-0" | 1.7 | 150 | 2.7 | 228 | 2.5 | 237 | 3'-0" | 1.7 | 150 | 2.7 | 228 | 3'-0" | 1.7 | 150 | 2.7 | 228 | 3'-0" |
| 3'-6" | 1.9 | 168 | 2.7 | 228 | 2.5 | 237 | 3'-6" | 1.9 | 168 | 2.7 | 228 | 3'-6" | 1.9 | 168 | 2.7 | 228 | 3'-6" |
| 4'-0" | 2.1 | 183 | 2.7 | 228 | 2.5 | 237 | 4'-0" | 2.1 | 183 | 2.7 | 228 | 4'-0" | 2.1 | 183 | 2.7 | 228 | 4'-0" |
| 4'-6" | 2.3 | 200 | 2.7 | 228 | 2.5 | 237 | 4'-6" | 2.3 | 200 | 2.7 | 228 | 4'-6" | 2.3 | 200 | 2.7 | 228 | 4'-6" |
| 5'-0" | 2.5 | 216 | 2.7 | 228 | 2.5 | 237 | 5'-0" | 2.5 | 216 | 2.7 | 228 | 5'-0" | 2.5 | 216 | 2.7 | 228 | 5'-0" |
| 5'-6" | 2.8 | 239 | 2.7 | 228 | 2.5 | 237 | 5'-6" | 2.8 | 239 | 2.7 | 228 | 5'-6" | 2.8 | 239 | 2.7 | 228 | 5'-6" |
| 6'-0" | 3.0 | 258 | 2.7 | 228 | 2.5 | 237 | 6'-0" | 3.0 | 258 | 2.7 | 228 | 6'-0" | 3.0 | 258 | 2.7 | 228 | 6'-0" |
| 6'-6" | 3.2 | 278 | 2.7 | 228 | 2.5 | 237 | 6'-6" | 3.2 | 278 | 2.7 | 228 | 6'-6" | 3.2 | 278 | 2.7 | 228 | 6'-6" |
| 7'-0" | 3.5 | 308 | 2.7 | 228 | 2.5 | 237 | 7'-0" | 3.5 | 308 | 2.7 | 228 | 7'-0" | 3.5 | 308 | 2.7 | 228 | 7'-0" |
| 7'-6" | 3.7 | 336 | 2.7 | 228 | 2.5 | 237 | 7'-6" | 3.7 | 336 | 2.7 | 228 | 7'-6" | 3.7 | 336 | 2.7 | 228 | 7'-6" |
| 8'-0" | 3.9 | 367 | 2.7 | 228 | 2.5 | 237 | 8'-0" | 3.9 | 367 | 2.7 | 228 | 8'-0" | 3.9 | 367 | 2.7 | 228 | 8'-0" |

FOR 2nd 30" PIPE DEDUCT 0.18 C.Y. FOR 2nd 42" PIPE DEDUCT 0.36 C.Y., OR 0.18 FOR 1 PIPE FOR 2nd 36" PIPE DEDUCT 0.26 C.Y. FOR 2nd 48" PIPE DEDUCT 0.41 C.Y., OR 0.24 FOR 1 PIPE



ALL REINFORCING STEEL TO BE NO. 5 DEFORMED BARS, EVENLY SPACED WITH A MAXIMUM SPACING OF 12" C/C. ALL STEEL TO HAVE 2 INCH MIN. COVER. DROP INLET TO BE CONSTRUCTED IN ACCORDANCE WITH STRUCTURAL CONCRETE, SECTION 501. GRATES TO CONFORM TO DROP INLETS, CATCH BASINS, AND MANHOLES, SECTION 604. FURNISHING AND LAYING OF BRICKS FOR ADJUSTING ELEVATION OF GRATE SHALL BE INCLUDED IN UNIT BID PRICE FOR CONCRETE, CLASS B, PAY ITEM 50.25, AND THEIR VOLUME TO BE INCLUDED IN THE FINAL QUANTITIES. MORTAR, TYPE II, TO BE USED AS JOINT FILLER AND LAYING OF BRICK. FOR PIPES OF 30" OR MORE IN DIAMETER, ALLOWANCE SHALL BE MADE FOR THE OPENING IN COMPUTING CONCRETE VOLUMES. THIS DEDUCTION WILL BE BASED ON THE RATED DIAMETER OF THE PIPE USED. WITH THE SAME DEDUCTION FOR CONCRETE AND METAL PIPE. ABOVE TABLES INDICATE DEDUCTION FOR ONE PIPE.



TOP AND ADAPTER PLAN VIEW



PLAN VIEW TOP WITH TWO CAST IRON GRATES



PLAN VIEW TOP WITH ONE CAST IRON GRATE


REVISIONS AND CORRECTIONS
APR. 4, 1973 - ORIGINAL APPROVAL
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.

APPROVED
[Signature]
DIRECTOR OF ENGINEERING
[Signature]
DESIGN ENGINEER

REINFORCED CONCRETE DROP INLET WITH GRATE FOR USE IN DITCHES




STANDARD
D-6



GRATE SIZE SINGLE 24 3/4" X 30"
DOUBLE 24 3/4" X 54"

WEIGHT 95 LBS OR MORE
GRATES SHALL BE CAPABLE OF SUPPORTING H-20 (32,000 LB. AXLE LOAD) INCLUDING 30X IMPACT.


| UNIT STRESSES (LBS PER SQ. IN.) | 18,000 | 20,000 |
|--|--------|--------|
| MAIN BAR PARALLEL TO TRAFFIC H-20 | 49" | 53" |
| MAIN BAR PERPENDICULAR TO TRAFFIC H-20 | 39" | 42" |




CAST IRON COVER WITH FRAME

| BAR NO. | LENGTH |
|---------|------------------|
| B | 4 8" 3'-8" 8" |
| C | 6 3'-8" STRAIGHT |
| D | 4 3'-8" STRAIGHT |

ALL REINFORCING STEEL TO BE NO. 5 DEFORMED BARS





ELEVATION



PLAN


GENERAL NOTES:
WEIGHT OF FRAME AND COVER = 425 LBS.



SECTION A-A


RECTANGULAR CAST IRON FRAME FOR TWO 24" SQUARE CAST IRON GRATES

CAST IRON GRATE WITH FRAME



ELEVATION OF REINFORCED CONCRETE DROP INLET WITH VERTICAL GRANITE CURB AND 3 FLANGE CAST IRON FRAME FOR CAST IRON GRATE


SEE STANDARD D-9 FOR CONCRETE VOLUME, REINFORCING STEEL SCHEDULE, AND CURB JOINT DETAIL.




ELEVATION

WEIGHT OF 3 FLANGED FRAME AND GRATE

| | |
|-------|---------|
| GRATE | 220 LBS |
| FRAME | 260 LBS |
| TOTAL | 480 LBS |




SECTION B-B



SQUARE CAST IRON FRAME FOR CAST IRON GRATE TYPE A


* NOTE: FRAME DEPTH TO BE "6" WHEN USED IN CONJUNCTION WITH DROP INLET DETAILED ON STANDARD D-6.

CAST IRON GRATE, TYPE A




PLAN

SECTION C-C



SECTION A-A



SECTION B-B

USE OF THE TYPE A GRATE IS PROHIBITED WHERE BICYCLE TRAFFIC IS EXPECTED

THIS FRAME TO BE PLACED IN DROP INLET TOP BEFORE CONCRETE IS POURED. 4 FLANGES UNLESS OTHERWISE INDICATED. FRAMES TO BE FURNISHED WITH 3 FLANGES WHEN USED IN CONJUNCTION WITH CURB OR AS DIRECTED BY THE ENGINEER.

REVISIONS AND CORRECTIONS

DEC. 6, 1971 - ORIGINAL APPROVAL
APR. 25, 1972 - CAST IRON COVER CHANGED FROM SQUARE TO CIRCULAR
SEPT. 4, 1980 - OPTIONAL CROSSBAR ADDED TO A GRATE; NOTE ADDED TO A GRATE FRAME DETAIL
AUG. 25, 1981 - NOTE ADDED RESTRICTING USE OF TYPE A GRATE
JUNE 1, 1994 - REISSUED, WITHOUT CHANGE, UNDER NEW SIGNATURES.

APPROVED


APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION FROM FINAL APPROVAL PENDING.

Scott C. McArthur, PE
DIRECTOR OF ENGINEERING
Robert D. Murphy, PE
DESIGN ENGINEER

STEEL GRATE
CAST IRON GRATE TYPE A
CAST IRON COVER




STANDARD
D-11




BASIC DIMENSIONS


| A | B | C | D | E | F | G | H | DIAMETER | SLOPE | R ₁ | R ₂ | RATIO |
|-----------|-----------|-----------|-----------|----------|-------------------|-------------------|------------------|----------|-------|----------------|----------------|-------|
| 48 | 36 | 24 | 24 | 4 | 18 | 15 | 10 | 1.52 | 6'-0" | 1 | 1 | 1.00 |
| 36 | 24 | 18 | 18 | 3 | 12 | 9 | 6 | 1.00 | 4'-0" | 1 | 1 | 1.00 |
| 24 | 18 | 12 | 12 | 2 | 8 | 6 | 4 | 0.67 | 3'-0" | 1 | 1 | 1.00 |
| 18 | 12 | 9 | 9 | 1.5 | 6 | 4.5 | 3 | 0.50 | 2'-0" | 1 | 1 | 1.00 |
| 12 | 9 | 6 | 6 | 1 | 4 | 3 | 2 | 0.33 | 1'-0" | 1 | 1 | 1.00 |
| 9 | 6 | 4.5 | 4.5 | 0.75 | 3 | 2.25 | 1.5 | 0.25 | 0'-6" | 1 | 1 | 1.00 |
| 6 | 4.5 | 3 | 3 | 0.5 | 2 | 1.5 | 1 | 0.17 | 0'-4" | 1 | 1 | 1.00 |
| 4.5 | 3 | 2.25 | 2.25 | 0.375 | 1.5 | 1.125 | 0.75 | 0.125 | 0'-3" | 1 | 1 | 1.00 |
| 3 | 2.25 | 1.5 | 1.5 | 0.25 | 1 | 0.75 | 0.5 | 0.083 | 0'-2" | 1 | 1 | 1.00 |
| 2.25 | 1.5 | 1.125 | 1.125 | 0.1875 | 0.75 | 0.5625 | 0.375 | 0.052 | 0'-1" | 1 | 1 | 1.00 |
| 1.5 | 1.125 | 0.75 | 0.75 | 0.125 | 0.5 | 0.375 | 0.25 | 0.033 | 0'-0" | 1 | 1 | 1.00 |
| 1.125 | 0.75 | 0.5625 | 0.5625 | 0.09375 | 0.375 | 0.28125 | 0.1875 | 0.021 | 0'-0" | 1 | 1 | 1.00 |
| 0.75 | 0.5625 | 0.375 | 0.375 | 0.0625 | 0.25 | 0.1875 | 0.125 | 0.014 | 0'-0" | 1 | 1 | 1.00 |
| 0.5625 | 0.375 | 0.28125 | 0.28125 | 0.041667 | 0.1875 | 0.140625 | 0.09375 | 0.009 | 0'-0" | 1 | 1 | 1.00 |
| 0.375 | 0.28125 | 0.1875 | 0.1875 | 0.027778 | 0.125 | 0.09375 | 0.0625 | 0.006 | 0'-0" | 1 | 1 | 1.00 |
| 0.28125 | 0.1875 | 0.140625 | 0.140625 | 0.018519 | 0.09375 | 0.0703125 | 0.046875 | 0.004 | 0'-0" | 1 | 1 | 1.00 |
| 0.1875 | 0.140625 | 0.09375 | 0.09375 | 0.012346 | 0.0625 | 0.046875 | 0.03125 | 0.003 | 0'-0" | 1 | 1 | 1.00 |
| 0.140625 | 0.09375 | 0.0703125 | 0.0703125 | 0.008230 | 0.046875 | 0.03515625 | 0.0234375 | 0.002 | 0'-0" | 1 | 1 | 1.00 |
| 0.09375 | 0.0703125 | 0.0527083 | 0.0527083 | 0.005487 | 0.03125 | 0.0234375 | 0.015625 | 0.001 | 0'-0" | 1 | 1 | 1.00 |
| 0.0703125 | 0.0527083 | 0.0395312 | 0.0395312 | 0.003658 | 0.0234375 | 0.017578125 | 0.01171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0527083 | 0.0395312 | 0.0296458 | 0.0296458 | 0.002439 | 0.017578125 | 0.01318125 | 0.00878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0395312 | 0.0296458 | 0.0222344 | 0.0222344 | 0.001626 | 0.01318125 | 0.009875 | 0.00658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0296458 | 0.0222344 | 0.0166758 | 0.0166758 | 0.001084 | 0.009875 | 0.00740625 | 0.00498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0222344 | 0.0166758 | 0.0125069 | 0.0125069 | 0.000723 | 0.00740625 | 0.00555625 | 0.00371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0166758 | 0.0125069 | 0.0093802 | 0.0093802 | 0.000482 | 0.00555625 | 0.0041675 | 0.002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0125069 | 0.0093802 | 0.0070351 | 0.0070351 | 0.000321 | 0.0041675 | 0.003125 | 0.00208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0093802 | 0.0070351 | 0.0052763 | 0.0052763 | 0.000214 | 0.003125 | 0.00234375 | 0.0015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0070351 | 0.0052763 | 0.0039572 | 0.0039572 | 0.000143 | 0.00234375 | 0.0017578125 | 0.001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0052763 | 0.0039572 | 0.0029679 | 0.0029679 | 0.000095 | 0.0017578125 | 0.001318125 | 0.000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0039572 | 0.0029679 | 0.0022259 | 0.0022259 | 0.000063 | 0.001318125 | 0.0009875 | 0.000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0029679 | 0.0022259 | 0.0016676 | 0.0016676 | 0.000042 | 0.0009875 | 0.000740625 | 0.000498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0022259 | 0.0016676 | 0.0012507 | 0.0012507 | 0.000028 | 0.000740625 | 0.000555625 | 0.000371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0016676 | 0.0012507 | 0.0009381 | 0.0009381 | 0.000019 | 0.000555625 | 0.00041675 | 0.0002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0012507 | 0.0009381 | 0.0007036 | 0.0007036 | 0.000013 | 0.00041675 | 0.0003125 | 0.000208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0009381 | 0.0007036 | 0.0005277 | 0.0005277 | 0.000009 | 0.0003125 | 0.000234375 | 0.00015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0007036 | 0.0005277 | 0.0003958 | 0.0003958 | 0.000006 | 0.000234375 | 0.00017578125 | 0.0001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0005277 | 0.0003958 | 0.0002968 | 0.0002968 | 0.000004 | 0.00017578125 | 0.0001318125 | 0.0000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0003958 | 0.0002968 | 0.0002226 | 0.0002226 | 0.000003 | 0.0001318125 | 0.00009875 | 0.0000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0002968 | 0.0002226 | 0.0001668 | 0.0001668 | 0.000002 | 0.00009875 | 0.0000740625 | 0.0000498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0002226 | 0.0001668 | 0.0001251 | 0.0001251 | 0.000001 | 0.0000740625 | 0.0000555625 | 0.0000371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0001668 | 0.0001251 | 0.0000938 | 0.0000938 | 0.000001 | 0.0000555625 | 0.000041675 | 0.00002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0001251 | 0.0000938 | 0.0000704 | 0.0000704 | 0.000000 | 0.000041675 | 0.00003125 | 0.0000208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000938 | 0.0000704 | 0.0000528 | 0.0000528 | 0.000000 | 0.00003125 | 0.0000234375 | 0.000015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000704 | 0.0000528 | 0.0000396 | 0.0000396 | 0.000000 | 0.0000234375 | 0.000017578125 | 0.00001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000528 | 0.0000396 | 0.0000297 | 0.0000297 | 0.000000 | 0.000017578125 | 0.00001318125 | 0.00000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000396 | 0.0000297 | 0.0000223 | 0.0000223 | 0.000000 | 0.00001318125 | 0.000009875 | 0.00000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000297 | 0.0000223 | 0.0000167 | 0.0000167 | 0.000000 | 0.000009875 | 0.00000740625 | 0.00000498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000223 | 0.0000167 | 0.0000125 | 0.0000125 | 0.000000 | 0.00000740625 | 0.00000555625 | 0.00000371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000167 | 0.0000125 | 0.0000094 | 0.0000094 | 0.000000 | 0.00000555625 | 0.0000041675 | 0.000002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000125 | 0.0000094 | 0.0000070 | 0.0000070 | 0.000000 | 0.0000041675 | 0.000003125 | 0.00000208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000094 | 0.0000070 | 0.0000053 | 0.0000053 | 0.000000 | 0.000003125 | 0.00000234375 | 0.0000015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000070 | 0.0000053 | 0.0000039 | 0.0000039 | 0.000000 | 0.00000234375 | 0.0000017578125 | 0.000001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000053 | 0.0000039 | 0.0000029 | 0.0000029 | 0.000000 | 0.0000017578125 | 0.000001318125 | 0.000000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000039 | 0.0000029 | 0.0000022 | 0.0000022 | 0.000000 | 0.000001318125 | 0.0000009875 | 0.000000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000029 | 0.0000022 | 0.0000017 | 0.0000017 | 0.000000 | 0.0000009875 | 0.000000740625 | 0.000000498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000022 | 0.0000017 | 0.0000013 | 0.0000013 | 0.000000 | 0.000000740625 | 0.000000555625 | 0.000000371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000017 | 0.0000013 | 0.0000010 | 0.0000010 | 0.000000 | 0.000000555625 | 0.00000041675 | 0.0000002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000013 | 0.0000010 | 0.0000009 | 0.0000009 | 0.000000 | 0.00000041675 | 0.0000003125 | 0.000000208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000010 | 0.0000009 | 0.0000007 | 0.0000007 | 0.000000 | 0.0000003125 | 0.000000234375 | 0.00000015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000009 | 0.0000007 | 0.0000005 | 0.0000005 | 0.000000 | 0.000000234375 | 0.00000017578125 | 0.0000001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000007 | 0.0000005 | 0.0000004 | 0.0000004 | 0.000000 | 0.00000017578125 | 0.0000001318125 | 0.0000000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000005 | 0.0000004 | 0.0000003 | 0.0000003 | 0.000000 | 0.0000001318125 | 0.00000009875 | 0.0000000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000004 | 0.0000003 | 0.0000002 | 0.0000002 | 0.000000 | 0.00000009875 | 0.0000000740625 | 0.0000000498125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000003 | 0.0000002 | 0.0000002 | 0.0000002 | 0.000000 | 0.0000000740625 | 0.0000000555625 | 0.0000000371875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000002 | 0.0000002 | 0.0000001 | 0.0000001 | 0.000000 | 0.0000000555625 | 0.000000041675 | 0.00000002779167 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000002 | 0.0000001 | 0.0000001 | 0.0000001 | 0.000000 | 0.000000041675 | 0.00000003125 | 0.0000000208125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000001 | 0.0000001 | 0.0000000 | 0.0000000 | 0.000000 | 0.00000003125 | 0.0000000234375 | 0.000000015625 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000001 | 0.0000000 | 0.0000000 | 0.0000000 | 0.000000 | 0.0000000234375 | 0.000000017578125 | 0.00000001171875 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000000 | 0.0000000 | 0.0000000 | 0.0000000 | 0.000000 | 0.000000017578125 | 0.00000001318125 | 0.00000000878125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000000 | 0.0000000 | 0.0000000 | 0.0000000 | 0.000000 | 0.00000001318125 | 0.000000009875 | 0.00000000658125 | 0.000 | 0'-0" | 1 | 1 | 1.00 |
| 0.0000000 | 0.0000000 | 0.0000000 | 0.0000000 | 0.000000 | 0.000000009875 | 0.00000000740625 | 0.00000000498125 | | | | | |



| SIGN | DIMENSIONS (INCHES) | | | | | | | | | | |
|---------|---------------------|-----|-------|----|-------|-------|--------|--------|--------|-------|---|
| | A | B | C | D | E | F | G | H | J | K | L |
| MIN. | 30 | 1/4 | 3/4 | 40 | 2 1/2 | 2 1/2 | 6 1/2 | 7 | 7 1/2 | 1 1/2 | 3 |
| STD. | 30 | 3/8 | 3/4 | 50 | 3 1/4 | 3 1/4 | 6 1/2 | 8 1/2 | 9 | 2 1/4 | 3 |
| SPECIAL | 48 | 3/4 | 1 1/4 | 70 | 4 1/4 | 4 1/4 | 11 1/4 | 12 1/4 | 12 1/4 | 3 | 3 |



| DIMENSIONS (INCHES) | | | | | | | |
|---------------------|--------|--------|--------|--------|--------|--------|--------|
| A | B | C | D | E | F | G | H |
| 40 | 8 1/4 | 8 1/4 | 8 1/2 | 9 | 9 | 7 1/2 | 8 1/4 |
| 50 | 10 1/4 | 10 1/4 | 10 1/2 | 11 1/4 | 11 1/4 | 9 1/2 | 10 1/4 |
| 70 | 14 1/4 | 14 1/4 | 14 1/2 | 15 1/4 | 15 1/4 | 13 1/2 | 14 1/4 |



G20-1
THIS SIGN TO BE USED WHEN PROJECT LENGTH EXCEEDS 2 MILES OR AS REQUESTED BY THE RESIDENT ENGINEER. SHOW MILEAGE TO NEAREST 1/4 MILE USING FRACTIONS, NOT DECIMALS. HAND LETTERING OF MILEAGE WILL NOT BE ALLOWED.

NOTES CONT.

MAINTENANCE
SIGNS SHALL BE MAINTAINED IN A CLEAN AND LEGIBLE CONDITION SATISFACTORY TO THE ENGINEER. THEY SHALL BE COMPLETELY VISIBLE TO APPROACHING TRAFFIC AT ALL TIMES. THEY SHALL BE KEPT PLUMB AND LEVEL, AND ALWAYS PRESENT A NEAT APPEARANCE. DAMAGED, DEFACED, OR DIRTY SIGNS SHALL BE REPAIRED, CLEANED OR REPLACED AS ORDERED BY THE ENGINEER.

GENERAL
THE COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING ALL CONSTRUCTION APPROACH SIGNS WILL BE CONSIDERED CONSTRUCTION WORK PERTAINING TO THE PROJECT AS A WHOLE AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR VARIOUS ITEMS INVOLVED IN THE CONTRACT. DURING ALL PHASES OF CONSTRUCTION THE REQUIREMENTS SET FORTH IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" SHALL BE MET. WHEN THE PROJECT IS CLOSED DOWN FOR TEMPORARY PERIODS THE SIGNS SHALL BE COVERED IN A WORKMANLIKE MANNER.

SIGN COVERS
SIGN COVERS SHALL CONSIST OF A PANEL FINISHED FLAT BLACK, THE SAME SIZE AS THE SIGN IT COVERS. THE PANEL SHALL BE OF WOOD, PLYWOOD, HARDBOARD OR ANY MATERIAL SATISFACTORY TO THE ENGINEER. NO MATERIAL WILL BE APPROVED THAT WILL DETERIORATE BY EXPOSURE TO THE WEATHER DURING THE PROJECT. MOUNTING OF THE PANEL SHALL BE DONE IN SUCH A WAY AS NOT TO DAMAGE THE SIGN FACE MATERIAL. CONTRACTORS SHALL COORDINATE THEIR SIGNING ACTIVITIES WITH OTHER CONTRACTORS WITHIN THE PROJECT LIMITS, AS DIRECTED BY THE REGIONAL CONSTRUCTION ENGINEER.

SIGN POSTS

WHERE CONSTRUCTION SIGN INSTALLATIONS ARE NOT PROTECTED BY GUARD RAIL OR OTHER APPROVED TRAFFIC BARRIER THE POSTS ON WHICH THE SIGNS ARE MOUNTED SHALL BE YIELDING METAL POSTS AS DESIGNATED IN THE SERIES OF STANDARD DRAWINGS OR YIELDING WOODEN POSTS IN ACCORDANCE WITH THE FOLLOWING REQUIREMENTS:

WOODEN POSTS ARE ACCEPTABLE FOR USE WITH CONSTRUCTION SIGNS. THESE POSTS SHALL HAVE A UNIFORM CROSS-SECTION AND SHALL BE MADE FROM GRADE 2, DROVE OR SOUTHERN YELLOW PINE OR ANOTHER EQUIVALENT SOFTWOOD. AN ACCEPTABLE EQUIVALENT SOFTWOOD SHALL BE AN EXTREME FIBER IN RESISTANCE TO WEAVER. DESIGN VALUE NOT TO EXCEED 1400 PSI AND HORIZONTAL SHEAR "V" DESIGN VALUE NOT TO EXCEED 90 PSI SPECIFICATION DESIGN VALUES FOR WOOD CONSTRUCTION AND RELATED SUPPLEMENT, DATED 1986.

AS ESTABLISHED BY THE NATIONAL FOREST PRODUCTS ASSOCIATION IN THEIR NATIONAL DESIGN THE FOLLOWING ARE CONSIDERED TO BE ACCEPTABLE WOODEN POSTS:

- 4' x 4' (ACTUAL DIMENSIONS ARE 3.5" x 3.5")
 - ACCEPTABLE FOR SINGLE OR DUAL POSTS INSTALLATION WITH NO MODIFICATIONS.
- 4' x 6' (ACTUAL DIMENSIONS ARE 3.5" x 5.5")
 - ACCEPTABLE FOR SINGLE POST INSTALLATIONS ONLY WHEN MODIFIED BY DRILLING TWO 1 1/2" DIAMETER HOLES, ONE AT 4" AND THE OTHER 18" ABOVE THE GROUND LINE AND PERPENDICULAR TO THE ROADWAY CENTERLINE.
- 6' x 6' (ACTUAL DIMENSIONS ARE 5.5" x 5.5")
 - ACCEPTABLE FOR SINGLE POST INSTALLATIONS ONLY WHEN MODIFIED BY DRILLING TWO 2" DIAMETER HOLES, ONE AT 4" AND THE OTHER AT 18" ABOVE THE GROUND LINE AND PERPENDICULAR TO ROADWAY CENTERLINE.
- 6' x 8' (ACTUAL DIMENSIONS ARE 5.5" x 7.5")
 - ACCEPTABLE FOR SINGLE POST INSTALLATIONS ONLY WHEN MODIFIED BY DRILLING TWO 2" DIAMETER HOLES, ONE AT 4" AND THE OTHER AT 18" ABOVE THE GROUND LINE AND PERPENDICULAR TO THE ROADWAY CENTERLINE.

ADDITIONAL DESIGN CRITERIA

THE LONGER DIMENSION OF THE POST(S), SUCH AS THE 6' DIMENSION OF THE 4' x 6' POST, SHALL BE PLACED PARALLEL TO THE ROADWAY CENTERLINE.
ALL WOODEN POSTS SHALL HAVE AN EMBEDMENT DEPTH OF 4 FEET.
NO CROSS-BRACING OR BACK-BRACING TO KEEP THE POSTS PLUMB WILL BE ALLOWED. CONCRETE FOUNDATIONS, COLLARS, OR SOIL BEARING PLATES ARE NOT PERMITTED. CONSTRUCTION SIGNS SHALL BE PLACED ON TWO OR MORE POSTS WHEN ANY OF THE FOLLOWING CONDITIONS OCCUR:
A) THE SIGN WIDTH (HORIZONTAL DIMENSIONS FOR DIAMOND SHAPED SIGNS) EXCEEDS 3 1/2 FEET.
B) THE EXPOSED SIGN AREA OF ANY SINGLE SIGN OR ASSEMBLY EXCEEDS 12 1/2 SQ. FEET.
C) THE SV OF A SINGLE POST IS EXCEEDED. (SEE THE POST SELECTION CHART BELOW).

| WOOD POST SELECTION CHART | |
|---|-----------------|
| SIGN AREA (FT ²) X HEIGHT (FT) < SV | DESIGN CRITERIA |
| POST SIZE | SV |
| 4' x 4' | 64 |
| 4' x 6' | 147 |
| 6' x 6' | 216 |
| 6' x 8' | 309 |

| DESIGN CRITERIA | VALUE |
|--------------------------|--------------------|
| WIND SPEED | 60 MPH (10-DECADE) |
| MEAN OCCURRENCE INTERVAL | 10 YEARS |
| WIND PRESSURE | 13 psf |
| ALLOWABLE BENDING STRESS | S |

POST SELECTION CHART DETAIL

NOTES

THE SIGNS SHOWN ON THIS SHEET ARE INTENDED FOR USE IN PROVIDING ADVANCE WARNING AND INFORMATION ON CONSTRUCTION PROJECTS OVER WHICH TRAFFIC WILL BE FURNISHING APPROACH SIGNS. OTHER TYPES OF ADVANCE SIGNING OR CONTROL ARE NECESSARY. THE PLANS AND/OR THE SPECIFICATIONS FOR THAT PROJECT WILL DEFINE THE DETAILS OF THE SIGNS AND DEVICES REQUIRED. FOR ON-PROJECT CONSTRUCTION SIGNS REFER TO APPROPRIATE STANDARD SHEETS.

APPLICATION OF STANDARDS
SINCE IT IS NOT POSSIBLE TO PRESCRIBE DETAILED STANDARDS OF APPLICATION FOR ALL OF THE SITUATIONS THAT MAY CONCEIVABLY ARISE ON A CONSTRUCTION PROJECT, REFERENCE SHALL BE MADE TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" FOR THE PARTICULAR PROCEDURES AND STANDARDS THAT WILL BE REQUIRED IN CONNECTION WITH ADVANCED WARNING AND ON-PROJECT CONSTRUCTION SIGNS AND BARRIAGES. THE SIGNS SHOWN IN E-101 AND E-102 REPRESENT A SAMPLE OF THOSE MORE COMMONLY USED.

LOCATION

THE SIGNS SHALL BE LOCATED AS DETAILED ON THIS SHEET OR AS OTHERWISE SHOWN ON THE PLANS. THEY SHALL APPEAR AT EACH END OF THE HIGHWAY UNDER CONSTRUCTION AND ON ALL INTERSECTING PUBLIC HIGHWAYS. THE EXACT PLACEMENT OF ANY SIGN WILL DEPEND UPON THE ALIGNMENT INTENDED TO INDICATE THE SEQUENCE TO BE FOLLOWED AND THE APPROPRIATE SPACING TO BE OBSERVED. THE ENGINEER SHALL DETERMINE THE EXACT LOCATIONS.

LETTERS

LETTERS, DIGITS, ARROWS, SPACING AND TEXT DIMENSIONS SHALL CONFORM WITH THE "STANDARD ALPHABET FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" AND DESIGNS PRESCRIBED IN THE STANDARD HIGHWAY SIGNS AS SPECIFIED IN THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES ADOPTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMIN.

MATERIALS

THE SIGN BASE MATERIAL USED FOR THE SIGNS ON THIS SHEET MAY BE ANY OF THE FOLLOWING, WITH MINIMUM THICKNESSES AS NOTED:
FLAT SHEET ALUMINUM 0.125 INCHES
HIGH DENSITY OVERLAPPED PLYWOOD 7/8 INCHES
GALVANIZED SHEET STEEL 1/2 GAGE

REFLECTORIZATION


ALL REFLECTORIZED MATERIAL SHALL CONSIST OF TYPE 11B OR TYPE 111 SHEETS.

COLORS


THE COLORS SHALL CONFORM WITH THE STANDARD COLORS ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS AND APPROVED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION. COLORS SHOWN ON THIS SHEET CONSIST OF BLACK TEXT AND BORDER ON A REFLECTORIZED ORANGE BACKGROUND.

INSTALLATION

THE SIGNS SHALL BE ERECTED BEFORE THE START OF ANY WORK AND SHALL BE COVERED UNTIL WORK COMMENCES. DURING PERIODS OF INACTIVITY, OR UPON COMPLETION OF THE WORK, SIGNS MAY BE REMOVED UPON COMPLETION OF THE WORK AT THE DISCRETION OF THE ENGINEER. EACH SIGN SHALL BE ERECTED IN A NEAT AND WORKMANLIKE MANNER ON POSTS SET SECURELY IN THE GROUND. THE BOTTOM OF A SIGN SHALL BE AT LEAST 7 FEET ABOVE THE EDGE OF PAVEMENT, AND THE NEAREST EDGE OF A SIGN SHALL BE AT LEAST 6 FEET OUTSIDE THE SHOULDER OR FEET OUTSIDE THE CURB OR 6 FEET OUTSIDE THE CURBING OR SIDEWALK. THE INSTALLATION OF SIGNS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER. IN URBAN AREAS, THE BOTTOM OF THE SIGN SHALL BE AT LEAST 7 FEET ABOVE THE SIDEWALK.



G20-2A



TYPICAL APPROACH SIGNING
(SIGNS NOT SHOWN FOR OPPOSITE DIRECTION)

REVISIONS AND CORRECTIONS

- MAY 26, 1989 - DATE OF ORIGINAL ISSUE
- OCT 24, 1992 - REVISED WOOD POST REQUIREMENTS, ADDED SIGN DETAILS, & REVISED TITLE BLOCK
- AUG 08, 1995 - MINOR NOTE REVISIONS
- JAN 06, 1997 - MINOR NOTE AND DIMENSION REVISIONS

APPROVED

[Signature]
DIRECTOR OF ENGINEERING


[Signature]
DIRECTOR OF CONSTRUCTION AND MAINTENANCE

CONSTRUCTION APPROACH SIGNS

OTHER STANDARDS REQUIRED:




STANDARD E-100



STOP SIGN SHALL BE PLACED ON DRIVERS RIGHT, MAINTAINING MAXIMUM VISIBILITY. CLEARANCE SHALL BE A MINIMUM OF 6' AND A MAXIMUM OF 50' FROM EDGE LINE OF INTERSECTING ROADWAY AND DOES NOT HAVE TO BE ADJACENT TO THE STOP BAR.


LEGAL LOAD LIMIT AND STOP SIGNS AT INTERSECTIONS WITH TOWN HIGHWAYS



4" X 3" X 3/16" RECTANGULAR GALVANIZED STRUCTURAL STEEL TUBING



SIGNS ON MEDIAN ISLANDS IN THE LINE OF TRAFFIC

TO INSURE A TIGHT CONNECTION GALVANIZED WASHERS SHALL BE USED AS SPACERS.




SLEEVE DETAIL "A"

INCREASE VERTICAL CLEARANCE TO 7' IN AREAS OF FREQUENT ROADSIDE PARKING OR PEDESTRIAN ACTIVITY





SEE NOTE # 1




SEE NOTE # 1

RURAL



IF SUFFICIENT CLEARANCE IS NOT AVAILABLE BETWEEN CURB AND SIDEWALK MOUNT SIGN BEHIND SIDEWALK AS SHOWN AT TOP. CHECK FOR ADEQUATE R.O.W.



SEE NOTE # 1

URBAN

NOTES:

1. IN BOTH RURAL AND URBAN LOCATIONS, IF A SECONDARY SIGN IS MOUNTED BELOW ANOTHER SIGN, THE MINIMUM CLEARANCE MAY BE REDUCED BY ONE FOOT.
 2. IN RURAL AREAS WITH NO OR MINIMAL SHOULDER, THE LATERAL CLEARANCE TO THE EDGE OF A SIGN SHOULD BE A MINIMUM OF 12' FROM THE EDGE OF THE TRAVELED WAY.
 3. ALSO SEE OTHER STANDARD SHEETS FOR MOUNTING CLEARANCE AND SPACING OF DESTINATION AND ROUTE MARKER ASSEMBLIES AND TOWN LINE SIGNS.
- POST REFERENCE:
REFER TO THE DETAILS ON THE APPROPRIATE STANDARD DRAWING FOR INFORMATION CONCERNING THE PROPER MOUNTING OF SIGNS ON APPROPRIATE POSTS.

OTHER STDS. E-160 E-161 E-162 E-163 E-164
REQUIRED:

REVISIONS AND CORRECTIONS
JAN. 23, 1995 - DATE OF ORIGINAL ISSUE
AUG. 08, 1995 - VARIOUS MINOR NOTE REVISIONS

APPROVED

Scott J. McCall
DIRECTOR OF ENGINEERING

David A. Ross
TRAFFIC AND SAFETY ENGINEER

**STANDARD SIGN PLACEMENT
CONVENTIONAL ROAD**



**STANDARD
E-121**

APPROVED FOR THIS PROJECT AND/OR DESIGN IMPLEMENTATION. FINAL APPROVAL PENDING.

/traf/std/stc02l.dgn | std02LI