



- LEGEND**
- /// - PAVEMENT MARKING REMOVAL
  - - REFLECTORIZED PLASTIC DRUM
  - - TYPE I DELINEATOR (YELLOW)
  - - TYPE I DELINEATOR (WHITE)
  - ▤ - CONCRETE MEDIAN BARRIER
  - ▣ - TYPE III BARRICADE
  - ▢ - FLASHING ARROW PANEL
  - +
  - 
  - <f=
  -

- NOTES**
- 1) THIS SHEET IS INTENDED TO BE USED WITH STD. E-104 AND REQUIRES STD. E-103 FOR ADVANCE SIGNING.
  - 2) THE TEMPORARY TAPE PAVEMENT MARKINGS SHALL BE OF A TYPE WHICH CAN BE COMPLETELY REMOVED AFTER THE PROJECT WITHOUT SCARRING OR MARKING THE PAVEMENT SURFACE. PAYMENT FOR THE TAPE MARKINGS SHALL BE UNDER THE APPROPRIATE ITEM NUMBERS.
  - 3) PAVEMENT MARKING REMOVALS SHALL BE PAID UNDER THE APPROPRIATE ITEM NUMBER. TEMPORARY TAPE REMOVAL IS NOT PAID UNDER THE REMOVAL ITEM, IT IS SUBSIDIARY TO THE TAPE ITEM.
  - 4) THE RAISED PAVEMENT MARKINGS (RPM'S) SHALL BE OF A TYPE WHICH CAN BE EASILY REMOVED AND THEY SHALL BE PLACED TO THE OUTSIDE OF THE TEMPORARY TAPE PAVEMENT MARKINGS. THE RPM'S SHALL BE SPACED AT 20 FT. THE RPM'S ARE TO BE PAID UNDER THE ITEM TEMPORARY RAISED PAVEMENT MARKINGS. IF RPM'S ARE BUILT INTO AND INCLUDED AS A PART OF THE TEMPORARY TAPE PAVEMENT MARKINGS, THEN THE COST OF THE RAISED MARKERS SHALL BE CONSIDERED AS PART OF THE TEMPORARY PAVEMENT MARKING ITEM AND SEPERATE RPM'S ARE NOT REQUIRED.
  - 5) TAPE OR PAINT SHALL NOT BE ALLOWED ON THE SIDE OF THE CONCRETE MEDIAN BARRIER.

REVISIONS AND CORRECTIONS

OCT21, 1992 - CHANGED TAPER LAYOUTS PER STD. E-104  
- MINOR REVISIONS

APPROVED

JAN. 23, 1989  
DATE

*Gordon L. MacArthur*  
DIRECTOR OF ENGINEERING

*David A. Ross*  
TRAFFIC AND SAFETY ENGINEER

**PAVEMENT MARKING DETAILS - DIVIDED HIGHWAY**  
**ONE ROADWAY CLOSED**

