



**MATERIALS**

The sign base material used for the guide signs shown on this sheet shall be designated by the following identification letters.

A - Acrylic Overlaid Plywood, 3/4" minimum thickness.

B - Extruded Aluminum Panels, with baked enamel finish.

The reflective material used for the text shall be acrylic plastic reflectors in embossed letter frames.

**COLORS**

The signs shall have a reflectorized white text on a non-reflectorized blue background as indicated for each sign. The blue shall conform with the standard colors adopted by the American Association of State Highway and Transportation Officials and approved by the U.S. Department of Transportation, Federal Highway Administration.

**LETTERING**

Letters and digits shall conform with series D of the standard alphabet for highway signs approved by the National Joint Committee on Uniform Traffic Control Devices, with a stroke width modified to one fifth the height.

The design of these signs shall conform with the requirements set forth in the manual for Signing and Pavement Marking of the National Systems of Interstate and Defense Highways adopted by the American Association of State Highway and Transportation Officials.

**SPECIFICATION**

The signs shall meet standard state specifications for "Traffic Signs."

REVISIONS AND CORRECTIONS  
JUNE 30, 1976 - SIZE OF "I" INCREASED TO 15".

APPROVED

May 6, 1976  
DATE  
*E. H. Stickney*  
CHIEF ENGINEER  
*R. O. Munn*  
ASSY. CHIEF ENGINEER  
*Leon E. Jones*  
HIGHWAY ENGINEER

TRAFFIC SIGNS

GUIDE SIGNS

VERMONT  
DEPARTMENT  
OF HIGHWAYS  
STANDARD

E-14 A