

STREET SIGNS: MATERIALS

THE SIGN BASE MATERIALS USED FOR THE STREET SIGNS MAY BE EITHER OF THE FOLLOWING:
A - EXTRUDED ALUMINUM BLADES WITH REFLECTIVE SHEETING
B - FLAT ALUMINUM BLADES WITH REFLECTIVE SHEETING

1" RADIUS (TYP.)

S SAMPLE ST

VAR. 24" - 42"

RURAL

1 1/2"

6"

4"

1 1/2"

9"

ROUTE MARKER ASSEMBLY FRAMES

FRAME FOR
THREE ASSEMBLIES

Technical drawing of a rectangular frame. The drawing includes a note at the top: $\frac{1}{4}''$ TYP. pointing to the corner joints. The frame is defined by four lines: a top line, a bottom line, a left line, and a right line. The dimensions are as follows:

- Top line: 28 $\frac{1}{2}''$ (total length), with 13 $\frac{1}{2}''$ on each side of the center.
- Bottom line: 34 $\frac{1}{2}''$ (total length), with 16 $\frac{1}{2}''$ on each side of the center.
- Left line: 18 (total height), with 6'' on each side of the center.
- Right line: 12 (total height), with 6'' on each side of the center.

The drawing also shows a vertical dimension of 34'' on the far left and a horizontal dimension of 18'' on the far right, indicating the overall size of the assembly.

REVISIONS AND CORRECTIONS

12/1/82
ADDED 2 FRAME ASSEMBLY TO 2 POST ASSEMBLY
ADDED MINOR DESTINATION SIGN, MOUNTING HEIGHT
REVISED
2/10/83
SIGN HEIGHT CHANGED TO 7 FT.

FEB. 3, 1986 - UPDATED TO 1986
SPECIFICATIONS
DEC. 3, 1986 MAJOR REVISIONS

APPROVED

Dec 29, 1971

R. H. Arnold

E. H. Stickney

G. M. Lane

GUIDE SIGNS