QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

NON-PARTICIPATING	LANDSCAPING	EROSION	SIDEWALK	QUANTITIES	UNIT	ITEMS	ITEM NO.	ROUNDING
			1	1	LS	CLEARING & GRUBBING	201.10	
			1,070	1,070	CY	COMMON EXCAVATION	203.15	
			110	110	CY	EXCAVATION OF SURFACES & PAVEMENTS	203.28	
			40	40	CY	EARTH BORROW	203.30	EST
			40	40	CY	SAND BORROW	203.31	EST
			180	180	CY	TRENCH EXCAVATION OF EARTH	204.20	
			15	15	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	EST
			75	75	CY	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.26	
			575	575	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	
			4	4	CWT	EMULSIFIED ASPHALT	404.65	
			288	288	TON	BITUMINOUS CONCRETE PAVEMENT	406.25	
			0.5	0.5	MFBM	NON-STRUCTURAL LUMBER - TREATED	522.35	EST
						** BEGIN PIPE OPTIONS **		
			245	245	LF	12" CSP (.064, 2-2/3 X 1/2)	601.0005	2
			245	245	LF	12" CAAP (.060, 2-2/3 X 1/2)	601.0205	2
			245	245	LF	12" PCCSP (.064, 2-2/3 X 1/2)	601.0405	2
			245	245	LF	12" CPEP(SL)	601.2605	2
						** END PIPE OPTIONS **		
			17	17	CY	DRY RUBBLE MASONRY	602.20	
			3	3	EA	PRECAST REINFORCED CONC. CATCH BASIN WITH TYPE D CAST IRON GRATE	604.20	
			1	1	EA	PRECAST REINFORCED CONC, MANHOLE WITH CAST IRON COVER	604.21	
			2	2	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	
			2	2	EA	CAST IRON GRATE AND FRAME, TYPE A (MODIFIED - CURB INLET)	604.45	
			1	1	MGAL	DUST CONTROL WITH WATER	609.10	EST
			230	230	CY	STONE FILL, TYPE II	613.11	EST
			410	410	LF	CAST IN PLACE CONCRETE CURB, TYPE B	616.28	4
			9	9	LF	REMOVAL OF EXISTING CURB	616.41	
			7	7	EA	RELOCATE MAIL BOX SINGLE SUPPORT	617.10	
			840	840	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	
			85	85	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	0.7
			6	6	SY	DETECTABLE WARNING SURFACE	618.30	
			220	220	LF	CHAIN LINK FENCE - 4 FEET	620.11	
			2	2	EA	BRACING ASSEMBLY FOR CHAIN LINK FENCE - 4 FEET	620.20	
			30	30	LF	REMOVING AND RESETTING FENCE	620.50	
		620		620	LF	SNOW FENCE (MODIFIED 1-CONSTRUCTION FENCE)	620.70	EST
		1,000		1,000	LF	SNOW FENCE (MODIFIED2- PROJECT DEMARCATION FENCE)	620.70	EST
			30	30	LF	STEEL BEAM GUARD RAIL	621.20	
			25	25	LF	REMOVING AND RESETTING OF GUARD RAIL	621.75	
			500	500	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
			1000	1000	HR	FLAGGERS	630.15	
			1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
			1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS

PROJECT NAME - ESSEX CENTER SIDEWALK STP WALK (9)
PROJECT NUMBER 02-132