QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

		NON-PARTICIPATING		LANDSCAPING	EROSION	ROAD	QUANTITIES	UNIT	ITEMS	ITEM NO.	ROUNDING
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
						1	1	LS	TRAFFIC CONTROL	641.10	
						1,050	1,050	LF	DURABLE 4" WHITE LINE (TYPE I TAPE)	646.40	6
						3050	3050	LF	DURABLE 4" YELLOW LINE (TYPE I TAPE)	646.41	7
						2,570	2,570	LF	DURABLE 6" WHITE LINE (TYPE I TAPE)	646.414	6
						9	9	LF	DURABLE 8" YELLOW LINE (TYPE I TAPE)	646.43	
						20	20	LF	DURABLE 24" STOP BAR (TYPE I TAPE)	646.46	
						22	22	EA	DURABLE LETTER OR SYMBOL	646.50	
						25	25	LF	DURABLE CROSSWALK WITH DIAGONAL LINES (TYPE 1 TAPE)	646.51	
						2,500	2,500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	
					835		835	SY	GEOTEXTILE FOR SILT FENCE	649.51	
				45			45	LB	SEED	651.15	1.5
				185			185	LB	FERTILIZER	651.18	
				1			1	T	AGRICULTURAL LIMESTONE	651.20	0.25
				1			1	T	HAY MULCH	651.25	0.25
					40		40	EA	HAYBALES FOR EROSION CONTROL	651.26	
				195			195	CY	TOPSOIL	651.35	
				414			414	SY	GRUBBING MATERIAL	651.40	
					1		1	LS	EROSION & SEDIMENT CONTROL PLAN	652.10	
					200		200	HR	MONITORING EROSION & SEDIMENT CONTROL PLAN	652.20	
					1		1	LU	FIELD MAINTENANCE OF EROSION & SEDIMENT CONTROL PLAN	652.30	
									EVERGREEN TREES	656.20	
				1			1	EA	(Picea abies, NORWAY SPRUCE) (6' – 8' HEIGHT)		
									DECIDUOUS TREES	656.30	
				3			3	EA	(Fraxinus pennsylvanica, MARSHALL'S SEEDLESS ASH) (2 1/2" – 3" CAL)		
				4			4	EA	(Gleditsia triacanthos, HALKA HONEY LOCUST) (2 1/2" – 3" CAL)		
				3			3	EA	(Quercus rubra, NORTHERN RED OAK (2 1/2" – 3" CAL)		
				2			2	EA	(Robinia pseudoacacia, BLACK LOCUST) (2 1/2" – 3" CAL)		
				1			1	EA	TRANSPLANTING TREES	656.45	
				2			2	EA	TRANSPLANTING SHRUBS	656.50	
						71	71	SF	TRAFFIC SIGNS, TYPE A	675.20	0.25
						120	120	LF	FLANGED CHANNEL SIGN POSTS	675.301	0.25
						5	5	EA	REMOVING SIGNS	675.50	
						1	1	EA	ERECTING SALVAGED SIGNS	675.60	
						1	1	EA	ERECTING SALVAGED POSTS	675.61	
		440				155	595	LF	WIRED CONDUIT	678.23	
		1				4	5	EA	JUNCTION BOX	678.26	
		4				2	6	EA	LIGHT POLE BASE	679.21	
		4				2	6	EA	LIGHT POLE	679.45	
		4				2	6	EA	BRACKET ARM	679.47	
		4				2	6	EA	LUMINAIRE	679.50	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	–			

PROJECT NAME – ESSEX CENTER SIDEWALK STP WALK (9)
PROJECT NUMBER 02-132

I:\STPWALK(9)\Sfm.dgn 12/21/2005 10:38:43 AM