QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		FULL C.E.	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		-	-	1	-	1	LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-
		-	-	-	20	20	CY	COMMON EXCAVATION	203.15	8
		-	-	310	-	310	CY	CHANNEL EXCAVATION OF EARTH	203.25	6
		-	-	-	110	110	CY	EARTH BORROW	203.30	-
		-	-	150	-	150	CY	STRUCTURE EXCAVATION	204.25	-
		-	-	80	-	80	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	8
		-	-	-	80	80	CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25	4
		-	-	-	15	15	TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.27	3
					1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
		-	-	75	-	75	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	4
		-	-	1	-	1	LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10	-
		-	-	2	-	2	EA	DYNAMIC PILE LOADING TEST	505.45	-
		-	-	29,410	-	29,410	LB	STRUCTURAL STEEL, ROLLED BEAM	506.50	5
		-	-	11,400	-	11,400	LB	STRUCTURAL STEEL	506.60	4
		-	-	4,340	-	4,340	LB	REINFORCING STEEL	507.15	-
		-	-	1	-	1	LS	STRUCTURAL PAINTING, SHOP APPLIED	513.25	-
		-	-	1	-	1	LS	STRUCTURAL PAINTING, FIELD APPLIED	513.30	-
		-	-	1	-	1	LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD	513.36	-
		-	-	1	-	1	LS	SURFACE PREPARATION, SHOP	513.40	-
		-	-	1	-	1	LS	SURFACE PREPARATION, FIELD	513.41	-
		-	-	4	-	4	GAL	WATER REPELLENT, SILANE	514.10	-
		-	-	6	-	6	MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25	-
		-	-	65	-	65	LF	METAL HAND RAILING	525.15	-
		-	-	110	-	110	CY	STONE FILL, TYPE II	613.11	-
		-	-	260	-	260	CY	STONE FILL, TYPE III	613.12	-
		-	-	-	2	2	EA	BOLLARDS	619.14	-
		-	-	-	195	195	LF	CHAIN-LINK FENCE, 6 FEET	620.12	3
		-	-	-	4	4	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	-
		-	-	-	54	54	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-
		-	-	-	2	2	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	-
		-	-	-	2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
		1	-	-	-	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1	-	-	-	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
		1	-	-	-	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		1	-	-	-	1	LS	TESTING EQUIPMENT, PROTECTIVE COATINGS	631.18	-
		1	-	-	-	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
		-	-	-	1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
		-	-	-	1	1	LS	TRAFFIC CONTROL	641.10	-
		-	-	260	-	260	SY	GEOTEXTILE UNDER STONE FILL	649.31	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET 1

PROJECT NAME: WALLINGFORD
PROJECT NUMBER: STP ST WALK(14)

Drawing Copyright © 2009

CHA

FILE NAME: $FILES$
PROJECT MANAGER: SUSAN SCRIBNER
DESIGNED BY: L. HARDEN
BRIDGE DESIGN SUPERVISOR: P. HALSTEAD

PLOT DATE: 1/22/2009
DRAWN BY: W. WEATHERBY
CHECKED BY: P. HALSTEAD
SHEET 3 OF 26

FILE NAME =u:\0659\MSTN\prefinal_submission\x82f136quan.dgn
DATE/TIME =1/22/2009
USER =2552