QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		FULL C.E.	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		-	90	-	-	90	SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	8
		-	150	-	-	150	SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	4
		-	-	-	10	10	LB	SEED	651.15	-
		-	-	-	50	50	LB	FERTILIZER	651.18	-
		-	-	-	1	1	TON	AGRICULTURAL LIMESTONE	651.20	-
		-	-	-	10	10	CY	TOPSOIL	651.35	-
		-	1	-	-	1	LS	EPSC PLAN	652.10	-
		-	100	-	-	100	HR	MONITORING EPSC PLAN	652.20	-
		-	1	-	-	1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-
		-	80	-	-	80	SY	TEMPORARY EROSION MATTING	653.20	-
		-	140	-	-	140	CY	VEHICLE TRACKING PAD	653.35	8
		-	210	-	-	210	LF	BARRIER FENCE	653.50	6
		-	875	-	-	875	LF	PROJECT DEMARCATION FENCE	653.55	12
		-	-	600	-	600	EA	SPECIAL PROVISION (THROUGH TRUSS RIVET REPLACEMENT)	900.620	-
		-	-	248	-	248	LF	SPECIAL PROVISION (BRIDGE RAILING, STEEL/PEDESTRIAN)	900.640	-
		-	-	1,360	-	1,360	LF	SPECIAL PROVISION (STEEL PILING, CONCRETE-FILLED 12¾" O.D. x ⅜" PIPE)	900.640	6
		-	-	1	-	1	LS	SPECIAL PROVISION (INCORPORATING SALVAGED BRIDGE COMPONENTS)	900.645	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET 2

PROJECT NAME: WALLINGFORD
PROJECT NUMBER: STP ST WALK(14)

Drawing Copyright © 2009

CHA

FILE NAME: $FILES$
PROJECT MANAGER: SUSAN SCRIBNER
DESIGNED BY: L. HARDEN
BRIDGE DESIGN SUPERVISOR: P. HALSTEAD

PLOT DATE: 1/9/2009
DRAWN BY: W. WEATHERBY
CHECKED BY: P. HALSTEAD
SHEET 4 OF 26

FILE NAME =u:\8669\mstn\prefinal_submission\x02f136quan.dgn
DATE/TIME =1/9/2009
USER =2352