STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

FENCE

BEGIN STATION	END STATION	CHAIN LINK FENCE, 6 FEET LF	BRACING ASSEMBLY FOR CHAIN LINK FENCE EA	REMARKS
ITEM 620.12 CHAIN-LINK FENCE, 6 FEET				
1+10.0	2+60.0	192		
ROUNDING		3		
TOTAL		195		
ITEM 620.21 BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET				
BRACING ASSEMBLIES SHALL BE INSTALLED AT EACH END AND AT THE CORNER. SEE VAOT STANDARD SHEET F-2.				
SUBTOTAL			4	
ROUNDING			-	
TOTAL			4	

MISCELLANEOUS

STATION	BOLLARDS EA	POSITION LEFT	POSITION RIGHT	REMARKS
ITEM 619.14 BOLLARDS				
0+20	1			
1+46	1			
SUBTOTAL	2			
ROUNDING	-			
TOTAL	2			

GUARDRAIL

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	END TREATMENT BEGIN EA	END TREATMENT END EA
ITEM 621.205 STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POSTS					
0+20.0	0+23.0	27*			
CONNECT TO TERMINAL CONNECTOR AT STA. 0+23.0. 5'-0" RADIUS ON ONE END ONLY AT TERMINAL CONNECTOR. 16'-0" RADIUS ON ONE END ONLY AT END SECTION.					
0+21.0	0+23.0		27*		
CONNECT TO TERMINAL CONNECTOR AT STA. 0+23.0. 5'-0" RADIUS ON ONE END ONLY AT TERMINAL CONNECTOR. 16'-0" RADIUS ON ONE END ONLY AT END SECTION.					
SUBTOTAL (LT & RT)		54			
ROUNDING		-			
TOTAL		54			
ITEM 621.53 TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL					
0+22.5	0+24.5 LT				1
CONNECT TO BRIDGE AT STA. 0+24.5.					
0+23.0	0+25.0 RT				1
CONNECT TO BRIDGE AT STA. 0+25.0.					
SUBTOTAL (BEGIN & END)					2
ROUNDING					-
TOTAL					2
ITEM 621.60 ANCHOR FOR STEEL BEAM RAIL					
0+18.5 LT				1	
0+19.0 RT				1	
SUBTOTAL (BEGIN & END)					2
ROUNDING					-
TOTAL					2

* PAY LENGTH INCLUDES ROUNDED W-BEAM END SECTION(S). SEE STD. G-1D FOR DETAILS.

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CF	TRENCH ROCK CF	GRAN BKFILL CF	FB EA	MKR PST EA

Drawing Copyright © 2009

CHA
11 Winners Circle, PO Box 5269 • Albany, NY 12205-0269
Main: (518) 453-4500 • www.chacompanies.com

PROJECT NAME: **WALLINGFORD**
PROJECT NUMBER: **STP ST WALK(14)**

FILE NAME: **Z02F136ITEMDETAIL.XLS**
PROJECT LEADER: **SUSAN SCRIBNER**
DESIGNED BY: **D. EMERICH**
ITEM DETAIL SHEET

PLOT DATE: **08/07/2008**
DRAWN BY: **D. EMERICH**
CHECKED BY: **P. HALSTEAD**
SHEET **6** OF **26**