

STATE OF VERMONT AGENCY OF TRANSPORTATION																QUANTITY SHEET											
SUMMARY OF ESTIMATED QUANTITIES																TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES					
					PATH ABUT 1	PATH ABUT. 2							FULL E & C	EROSION CONTROL		PATH	RAISED PATH	ROUND	GRAND TOTAL	FINAL	UNIT				ITEMS	ITEM NUMBER	QUANTITIES
																	0.35			0.35		ACRE	THINNING AND TRIMMING (MOD)	201.30			
																	184			184		CY	COMMON EXCAVATION	203.15			
					48	72											120			120		CY	STRUCTURE EXCAVATION	204.25			
					50	61											111			111		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
																	225			225		CY	SUBBASE OF GRAVEL	301.15			
														10						10		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35			
																	2.00			2		TON	AGGREGATE SHOULDERS (MOD)	402.12			
																	25			25		TON	MEDIUM DUTY BIT. CONC. PAVEMENT	406.27			
					9	11											20			20		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34			
																	1			1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10			
																	4160			4160		LF	CAST-IN-PLACE CONCRETE PILING	505.25			
					1346	1250											2110	2596		4706		LB	REINFORCING STEEL	507.15			
																	36			36		EACH	PRESTRESSED CONCRETE MEMBER (MOD) (PILE CAPS) (12')	510.20			
																	148			148		EACH	PRESTRESSED CONCRETE MEMBER (MOD) (3' SLAB)	510.20			
																	1			1		EACH	REMOVAL OF STRUCTURE (MOD) (15+50 LT)	529.15			
																	1			1		EACH	REMOVAL OF STRUCTURE (8+90 RT)(TIMBER WALL)	529.15			
																	592			592		EACH	BEARING DEVICE ASSEMBLY	531.10			
																	1			1		HR	BULLDOZER RENTAL, TYPE I	608.10			
																	3			3		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25			
																	5			5		HR	TRUCK RENTAL	608.37			
																	3			3		HR	LOADER RENTAL, TYPE I	608.40			
																		20		20		CY	STONE FILL, TYPE I	613.10			
														20						20		CY	STONE FILL, TYPE II	613.11			
																	25			25		LF	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28			
																	240			240		SY	PORTLAND CEMENT CONC. SIDEWALK, 5 INCH (MOD)	618.10			
																	1			1		EACH	WOOD MARKER POSTS	619.15			
																	74			74		LF	CHAIN LINK FENCE, 6 FEET (MOD) (TOP POLE INCLUDED)	620.12			
																	4			4		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21			
																	30			30		LF	REMOVING AND RESETTNG FENCE (27+20 TO 27+50 LEFT)	620.50			
																	80			80		LF	REMOVAL OF EXISTING FENCE (MOD) (22+65, 23+85, & 28+25)	620.55			
																		4958		4958		LF	SNOW FENCE	620.70			
													1							1		LS	FIELD OFFICE-ENGINEERS	631.10			
													1							1		LS	TESTING EQUIPMENT - CONCRETE	631.16			
													1							1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
													1							1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
																	1			1		LS	MOBILIZATION	635.10			
																	114			114		LF	4" YELLOW LINE	646.21			
																	6			6		EA	LETTER OR SYMBOL	646.30			
														55						55		SY	GEOTEXTILE UNDER STONE FILL	649.31			
														160						160		SY	GEOTEXTILE FOR SILT FENCE	649.51			
PROJECT NAME: COLCHESTER																											
PROJECT NUMBER: STP BIKE(48)																											
FILE NAME: sf038quant.xls																											
PLOT DATE: 07/30/2003																											
PROJECT LEADER: C. KELLER																											
DRAWN BY: J. GEORGE																											
DESIGNED BY: J. GEORGE																											
CHECKED BY: M.E.M.																											
QUANTITY SHEET #1																											
SHEET 8 OF 87																											
Scan - qty1																											