

STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH DIVISION SUBSURFACE INFORMATION				HOLE NO.: B-201 SHEET 1 OF 2 DATE STARTED: 11/8/02 DATE COMPLETED: 11/8/02						
PROJECT NAME: BURLINGTON-COLCHESTER SITE NAME: BIKE PATH STATION: 12+00.00 GROUND EL.: 99.62				PROJECT NUMBER: STP BIKE (45) SITE NO.: DELTA PARK OFFSET: 0.00 G.W. DEPTH: HOLE CAVED IN						
BORING CREW CREW CHIEF: HOLT DRILLER: YOUNG LOGGER: SOMERS				BORING RIG: TRACK RIG BORING TYPE: WASH BORE SAMPLE TYPE: SPLIT BARREL						
DEPTH	SYMBOL	CLASSIFICATION OF MATERIALS (Description)	BLOWS PER FOOT	M.C. %	GRAVEL %	SAND %	FINES %	LL	PI	
5	OR	A-4, SaSi with Trace of Organics (2.4%), gry, Moist, Rec. = 2.00'	3	42		42.6	57.4			
10		A-3, Sa, gry, Moist, Rec. = 0.65'	6	22	5.7	91.1	3.2			
15		A-1-b, Sa, gry, Moist, Rec. = 0.50'	4	22.5	3.2	95.4	1.4			
20		A-3, Sa, gry, Moist, Rec. = 0.75'	5	26.5	1	96.4	2.6			
25		A-1-b, Sa, gry, Moist, Rec. = 0.90'	7	18.7	10.9	84	5.1			
30		A-3, Sa, gry, Moist, Rec. = 0.85'	6	23.6	3.3	91.1	5.6			
35		A-1-b, Sa, gry, Moist, Rec. = 0.90'	4	20	8.4	87.3	4.3			
40		A-2-4, SiSa with Wood, gry, Moist, Rec. = 1.75'	WH	33.7	8	59.8	32.2			
45		A-4, SiSa, gry, Moist, Rec. = 1.30'	8	28.8	2.5	55.2	42.3			

STATE OF VERMONT AGENCY OF TRANSPORTATION MATERIALS & RESEARCH DIVISION SUBSURFACE INFORMATION				HOLE NO.: B-201 SHEET 2 OF 2 DATE STARTED: 11/8/02 DATE COMPLETED: 11/8/02						
PROJECT NAME: BURLINGTON-COLCHESTER SITE NAME: BIKE PATH STATION: 12+00.00 GROUND EL.: 99.62				PROJECT NUMBER: STP BIKE (45) SITE NO.: DELTA PARK OFFSET: 0.00 G.W. DEPTH: HOLE CAVED IN						
BORING CREW CREW CHIEF: HOLT DRILLER: YOUNG LOGGER: SOMERS				BORING RIG: TRACK RIG BORING TYPE: WASH BORE SAMPLE TYPE: SPLIT BARREL						
DEPTH	SYMBOL	CLASSIFICATION OF MATERIALS (Description)	BLOWS PER FOOT	M.C. %	GRAVEL %	SAND %	FINES %	LL	PI	
	OR	A-4, Si with Trace of Organics (3.4%), gry, Moist, Rec. = 1.80'	6	41.9		9.6	90.4			
55		A-2-4, SiSa, gry, Moist, Rec. = 1.20'	18	19.2	4	70.2	25.8			
60		A-4, SaGrSi, gry, Moist, Rec. = 1.00'	10	15.1	35.7	24.3	40			
65		A-2-4, SiSa, gry, Moist, Rec. = 1.75'	29	19.8	5.6	72.9	21.5			
70		A-2-4, Sa, gry, Moist, Rec. = 1.75'	28	22	2.6	86.5	10.9			
75		A-3, Sa, gry, Moist, Rec. = 0.90'	12	22.7		97.8	2.2			
80		A-4, SaSi, gry, Moist, Rec. = 1.10'	11	28		26.2	73.8			
85		A-4, Si, gry, Moist, Rec. = 1.50'	13	30		14.6	85.4			
90		A-4, Si, gry, Moist, Rec. = 2.00'	9	29.8		10.9	89.1			
Hole stopped @ 92.0'										
95										

SURVEYED BY
DRAWN BY J. TOUCHEITTE
SQUAD LEADER C. C. BENDA
DESIGN FILE NO. /M&R/01f132/mf132bor.dgn
IFARM FILE
DATE
PLOTTED 05-AUG-2003

PROJ. NAME COLCHESTER
PROJ. NO. STP BIKE(48)
SHEET 35 OF 87 SHEETS