STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

FULL C.E. ITEMS	ROADWAY	TOTAL QUANTITY	UNIT	DESCRIPTION	ITEM	ROUNDING
	66	66	CY	COMMON EXCAVATION	203.15	
	1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
	10	10	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	
	500	500	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	
	440	440	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	
	1,580	1,580	SF	DETECTABLE WARNING SURFACE	618.30	
	60	60	LF	CHAIN-LINK FENCE, 4 FEET	620.11	
	2	2	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 4 FEET	620.20	
	60	60	LF	REMOVAL OF EXISTING FENCE	.620.55	
1		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	
	1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
	185,400	185,400	SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	
	2	2	LB	SEED	651.15	
	10	10	LB	FERTILIZER	651.18	
	0.05	0.05	TON	HAY MULCH	651.25	
	150	150	CY	VEHICLE TRACKING PAD	653.35	
	20	20	EA	INLET PROTECTION DEVICE, TYPE II	653.41	
	9	9	SF	TRAFFIC SIGNS, TYPE A	675.20	ESTIMATE
	40	40	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	ESTIMATE
	17,600	17,600	CY	SPECIAL PROVISION (AGGREGATE SURFACE COURSE, SIDEWALK/TRAIL) (FPQ)	900.608 REV.1	
	1	1	LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL INCLUSIVE)	900.645	

REV.1	UPDATED QUANTITY OF SPECIAL PROVISION (AGGREGATE SURFACE COURSE, SIDEWALK/TRAIL) (FPQ)	REVISED BY: J. KAPLAN	REVISED ON: 12/4/2009

PROJECT LEADER: **JON KAPLAN**
CHECKED BY: **SUE SCRIBNER**

PROJECT NAME/NUMBER:
STATEWIDE STP NWRT (1)