



4' HIGH WOVEN WIRE FENCE
 RTE 289 STA 765+50,90' LT - STA 779+00,90' LT
 RTE 289 STA 765+50,100' RT - STA 779+00,100' RT

STA 769+50 LT TO STA 773+00 LT
 NEW 6" x 330' UNDERDRAIN
 W/6" x 20' CARRIER PIPE W/CAP END

STA 775+50 LT TO STA 779+00 LT
 NEW 6" x 350' UNDERDRAIN
 W/CAP END

STA 771+00 C TO STA 774+00 C
 NEW 18" x 300' RCP CLASS III

STA 768+00 C TO STA 771+00 C
 NEW 18" x 300' RCP CLASS III

765+50
 90' LT.

765+50
 100' RT.

REMOVAL OF EXISTING FENCE
 RTE 289 STA 765+50,2' LT TO STA 779+00,7' RT
 RTE 289 STA 770+85,2' RT TO STA 770+85,177' RT
 RTE 289 STA 776+89,4' RT TO STA 776+89,177' RT

STA 774+00 RT TO STA 779+00 RT
 CONSTRUCT 4' WIDE SPECIAL DITCH

STA 777+00 C TO STA 777+00 RT
 NEW 18" x 80' OPTION PIPE W/3' x 8'
 FLOW PAD W/TYPE I STONE FILL

STA 774+00 C TO STA 774+00 RT
 NEW 18" x 78' OPTION PIPE W/3' x 8'
 FLOW PAD W/TYPE I STONE FILL

STA 766+00 RT TO STA 772+50 RT
 NEW 6" x 630' UNDERDRAIN
 W/6" x 20' CARRIER PIPE W/CAP END

DATUM
 VERTICAL _____
 HORIZONTAL _____

R. O. W. PLANS
 SURVEYED BY PINKHAM ENG. DATE 8-87
 DRAWN BY D.R.O. DATE 6-89
 TRACED BY J.B.C./R.S.J. DATE 6-89
VERMONT ROUTE 289 (F.A.P.)
TOWN OF WILLISTON
 PROJ. WILLISTON NO. PB 033-1(1)
 COLCHESTER
 SHEET 14 OF 26