



DRILLING AND BLASTING OF SOLID ROCK SUBGRADE  
 STA 828+25 TO STA 829+75

GUARD RAIL APPROACH SYSTEM, TYPE I  
 NOTE: ALL STATIONS AND OFFSETS ON THIS SHEET ARE REFERENCED TO ROUTE 289 BASELINE UNLESS OTHERWISE NOTED.

STEEL BEAM GUARD RAIL W/ WOOD POSTS  
 RTE 289 STA 822+00, RT TO STA 822+50 RT

CONCRETE MEDIAN BARRIER  
 RTE 289 STA 822+00 TO STA 831+00

NATIVE TREE ESTABLISHMENT  
 RTE 289 STA 822+00, RT TO STA 822+50, RT

END ROW PROJECT  
 PB 033-1(1) SECTION 1B  
 STA. 831+00

BEGIN ROW PROJECT  
 TR 089-2(12)  
 STA. 831+00

REMOVAL OF EXISTING FENCE  
 100' RT.  
 RTE 289 STA 827+00, 2' LT TO STA 831+00 @  
 RTE 289 STA 827+24, 2' LT TO STA 827+52, 101' RT  
 RTE 289 STA 830+89, @ TO STA 830+97, 103' LT

4' HIGH WOVEN WIRE FENCE  
 RTE 289 STA 822+00, 100' LT - STA 824+70, 100' LT  
 RTE 289 STA 825+32, 110' LT - STA 831+00, 110' LT  
 RTE 289 STA 822+20, 280' RT - STA 824+40, 280' RT  
 RTE 289 STA 824+40, 280' RT - STA 824+40, 110' RT  
 RTE 289 STA 824+40, 110' RT - STA 824+80, 80' RT  
 RTE 289 STA 825+45, 80' RT - STA 826+15, 110' RT  
 RTE 289 STA 829+15, 110' RT - STA 827+30, 100' RT  
 RTE 289 STA 827+30, 100' RT - STA 831+00, 100' RT

\* CORNER BRACE SHALL BE INSTALLED AND CONNECTED AT INTERSECTIONS BETWEEN EXISTING FENCE AND R.O.W. FENCE.

R.O.W. PLANS

SURVEYED BY	PINKHAM ENG.	DATE	8-87
DRAWN BY	D.R.O.	DATE	6-89
TRACED BY	J.B.C./C.S.L.	DATE	6-89
VERMONT ROUTE 289 (F.A.P.)			
TOWN OF WILLISTON			
WILLISTON		NO. PB 033-1(1)	
PROJ. COLCHESTER	SHEET 18 OF 26		

DATUM  
 VERTICAL \_\_\_\_\_  
 HORIZONTAL \_\_\_\_\_