



VERMONT ROUTE 289
 CURVE DATA #1
 $\Delta = 23^\circ-23'-45''$ RT
 $D_c = 01^\circ-00'-00''$
 $R = 5,729.58'$
 $T = 1,186.32'$
 $E = 121.53'$
 $L = 2,339.58'$
 BANK = 0.021 FT./FT.

E.B. ON-RAMP
 CURVE DATA #3
 $\Delta = 39^\circ-00'-33''$ RT
 $D_c = 09^\circ-32'-57''$
 $R = 600.00'$
 $T = 212.53'$
 $E = 36.53'$
 $L = 408.50'$
 BANK = 0.076 FT./FT.

4' HIGH WOVEN WIRE FENCE
 RTE 289 STA 445+00, 228' LT - RTE 289 STA 450+00, 75' LT
 RTE 289 STA 450+00, 75' LT - RTE 289 STA 458+00, 75' LT
 RTE 289 STA 445+00, 215' RT - RTE 289 STA 448+42, 123' RT
 RTE 289 STA 448+42, 123' RT - RTE 289 STA 458+00, 158' RT

REMOVAL OF EXISTING FENCE
 RTE 289 STA 451+38, 106' LT - RTE 289 STA 451+61, 100' RT

DATUM	
VERTICAL	N.G.V.D. 1929
HORIZONTAL	N.A.D. 1927



NOTE: REFER TO DRAINAGE PLANS FOR DRAINAGE DETAILS

VERMONT ROUTE 289 (F.A.P.)
 TOWN OF ESSEX
 PROJ. WILLISTON - NO. PB 033-1(1)
 COLCHESTER
 SHEET 34 OF 61