



CURVE DATA #2
 $\Delta = 102^\circ-13'-08''$ RT.
 $D_c = 05^\circ-43'-46''$
 $R = 1000.00'$
 $T = 1239.69'$
 $E = 592.75'$
 $L = 1784.03'$
 $BANK = 0.061$ FT./FT.

CURVE DATA #3
 $\Delta = 33^\circ-10'-52''$ LT.
 $D_c = 05^\circ-43'-46''$
 $R = 1000.00'$
 $T = 297.93'$
 $E = 43.44'$
 $L = 579.12'$
 $BANK = 0.042$ FT./FT.

STEEL BEAM GUARD RAIL
 SUSIE WILSON RD. 43+50 TO 45+87.5 LT.
 43+50 TO 45+87.5 RT.

STEEL BEAM GUARDRAIL WITH ANCHOR FOR STEEL BEAM RAIL
 OLD SUSIE WILSON RD. - NORTH TURNAROUND 225 LF W/ANCHORS

BARTLETT, ALAN H. & WEAVER, THOMAS C. & RUSSELL, JOHN A.
 SUSIE WILSON RD. 45+46 TO 46+12.5 LT.
 45+46 TO 46+12.5 RT.

BAKER, JAMES E. & CORINNE P.

BAKER, JAMES E. III & KATHY K.

ROONEY, SHAYNE R.

PARIKH, GHANSHYAM N. & SUDHA G.

PADE, LUCILLE Y.

NOTE: REFER TO SHEET FOR DETAILS OF TEMPORARY SUSIE WILSON RD. DETOUR.

NOTE: ALL STATIONS AND OFFSETS ON THIS SHEET ARE REFERENCED TO SUSIE WILSON ROAD.

NOTE: REFER TO DRAINAGE PLANS FOR DRAINAGE DETAILS.

SCALE IN FEET

DATUM	
VERTICAL	N.G.V.D. 1929
HORIZONTAL	N.A.D. 1927

SURVEYED BY VS, INC. / CHA. DATE 1988-90
 DRAWN BY W. PETERSON DATE 8/90
 TRACED BY MEDINA/HECHT DATE 1/89
 VERMONT ROUTE 289 (F.A.P.)
 TOWN OF ESSEX
 PROJ. WILLISTON - NO. PB 033-1(1)
 COLCHESTER
 SHEET 45 OF 61

R.O.W. PLAN