SUMSHEET5.DGN

# TRAFFIC SIGN SUMMARY SHEET

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS | EXISTING SIGNS: TO BE SALV. | EXISTING SIGNS: REMOVE | EXISTING SIGNS: RETAIN | NEW AND SALVAGED SIGNS: "A" | NEW AND SALVAGED SIGNS: "B" | NEW AND SALVAGED SIGNS: SALV. SIGN | NEW AND SALVAGED SIGNS: INSTALL UNDER ALTERNATE CONTRACT | EXISTING POSTS: RET. | EXISTING POSTS: DRILL | EXISTING POSTS: REM. | EXISTING POSTS: SALV. | NEW SIGN POSTS: NUMBER OF POSTS | FLANGED CHANNEL LB./FT.: 2.0 | FLANGED CHANNEL LB./FT.: 2.5 | FLANGED CHANNEL LB./FT.: 3.0 | TUBULAR ALUMINUM: 3.0"ø | TUBULAR ALUMINUM: 3.0"□ | TUBULAR ALUMINUM: 4.0"ø | TUBULAR ALUMINUM: 4.0"øM. | TUBULAR STEEL: 3" Ø | TUBULAR STEEL: 3.5" Ø | TUBULAR STEEL: 4.0" Ø | TUBULAR STEEL: 5.0" Ø | W SHAPED STEEL: POST SIZE | W SHAPED STEEL: WEIGHT | ITEM625.41 24" FTG | ITEM625.42 30" FTG | REMARKS | FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER | FOR SIGN DETAIL SHEET: STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| RTE 15 17+20 RT 77-2 | | 21"x 15" | | | | 2.2 | | | | | | | | | | | | | | | | | | | | | | | | | | E-136 |
| RTE 15 17+20 RT 77-3 | WEST | 24"x 12 | | | | 2 | | | | | | | | | | | | | | | | | | | | | | | | | | " |
| RTE 15 18+35 MED 78-1 | | 24"x30" | | | | 5 | | | | | | | | 1 | | 14 | | | | | | | | | | | | | | | | E-142 |
| RTE 15 18+35 MED 78-2 | | 18"x18" | | | | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | E-150 |
| RTE 15 18+95 MED 79-1 | | 24"x30" | | | | 5 | | | | | | | | 1 | | 14 | | | | | | | | | | | | | | | | E-142 |
| RTE 15 18+95 MED 79-2 | | 18"x18" | | | | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | E-150 |
| RTE 15 20+50 RT 80-1 | | 21"x 15" | | | | 2.2 | | | | | | | | 1 | | | 16 | | | | | | | | | | | | | | | E-136 |
| RTE 15 20+50 RT 80-2 | WEST | 24"x 12" | | | | 2 | | | | | | | | | | | | | | | | | | | | | | | | | | " |
| RTE 15 20+50 RT 80-3 | 289 | 30"x 24" | | | | 5 | | | | | | | | | | | | | | | | | | | | | | | | | | " |
| RTE 15 21+30 MED 81-1 | | 24"x30" | | | | 5 | *SEE CONTRACT FEGC-033-1(8) | | | FOR ADDITIONAL SIGNAGE AND PAVEMENT MARKINGS | | | | 1 | | 14 | | | | | | | | | | | | | | | | E-142 |
| RTE 15 21+30 MED 81-2 | | 18"x18" | | | | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | E-150 |
| RTE 15 21+85 MED 82-1 | | 24"x30" | | | | 5 | | | | | | | | 1 | | 14 | | | | | | | | | | | | | | | | E-142 |
| RTE 15 21+85 MED 82-2 | | 18"x18" | | | | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | E-150 |
| RTE 15 RAMP D 0+90 LT 83 | | 18"x18" | | | | 2.25 | | | | | | | | 1 | 12 | | | | | | | | | | | | | | | | | E-150 |
| RTE 15 23+70 84 | | 30" x 30" | | | | 6.25 | | | | | | | | 1 | | | 16 | | | | | | | | | | | | | | | E-151 |
| RTE 15 25+10 RT 85-1 | NORTH | 24"x 12" | | | | 2 | | | | | | | | 1 | | 16 | | | | | | | | | | | | | | | | E-136 |
| RTE 15 25+10 RT 85-2 | 15 | 24"x24" | | | | 4 | | | | | | | | | | | | | | | | | | | | | | | | | | " |
| RTE 15 25+70 LT 86 | | 30" x 30" | | | | 6.25 | | | | | | | | 1 | | | | | | | | | | | | | | | | | | E-151 |
| RTE 15 23+80 MED 87-1 | | 24"x30" | | | | 5 | | | | | | | | 1 | | 14 | | | | | | | | | | | | | | | | E-142 |
| RTE 15 23+80 MED 87-2 | | 18"x18" | | | | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | E-150 |
| FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S 'SIGN POST DESIGN MANUAL'. | | TOTALS | | EA. | | SF. 70.4 | SF. | EA. | EA. | | | | | | 335.0 | | | | | | | | | | | | | | | TRAFFIC SIGN SUMMARY SHEET | | |

PREPARED BY TR DATE 4-91
CHECKED BY _____ DATE ____
DESIGN SUPERVISOR _____ DATE ____
PROJ. PB 033-1(2)
WILLISTON-COLCHESTER
VT RTE 289 (FAP) TOWN OF ESSEX
TRAFFIC SHEET NO. ____ OF ____
SHEET 107 OF 400 SHEETS