



- NOTES:
1. FOR ANCHOR BOLT LOCATIONS, SEE BEARING DEVICE DETAILS ON DWG. BR310. ANCHOR BOLTS SHALL BE SET BEFORE ABUTMENT CONCRETE IS PLACED.
 2. BRIDGE SEAT AREAS SHALL BE SLOPED 1/2"/FT, EXCEPT UNDER BEARING DEVICES WHICH SHALL BE LEVEL. SEE GENERAL NOTES.
 3. FINAL BRIDGE SEAT ELEVATIONS SHALL BE SET ONLY AFTER APPROVAL OF BEARING DEVICE FABRICATION PLANS.
 4. FOR LIMITS OF EXCAVATION AND FILL AT ABUTMENTS, SEE DETAILS ON DWG. BR309.

STATE OF VERMONT AGENCY OF TRANSPORTATION	
TOWN OF ESSEX	Bridge No. 13
HIGHWAY NO. VT. RTE. 289	Log Sta.
VT. RTE. 289 "RAMP D" OVER CVRR	
ABUTMENT 2 - PLAN, ELEVATION & SECTIONS	
Designed by KRH	Drawn by JDH Sr. / M.W.D.
Checked by RJS date 10-12-90	Bridge Design Supervisor MWO date 10-12-90
PROJECT WILLISTON - COLCHESTER	PROJECT NO. PB 033-1(2)
Bridge Sheet No. BR316	Sheet 181 of 400