STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

NON-FEDERAL PARTIC.	EMPLOYEE TRAINEESHIP	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			200	200	m3	EARTH BORROW	203.30	40
			9,100	9,100	M	SHOULDER BERM REMOVAL	203.99	EST
			1	1	m3	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	EST
			257,000	257,000	m2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	405
			28,100	28,100	M	MILLED RUMBLE STRIPS	213.10	EST
			5,350	5,350	T	AGGREGATE SHOULDERS (MOD.)	402.12	45
			31,000	31,000	KG	EMULSIFIED ASPHALT	404.65	EST
			1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	--
			31,200	31,200	T	SUPERPAVE BITUM. CONC. PAVEMENT (PG 64-34)	490.30	176
		50		50	M	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10	1
		3		3	m3	RAPID SETTING CONC. REPAIR MTRL. W/COARSE AGGR.	580.20	EST
			34	34	EA	CHANGING ELEVATION OF D.I., C.B. OR M.H.	604.40	EST
			23	23	EA	REHABILITATION OF D.I., C.B. OR M.H., CLASS I	604.412	EST
			100	100	HR	POWER GRADER RENTAL	608.15	EST
			300	300	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
			90	90	HR	POWER BROOM RENTAL	608.30	EST
			600	600	HR	TRUCK RENTAL	608.37	EST
			25	25	HR	LOADER RENTAL, TYPE I	608.40	EST
			5	5	T	BITUMINOUS CONCRETE CURB, TYPE A	616.30	EST
			100	100	M	TREATED TIMBER CURB	616.35	EST
			150	150	M	REMOVAL OF EXISTING CURB	616.41	EST
			3	3	T	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	0.14
			900	900	M	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	67
			4	4	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	--
			4	4	EA	TRAILING END TERMINAL	621.52	--
			150	150	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	--
			700	700	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	--
			500	500	M	ADJUST HEIGHT OF GUARDRAIL	621.79	EST
			500	500	M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	5
			2,600	2,600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			3,000	3,000	HR	FLAGGERS	630.15	EST
			1	1	LS	FIELD OFFICE - ENGINEER'S	631.10	--
			1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--
			1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	--
	520			520	HR	EMPLOYEE TRAINEESHIP	634.10	--
			1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
			1	1	LS	TRAFFIC CONTROL	641.10	EST
			8	8	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
228,102	m2	MAINLINE - NB TRAVEL LANES AND SHOULDERS
2,331	m2	REST AREA ACCEL/DECEL LANES
5,789	m2	WRJ RAMPA/RAMPC
4,637	m2	WRJ RAMP B
1,626	m2	WRJ RAMP G
4,343	m2	WRJ RAMP H
3,562	m2	QUECHEE RAMP B
4,099	m2	QUECHEE RAMP A
2,106	m2	U-TURNS
405	m2	ROUNDING
257,000	m2	TOTAL
		SUPERPAVE BITUM. CONC. PAVEMENT (PG 64-34)
		TYPE IIIS (WEARING SURFACE)
27,258	T	MAINLINE - NB TRAVEL LANES AND SHOULDERS
279	T	REST AREA ACCEL/DECEL LANES
692	T	WRJ RAMPA/RAMPC
554	T	WRJ RAMP B
194	T	WRJ RAMP G
519	T	WRJ RAMP H
426	T	QUECHEE RAMP B
490	T	QUECHEE RAMP A
252	T	U-TURNS
		TYPE IVS (BRIDGE SURFACE)
360	T	BRIDGES 6-N AND 11-N
176	T	ROUNDING
31,200	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	meters	kilometers	REMARKS

TOTALS

/pave/01a028/p01a028.dgn/p01a028qsl.1

QUANTITY SHEET #1

PROJECT NAME **HARTFORD - SHARON**
PROJECT NUMBER **AC IM 089-1(51)**

DATE PLOTTED: 31-JAN-2006 13

SHEET **5** OF **21** SHEETS