STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
QUECHEE INTERCHANGE																																				
RAMP B 0+539 LT	STOP / DO NOT ENTER	1 1	750 750	750 750	0.56 0.56						1			X		X																		MOUNT STOP SIGN BACK TO BACK WITH DO NOT ENTER SIGN.		E-143 E-143
		1 1	450 450	450 450	0.20 0.20																												MOUNT HAZARD MARKERS BACK TO BACK.		E-150 E-150
REST AREA NB STA. 14+090 RT&LT	WRONG WAY	2	900	600	1.08						4			X		X																		INSTALLED WITH CONSTRUCTION OF REST AREA		E-143
NB STA. 13+647 RT	BEAR CROSSING / NEXT 2 MILES	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
NB STA. 15+337 RT	BEAR CROSSING / NEXT 1 MILE	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
NB STA. 17+140 RT	MOOSE CROSSING / NEXT 3 MILES	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
SOUTHBOUND MM 9.77 RT	BEAR CROSSING / NEXT 1 MILE	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
SOUTHBOUND MM 10.57 RT	BEAR CROSSING / NEXT 2 MILES	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
SOUTHBOUND MM 12.78 RT	MOOSE CROSSING / NEXT 3 MILES	1 1	1200 750	1200 600	1.44 0.45						2			X		X																			9 9	
	SHEET 11 TOTALS SHEET 10 TOTALS ROUNDING				13.94 10.78 1.28									78.2 92.0 4.8		78.2 92.0 4.8																					
												m	m	m 175	m	m 175	m		EA	kg	kg	kg		kg	kg	kg	kg								
	PROJECT TOTALS				m² 26.00	m²	EA.	m²				m 175			m 175					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **HARTFORD – SHARON**
PROJECT NO.: **AC IM 089-1(51)**
DESIGN FILE NAME: /pave/01a028/p01a028.dgn
IPARM FILE NAME: p01a028ts2.1
PLOT DATE: 31-JAN-2006 13
SURVEYED BY: LFW
SURVEY DATE: 05-04
SQUAD LEADER: _____
DRAWN BY: LFW
SHEET: 11 OF 21