

LOCATION			DRAINAGE				GUARDRAIL							MISC		REMARKS						
MM	MM	POS.	604.40	604.412	604.415	604.418	621.20	621.205		621.50	621.60	621.70	621.71	621.80	676.10 DEL IN. W/STEEL POST				616.305	601.0005		
			CHANGING ELEVATION OF DI, CB, OR MH	REHAB. DI, CB, OR MH CLASS I	REHAB. DI, CB, OR MH CLASS II	REHAB. DI, CB, OR MH CLASS III	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8 FT POSTS		MTS, FLARED	ANCHOR FOR STEEL BEAM RAIL	GUARDRAIL APPROACH SECTION, GALV. TYPE I	GUARDRAIL APPROACH SECTION, GALV. TYPE II	REMOVAL & DISPOSAL OF GUARDRAIL						TYPE I MILE POSTS	BITUMINOUS CONCRETE CURB, TYPE A	12" CSP .064 (2-2/3 x 1/2)
SPRINGFIELD			(EA)	(EA)	(EA)	(EA)	(LF)	(LF)		(EA)	(EA)	(EA)	(LF)	(LF)		(EA)	(LF)	(LF)	(LF)	(LF)	(LF)	
37.270	37.406	RT												718.0								
37.277	37.405	RT					677.0								2						MTS @ 37.270, ANCHOR @ 37.405	
37.563	37.584	RT												112.5							REMOVE BURIED CABLE TERMINAL (BCT) AND DAMAGED GUARDRAIL	
37.570	37.584	RT					75.0								1						MTS @ 37.563	
37.584	37.780	RT																			RETAIN EXISTING GUARDRAIL	
37.780	37.787	RT					37.5							37.5	1			40.0			ANCHOR @ 37.787, CURB 37.780 - 37.787	
37.898	38.120	RT												1173.0								
37.905	38.120	RT					1139.5								2						MTS @ 37.898, ANCHOR @ 38.120	
37.918	38.110	RT																1014.0				
38.303	38.978	RT												3564.0								
38.310	38.978	RT					3257.0								2						MTS @ 38.303, ANCHOR @ 38.978	
38.500	38.947	RT																2360.0				
39.330	39.540	RT												1109.0								
39.337	39.548	RT					1114.5								2						MTS @ 39.330, ANCHOR @ 39.548	
39.433	39.540	RT																565.0		30		
39.629	40.081	LT												2387.0								
39.636	40.081	LT					2352.0								2						MTS @ 39.629, ANCHOR @ 40.081	
40.220	40.230	LT												50.0							REMOVE BURIED CABLE TERMINAL (BCT)	
40.227	40.230	LT					12.5								1						MTS @ 40.220	
40.230	40.386	LT																			RETAIN EXISTING GUARDRAIL	
40.386	40.393	LT					39.5							37.5	1						ANCHOR @ 40.393, REMOVE TWIST DOWN TERMINAL	
40.256	40.426	RT												897.0								
40.263	40.427	RT					862.5								2						MTS FLARED @ 40.256, ANCHOR @ 40.427	
40.299	40.427	RT																674.0				
40.495	40.502	RT												37.5	1						REMOVE BURIED CABLE TERMINAL (BCT)	
40.502	40.593	RT																			RETAIN EXISTING GUARDRAIL	
40.593	40.600	RT					39.5							37.5	1			38.0			ANCHOR @ 40.600, REMOVE TWIST DOWN TERMINAL, CURB 40.593 - 40.600	
40.689	40.814	NB LT												660.0								
40.695	40.901	NB LT					462.5								1						MTS @ 40.688	
40.891	40.911	NB LT												129.0							REMOVE BULLNOSE - SEE SHEET 39	
40.901	40.911	NB LT																				
40.911	40.983	NB LT																			RETAIN EXISTING GUARDRAIL, INCLUDES BRIDGE 25N	
40.909		NB/SB					40.0														MEDIAN "DROP DEAD" RAIL	
40.983		NB/SB					40.0														MEDIAN "DROP DEAD" RAIL	
40.983	41.007	NB LT												122.5							REMOVE BULLNOSE - SEE SHEET 39	
40.983	40.988	NB LT					27.0								1						ANCHOR @ 40.988	
40.902	40.990	LT&RT																			BRIDGE 25N, TO REPLACE DAMAGED PANELS ON APPROACH RAIL	
40.840	40.896	NB RT					300.0								1			140.0	30		MTS @ 40.832, ATTACH TO EXISTING GUARDRAIL @ 40.896, CURB 40.870 - 40.896	
40.841	40.896	NB RT												293.0								
40.896	41.300	NB RT																			RETAIN EXISTING GUARDRAIL, INCLUDES BRIDGES 25N & 26N	
40.891	40.908	SB												79.0							REMOVE BULLNOSE - SEE SHEET 39	
40.904	40.908	SB					27.0								1						ANCHOR @ 40.904	
40.908	40.981	SB																			RETAIN EXISTING GUARDRAIL, INCLUDES BRIDGE 25N	
40.981	41.007	SB												173.0							REMOVE BULLNOSE - SEE SHEET 39	
40.981	40.991	SB																				
40.991	41.059	SB					362.5								1						MTS @ 41.066	
SUBTOTAL			0	0	0	0	10865.5	0		12	11	2	0	11617.0		23	0	0	0	4831.0	60.0	

**ITEM
DETAIL
SHEET 2**

PROJECT NAME: WESTMINSTER-SPRINGFIELD
PROJECT NUMBER: IM 091-1(62)
FILE NAME: /pave/01a014/pa014 PLOT DATE: 17-JAN-2013 12:43
PROJECT LEADER: PTS DRAWN BY: MRS
DESIGNED BY: NULL CHECKED BY: NULL/PTS
IPARM FILE NAME: 01a014_I5 SHEET 15 OF 43