LOCATION			DRAINAGE				GUARDRAIL														MISC		REMARKS
			604.40	604.412	604.415	604.418	621.20	621.205		621.50	621.60	621.70	621.71	621.80	676.10 DELIN. W/STEEL POST						616.305	601.0005	
MM	MM	POS.	CHANGING ELEVATION OF DI, CB, OR MH	REHAB. DI, CB, OR MH CLASS I	REHAB. DI, CB, OR MH CLASS II	REHAB. DI, CB, OR MH CLASS III	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8 FT POSTS		MTS, FLARED	ANCHOR FOR STEEL BEAM RAIL	GUARDRAIL APPROACH SECTION, GALV. TYPE I	GUARDRAIL APPROACH SECTION, GALV. TYPE II	REMOVAL & DISPOSAL OF GUARDRAIL		TYPE I	TYPE II	TYPE III	TYPE I MILE POSTS	BITUMINOUS CONCRETE CURB, TYPE A	12" CSP .064 (2-2/3 x 1/2)	
XX			(EA)	(EA)	(EA)	(EA)	(LF)	(LF)		(EA)	(EA)	(EA)	(LF)	(LF)		(EA)	(LF)	(LF)	(LF)	(LF)	(LF)	
42.715	42.727	RT												62.5									REMOVE BURIED CABLE TERMINAL (BCT) AND DAMAGED GUARDRAIL
42.722	42.727	RT					25.0			1						1							MTS @ 42.715
42.727	42.761	RT																					RETAIN EXISTING GUARDRAIL
42.761	42.768	RT					39.5				1			37.5		1							ANCHOR @ 42.768, REMOVE TWIST DOWN TERMINAL
42.715	42.724	LT												50.0									REMOVE BURIED CABLE TERMINAL (BCT) AND DAMAGED GUARDRAIL
42.722	42.724	LT					12.5			1						1							MTS @ 42.715
42.724	42.761	LT																					RETAIN EXISTING GUARDRAIL
42.761	42.768	LT					39.5				1			37.5		1							ANCHOR @ 42.768, REMOVE TWIST DOWN TERMINAL
42.848	42.860	RT												62.5									REMOVE BURIED CABLE TERMINAL (BCT) AND DAMAGED GUARDRAIL
42.855	42.860	RT					25.0			1						1							MTS @ 42.848
42.860	43.093	RT																					RETAIN EXISTING GUARDRAIL
43.093	43.100	RT					39.5				1			37.5		1							ANCHOR @ 43.100, REMOVE TWIST DOWN TERMINAL
42.942	42.949	LT								1				37.5		1							REMOVE BURIED CABLE TERMINAL (BCT)
42.949	43.000	LT																					RETAIN EXISTING GUARDRAIL
43.000	43.007	LT					39.5				1			37.5		1					26.0		ANCHOR @ 43.007, REMOVE TWIST DOWN TERMINAL, CURB 43.002 - 43.007
43.272	43.279	RT								1				37.5		1							REMOVE BURIED CABLE TERMINAL (BCT)
43.279	43.369	RT																					RETAIN EXISTING GUARDRAIL
43.369	43.376	RT					39.5				1			37.5		1							ANCHOR @ 43.376, REMOVE TWIST DOWN TERMINAL
43.606	43.613	LT								1				37.5		1							REMOVE BURIED CABLE TERMINAL (BCT)
43.613	44.042	LT																					RETAIN EXISTING GUARDRAIL
44.042	44.049	LT					39.5				1			37.5		1							ANCHOR @ 44.049, REMOVE TWIST DOWN TERMINAL
44.035	44.057	RT												116.0									
44.040	44.057	RT					87.5			1	1					2							MTS @ 44.033, ANCHOR @ 44.057
																							REMOVE BURIED CABLE TERMINAL (BCT) & TWIST DOWN TERMINAL
44.508	44.515	RT								1				37.5		1							REMOVE BURIED CABLE TERMINAL (BCT)
44.515	44.701	RT																					RETAIN EXISTING GUARDRAIL
44.701	44.708	RT					39.5				1			37.5		1							ANCHOR @ 44.708, REMOVE TWIST DOWN TERMINAL
44.650	44.657	LT								1				37.5		1							REMOVE BURIED CABLE TERMINAL (BCT)
44.657	45.034	LT																					RETAIN EXISTING GUARDRAIL
SUBTOTAL			0	0	0	0	426.5	0		9	8	0	0	741.0		17	0	0	0	26.0	0		

ITEM DETAIL SHEET 4

PROJECT NAME: WESTMINSTER-SPRINGFIELD

PROJECT NUMBER: IM 091-1(62)

FILE NAME: /pave/01a014/pa014
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: 01a014_17

PLOT DATE: 17-JAN-2013 12:43
DRAWN BY: MRS
CHECKED BY: NLL/PTS
SHEET 17 OF 43