



**EXIT 7 - RAMP D
NORTHBOUND ON RAMP**

SEE STANDARDS E-191, E-192 AND E-193
FOR PAVEMENT MARKING GUIDELINES

- (A) 0.151 LT
- 0.162 LT
- 0.173 LT
- 0.184 LT
- 0.207 LT
- 0.218 LT
- 0.230 LT

- 646.622 TEMPORARY 6" WHITE LINE, PAINT
- 646.426 DURABLE 6" WHITE LINE, RECESSED POLYUREA
- 0.110 TO 0.235 SOLID RT
- 646.632 TEMPORARY 6" YELLOW LINE, PAINT
- 646.436 DURABLE 6" YELLOW LINE, RECESSED POLYUREA
- 0.110 TO 0.235 SOLID LT
- 646.692 TEMPORARY LETTER OR SYMBOL, PAINT
- 646.492 DURABLE LETTER OR SYMBOL, THERMOPLASTIC
- 0.133 LT - "YIELD"
- 0.141 LT - "AHEAD"
- 203.40 SHOULDER BERM REMOVAL
- 0.167 TO 0.235 LT

- 616.41 REMOVAL OF EXISTING CURB
- 0.110 TO 0.235 RT
- 675.50 REMOVING SIGNS
- AS SHOWN - 1
- NOTE:
- REFER TO STANDARDS E-197, E-198
- AND E-199 FOR PLACEMENT
- GUIDELINES FOR TYPE I, TYPE II
- AND TYPE III DELINEATORS.

LEGEND

R	=	REMOVE EXISTING
S	=	SALVAGE
R&S	=	REMOVE AND SALVAGE
N	=	NEW
RET	=	RETAIN
B-B	=	BACK TO BACK
---	=	EXISTING GUARDRAIL
- - -	=	PROPOSED GUARDRAIL
○	=	TYPE I DELINEATOR, WHITE
●	=	TYPE I DELINEATOR, AMBER
⊙	=	TYPE II DELINEATOR, WHITE
⊙	=	TYPE III DELINEATOR, RIGHT
⊙	=	TYPE III DELINEATOR, LEFT

EXIT 7 NB ON RAMP DETAIL SHEET 2

PROJECT NAME: WESTMINSTER-SPRINGFIELD	FILE NAME: /pave/01a014/pa014	PLOT DATE: 17-JAN-2013 12:44
PROJECT NUMBER: IM 091-1(62)	PROJECT LEADER: PTS	DRAWN BY: MRS
	DESIGNED BY: NULL	CHECKED BY: PTS
	IPARM FILE NAME: 01a014_27	SHEET 27 OF 43

NOT TO SCALE