STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #6

SHS = FHWA STANDARD HIGHWAY SIGNS BOOK

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
0.317 RT	WRONG WAY	1	36	24	6.00						1		X		X																R5-1A		SHS
0.317 LT	WRONG WAY	1	36	24	6.00						1		X		X																R5-1A		SHS
0.360 RT	ONE WAY	1	36	12	3.00						2		X		X																R6-1L		SHS
EXIT 7 RAMP G NB OFF RAMP																																	
0.293 RT	WRONG WAY	1	36	24	6.00						1		X		X																R5-1A		SHS
0.293 LT	WRONG WAY	1	36	24	6.00						1		X		X																R5-1A		SHS
SUBTOTAL SHEET 32 SUBTOTAL SHEET 33 SUBTOTAL SHEET 34 SUBTOTAL SHEET 35					91.25 54.50 58.74 80.05		0 20 1 1				15.0 0.0 0.0 0.0		315.0 135.0 135.0 225.0								4	406.6											
SUBTOTAL SHEET 36 SUBTOTAL SHEET 37					11.25 27.00		22 0				15.0 0.0		60.0 90.0								4	396.8											
ROUNDING					7.21		0.0						10.0									1.6											
												FT 30.0	FT 970.0	FT		EA	LB	LB	LB		LB 805.0	LB	LB	LB									
PROJECT TOTALS		SF 330.0	SF	EA. 44	EA.							FT 1000.0					LB			EA. 8	LB 805.0				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #6

PROJECT NAME: WESTMINSTER-SPRINGFIELD
PROJECT NUMBER: IM 091-1(62)

FILE NAME: $FILEABBREV$
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: 01a014_37

PLOT DATE: 17-JAN-2013 12:44
DRAWN BY: JBZ
CHECKED BY: PTS
SHEET 37 OF 43