



No Exception Taken
 Make Correction (arrow)
 Submit Specified Item
 Revise and Resubmit as Noted
 Reject

Checking is for general compliance with the design concept of the project and general compliance with the specifications in the contract documents only. Any action shown is not an approval or approval to the requirements of the plans and specifications. Any action shown on the plans shall not indicate the checking of an assembly of which the item is a component. Contractor is solely responsible for dimensions which shall be confirmed and correlated at the job site, fabrication processes, techniques of construction, safety precautions, and coordination of his work with that of all other trades and the satisfactory performance of his work.

Reviewed By: *[Signature]* Date: 01/16/11

WY-LIN INTERNATIONAL

ALL FOR
 DIMENSIONS

Abutment 1

ROUGHENED CONSTRUCTION JOINT

PROPOSED GRADE
 (SEE NOTE 1)

*SEE SUPERSTRUCTURE
 PLAN & DETAILS SHEET
 FOR APPROACH SLAB,
 BACKWALL AND DECK
 REINFORCEMENT

Composite drainage
 panel, J-Drain 400

8" Terraflex compressible inclusion

8" GEOTEXTILE WITH 4" DRAINAGE PANEL

ASPHALTIC PLUG JOINT

DECK

INTEGRAL BACKWALL

SEE 'ZB-100-BR6-416' FOR
 BACKFILL TYPE AND LIMITS
 NOT SHOWN HERE

GEOFOAM FILL
 EPS 29

Stone w/
 perforated drain
 pipe
 BUTYL RUBBER SHEET
 (1/8" THICK)
 BOND SHEET WITH
 ADHESIVE TO THIS
 SURFACE ONLY

drain to weep holes in
 face of stemwall or
 wingwalls

BENCH

2 3/4" AVG. (4 1/2" MAX., 1" MIN.)
 SOUTH ABUTMENT

