



DECK POUR SEQUENCE NOTES:

- THE DECK SHALL BE CAST USING ONE OF THE FOLLOWING ALTERNATES.
- ALTERNATE 1: SEQUENTIAL POUR**
- POURS LABELED WITH A (1) SHALL BE PLACED SIMULTANEOUSLY.
 - A 72 HOUR DELAY BETWEEN THE COMPLETION OF POUR 1 AND THE BEGINNING OF POUR 2 SHALL BE OBSERVED.
 - THE POURING SEQUENCE AND ANTICIPATED DURATION SHALL BE SUBMITTED TO THE ENGINEER WITH THE PROPOSED MIX DESIGN FOR APPROVAL.
- ALTERNATE 2: SINGLE POUR**
- CASTING SHALL BEGIN AT ABUTMENT 2 AND PROGRESS TOWARD ABUTMENT 1.
 - WEATHER AND TEMPERATURE LIMITATIONS NOTED IN STANDARD SPECIFICATION SECTION 501.07 APPLY.
 - THE POURING SEQUENCE AND ANTICIPATED DURATION SHALL BE SUBMITTED TO THE ENGINEER WITH THE PROPOSED MIX DESIGN FOR APPROVAL.

BRIDGE 6S SUPERSTRUCTURE PLAN 1 OF 3
SCALE: 1/8" = 1'-0"

NOTES:

- SEE "ZB-100-BR6-417" FOR BARRIER REINFORCEMENT THAT IS CAST WITH THE DECK.
- SEE "ZB-100-BR6-418" FOR END DIAPHRAGM (BACKWALL) REINFORCEMENT.
- BARRIER LENGTHS AND ASSOCIATED REINFORCEMENT FOR BARRIERS ATTACHED TO THE APPROACH SLAB ARE BASED ON A 2 1/8" JOINT. SEE "ZB-100-BR6-419" FOR EXPANSION JOINT DETAILS.
- TRANSVERSE DECK BARS LOCATED AT THE ENDS OF DECK AND ADJACENT TO CONSTRUCTION JOINTS SHALL BE SKEWED TO MATCH THE ORIENTATION OF THE ADJACENT JOINT.
- SEE THE GENERAL NOTES SHEET, 'ZB-100-BR6-102,' FOR ADDITIONAL NOTES.

RFC PLANS - WORK PACKAGES #5&9
BRIDGE 6N & 6S
SEPTEMBER 30, 2011

**AS BUILT
RECORD PLANS**

BECK & BELLUCCI, INC. **TYLIN INTERNATIONAL**

PROJECT NAME: BRATTLEBORO	FILE NAME: ZB-100-BR6-463.dgn	PLOT DATE: 9/30/2011
PROJECT NUMBER: IM 091-(K50)	PROJECT LEADER: Brian W. Clogston P.E.	DRAWN BY: W. D. Roberts
	DESIGNED BY: Joseph Krajewski P.E.	CHECKED BY: R. L. Bollinger
	SUPERSTRUCTURE PLAN 1 OF 3	SHEET ZB-100-BR6-463