COMPOSITE QUANTITY SHEET #1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

GUILFORD-BRATTLEBORO AC IM 091-1(51)				GUILFORD-BRATTLEBORO AC IM 091-1(54)			QUANTITIES			ITEM
FULL C.E.	BRIDGE	ROADWAY	TRAINEESHIP	FULL C.E.	BRIDGE	ROADWAY	GRAND TOTAL	UNIT	ITEMS	NO.
		1				0	1	EA	THINNING AND TRIMMING (FOR SIGNS)	201.31
		345				720	1065	CY	COMMON EXCAVATION	203.15
		970				655	1625	CY	EARTH BORROW	203.30
		26000				20080	46080	LF	SHOULDER BERM REMOVAL	203.99
		0.5				0.5	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I)	204.20
		288370				295520	583890	SY	COLD PLANING-BIT.PAVEMENT	210.10
		105360				96800	202160	LF	MILLED RUMBLE STRIPS	213.10
		5040				5730	10770	TON	AGGREGATE SHOULDERS (MOD.)	402.12
		640				670	1310	CWT	EMULSIFIED ASPHALT	404.65
		0.5				0.5	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50
		36590				34910	71500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30
	930				1050		1980	LF	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10
	100				100		200	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/COARSE AGGREGATE	580.20
		6				7	13	EACH	CHANGING ELEV. OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40
		10				21	31	EACH	REHABING DI,CB OR MH CLASS I	604.412
		2				2	4	EACH	REHABING DI,CB OR MH CLASS II	604.415
		2				2	4	EACH	REHABING DI,CB OR MH CLASS III	604.418
		410				475	885	HR	POWER GRADER RENTAL	608.15
		50				50	100	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25
		330				340	670	HR	POWER BROOM RENTAL,TYPE II	608.31
		50				50	100	HR	TRUCK RENTAL	608.37
		275				0	275	LF	REMOVING AND RESETTING CURB	616.40
		0				300	300	LF	REMOVAL OF EXISTING CURB	616.41
		10				3	13	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47
	400				400		800	LF	SNOW BARRIER - GALVANIZED	620.75
		4660				6200	10860	LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20
		1310				2285	3595	LF	STEEL BEAM GUARD RAIL (GALVANIZED)(MOD. - 8' POSTS)	621.20
		0				280	280	LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21
		12				8	20	EACH	MANUFACTURED TERMINAL SECTION (FLARED)	621.505
		25				17	42	EACH	TRAILING END TERMINAL	621.52
		0				1	1	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60
		230				185	415	EACH	REPLACE GUARD RAIL POST ASSEMBLY	621.76
		340				275	615	EACH	REPLACE GUARD RAIL BEAM UNIT	621.77
		3990				8970	12960	LF	REMOVL AND DISP OF GUARD RAIL	621.80
		3050				2910	5960	HR	UNIFORMED TRAFFIC OFFICERS	630.10
		3050				2910	5960	HR	FLAGGERS	630.15
0.5				0.5			1	LS	FIELD OFFICE-ENGINEERS	631.10
0.5				0.5			1	LS	TESTING EQUIPMENT - CONCRETE	631.16

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

NOTE: REFER TO SHEETS 14 AND 15 AND SHEETS 40 AND 41 FOR DETAILED SUMMARIES OF QUANTITIES.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	-			
TOTALS									

22-JAN-2009 13:37
05A014cqs1.i

PROJECT NAME GUILFORD - BRATTLEBORO
PROJECT NUMBER AC IM 091-1(51) / AC IM 091-1(54)