STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	~~W-SHAPE STEEL REMOVALS~~ FTG. SIZE 24"	FTG. SIZE 30"	~~EACH WEIGHT~~	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
EXIT 1 RAMP E OFF RAMP 2+58 RT	WRONG WAY	1	36	24	6.00						2			X 28		X														1					E-143
EXIT 1 RAMP E OFF RAMP 7+32 LT		1	36	36	9.00						2			X 31		X																			E-150
EXIT 1 RAMP H ON RAMP 1+00 LT		1	18	18	2.25						1		X 9		X															1					E-150
EXIT 1 RAMP H ON RAMP 2+78 RT	36" x 36" x 36"	1			3.90						1			X 15		X														1					E-146
EXIT 1 RAMP H ON RAMP 2+78 LT	36" x 36" x 36"	1			3.90						1			X 15		X														1					E-146
EXIT 1 RAMP H ON RAMP 3+84 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 33		X														1					E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						1			X 14		X														1					E-143
EXIT 2 RAMP A/B OFF RAMP 0+17 LT	STOP / DEAD END	1 1	30 30	30 30	6.25 6.25						1			X 14		X														4				BACK TO BACK	E-143 E-143
	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00																												BACK TO BACK	E-142 E-142
EXIT 2 RAMP NB 1+82 L/R	WRONG WAY																													2				
EXIT 2 RAMP A/B RAMPS 0+19 CL		1 1	24 30	30 30	5.00 6.25						1			X 13		X														3				BACK TO BACK, RETAIN EXISTING SLEEVE	E-144 E-143
		1 1	18 18	18 18	2.25 2.25																												BACK TO BACK	E-150 E-150
EXIT 2 RAMP NB 2+88 ℄	WRONG WAY																													1				
												FT	FT 9	FT 163	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
													15	165	15	165																			
TOTALS		SF 83.55	SF	EA.	SF							FT 172		180	FT		180		LB	EA.	LB			EA.	EA.	LB 18								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: AC IM 091-1(51)

FILE NAME: 03A020tsS02.1
PROJECT LEADER: CRB
DESIGNED BY: CLD
CLD REF. NO. 04-0398

PLOT DATE: 22-JAN-2009 13:3
DRAWN BY: JCS
CHECKED BY: NLL
SHEET 32 OF 69