STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL REMOVALS FTG. SIZE 24"	30"	EACH WEIGHT	POST SIZE	SIGN FRAMES REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
EXIT 2 RAMP A/B OFF RAMP 2+88 LT	WRONG WAY	1	36	24	6.00																										1			MOUNT TO BACK OF DESTINATION BOARDS		E-143
EXIT 2 RAMP A/B ON RAMP 2+88 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 32		X													2						E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00																														E-142
EXIT 2 RAMP A/B RAMPS 3+36 CL		1	24	30	5.00						1			X 13		X														2			RETAIN EXISTING SLEEVE		E-144
		1 1	18 18	18 18	2.25 2.25																													BACK TO BACK		E-150 E-150
EXIT 2 RAMP A/B OFF RAMP 6+24 LT		1	36	36	9.00						2			X 29		X														1					E-150
EXIT 2 RAMP C OFF 0 +71 LT.	SEE SB SHEET 68 FOR SIGNS																						2	36.10'											
EXIT 2 RAMP A/B RAMPS 13+15 CL		1	24	30	5.00						1			X 13		X														2			RETAIN EXISTING SLEEVE		E-144
		1 1	18 18	18 18	2.25 2.25																													BACK TO BACK		E-150 E-150
EXIT 2 RAMP A/B OFF RAMP 13+40 LT	WRONG WAY	1	30	30	6.25		1				2			X 29		X														1			BACK TO BACK		E-151
EXIT 2 RAMP A ON RAMP 12+25 RT		1	30	30	6.25						1			X 14		X														1					E-143
EXIT 3 RAMP D ON RAMP 1+50 LT		1	18	18	2.25						1		X 9		X																				E-150
EXIT 3 RAMP D ON RAMP 6+25 RT		1	30	30	6.25						1			X 15		X														1					E-143
EXIT 3 RAMP C OFF 14+00 RT	SEE SB SHEET 68 FOR SIGNS						17																2	36.80'											
	SUBTOTAL SHEET 1				180.50	58.50						19.5	180	375	180	375							2			311.26									
	SUBTOTAL SHEET 2				83.55							9	15	165	15	165														14					
	SUBTOTAL SHEET 3				73.00		1 X 15					18	15	150	15	150																			
EXIT 3 RAMP C OFF 6+25 RT														366 163 145																1			36.8		
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB			35					
													146.5 210	674.0 690	210	690							554.0'		299.7 311.26				18 26					
	TOTALS	SF 337.05	SF 58.50	EA. 19 X 1	SF							FT 820.5 900			FT 900					LB			EA. 6 X 2		LB 853.7 311.26				EA.	EA.	LB EA 79					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: AC IM 091-1(51)

FILE NAME: 03A020+s03.1
PROJECT LEADER: CRB
DESIGNED BY: CLD
CLD REF. NO. 04-0398

PLOT DATE: 22-JAN-2009 13:3
DRAWN BY: JCS
CHECKED BY: NLL
SHEET 33 OF 69