# QUANTITY SHEET #2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

| FULL C.E. | BRIDGE | ROADWAY | QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | RND. |
|---|---|---|---|---|---|---|---|
| | | 0.5 | 0.5 | LS | MOBILIZATION / DEMOBILIZATION | 635.11 | - |
| | | 0.5 | 0.5 | LS | TRAFFIC CONTROL | 641.10 | - |
| | | 4 | 4 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | 641.15 | - |
| | | 9251O | 9251O | LF | DURABLE 6" WHITE LINE (MOD.-RETROREFLECTIVITY/INLAID) | 646.414 | 916 |
| | | 75270 | 75270 | LF | DURABLE 6" YELLOW LINE (MOD.-RETROREFLECTIVITY/INLAID) | 646.415 | 747 |
| | | 1920 | 1920 | LF | DURABLE 12" WHITE LINE (MOD.-RETROREFLECTIVITY/INLAID) | 646.44 | 21 |
| | | 55 | 55 | LF | DURABLE 24" STOP BAR (THERMOPLASTIC) | 646.46 | 4 |
| | | 67 | 67 | EACH | DURABLE LETTER OR SYMBOL (THERMOPLASTIC) | 646.50 | - |
| | | 9251O | 9251O | LF | TEMPORARY 6" WHITE LINE (PAINT) | 646.614 | 916 |
| | | 75270 | 75270 | LF | TEMPORARY 6" YELLOW LINE (PAINT) | 646.615 | 747 |
| | | 1920 | 1920 | LF | TEMPORARY 12" WHITE LINE (PAINT) | 646.64 | 21 |
| | | 55 | 55 | LF | TEMPORARY 24" STOP BAR (PAINT) | 646.66 | 4 |
| | | 67 | 67 | EACH | TEMPORARY LETTERS OR SYMBOLS (PAINT) | 646.70 | - |
| | | 5640 | 5640 | EACH | LINE STRIPING TARGETS | 646.76 | 56 |
| | | 275 | 275 | LF | PAINTED CURB | 646.81 | 5 |
| | | 35 | 35 | LB | SEED | 651.15 | EST. |
| | | 255 | 255 | LB | FERTILIZER | 651.18 | EST. |
| | | 1 | 1 | TON | AGRICULTURAL LIMESTONE | 651.20 | EST. |
| | | 1 | 1 | TON | HAY MULCH | 651.25 | EST. |
| | | 25 | 25 | CY | TOPSOIL | 651.35 | EST. |
| | | 408 | 408 | SF | TRAFFIC SIGNS, TYPE A | 675.20 | 4.77 |
| | | | | | BEGIN OPTION AA | | |
| | | 1045 | 1045 | LF | FLANGED CHANNEL SIGN POST | 675.301 | 10 |
| | | 1045 | 1045 | LF | SQUARE TUBE SIGN POSTS AND ANCHOR | 675.341 | 10 |
| | | | | | END OPTION AA | | |
| | | 77 | 77 | EACH | REMOVING SIGNS | 675.50 | - |
| | | 2 | 2 | EACH | ERECTING SALVAGED SIGNS | 675.60 | - |
| | | 675 | 675 | EACH | DELINEATORS W/STEEL POSTS | 676.10 | 22 |
| | | 675 | 675 | EACH | REMOVAL OF EXIST DELINEATORS | 676.12 | EST |
| | | 0.5 | 0.5 | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | - |

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

| STATIONS | | PAVEMENT WIDTHS | | | EQUATIONS | | FEET | MILES | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| FROM | TO | | | | + | - | | | |
| | | | | | | | | | |
| TOTALS | | | | | | | | | |

22-JAN-2009 13:40
05A014qty2.i

PROJECT NAME GUILFORD - BRATTLEBORO
PROJECT NUMBER AC IM 091-1(54)