



**EXIT 3 - RAMP A/B
SOUTHBOUND ONOFF RAMP**

SEE STANDARDS E-191, E-192 AND E-193
FOR PAVEMENT MARKING GUIDELINES

TEMPORARY AND DURABLE 6" WHITE LINE
 ON RAMP 0+00 TO 2+50 SOLID RT (RAMP A)
 OFF RAMP 0+00 TO 5+50 SOLID RT (RAMP A/B)
 ON RAMP 0+00 TO 5+50 SOLID LT (RAMP A/B)
 OFF RAMP 5+00 TO 7+20 SOLID RT (RAMP B)

TEMPORARY AND DURABLE 6" YELLOW LINE
 ON RAMP 0+00 TO 2+50 SOLID LT (RAMP A)
 OFF RAMP 0+00 TO 5+50 SOLID RT (RAMP A/B)
 ON RAMP 0+00 TO 5+50 SOLID LT (RAMP A/B)
 OFF RAMP 5+00 TO 7+20 SOLID LT (RAMP B)

REHABING DI, CB OR MH
 OFF RAMP 0+21 RT (RAMP A/B) CLASS I
 ON RAMP 0+50 RT (RAMP A) CLASS I
 ON RAMP 2+15 RT (RAMP A) CLASS I
 OFF RAMP 3+00 RT (RAMP A/B) CLASS I
 ON RAMP 3+11 LT (RAMP A/B) CLASS I
 ON RAMP 4+54 LT (RAMP A/B) CLASS I
 OFF RAMP 4+57 RT (RAMP A/B) CLASS I

DELINEATORS
 REFER TO STANDARDS E-197, E-198
 AND E-199 FOR PLACEMENT GUIDELINES

LEGEND

R	=	REMOVE EXISTING
S	=	SALVAGE
R & S	=	REMOVE AND SALVAGE
N	=	NEW
RET	=	RETAIN
B-B	=	BACK TO BACK
—	=	NEW RAIL
—	=	EXISTING RAIL

NOT TO SCALE

DATUM

VERTICAL	_____
HORIZONTAL	_____

**RAMP
DETAIL #15**

PROJECT NAME:	GUILFORD-BRATTLEBORO	PLOT DATE:	22-JAN-2009 13:41
PROJECT NUMBER:	AC IM 091-I(54)	DRAWN BY:	MRS
FILE NAME:	05A014r.d15.1	CHECKED BY:	NLL
PROJECT LEADER:	CRB	CLD REF. NO. 05-0387	SHEET 61 OF 69
DESIGNED BY:	CLD		