STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W SHAPE STEEL REMOVAL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
EXIT I RAMP C OFF RAMP I+82 RT	STOP / DO NOT ENTER	I	30	30	6.25						I			X		X 14																		BACK TO BACK		E-143
	ONE WAY / ONE WAY	I	36	12	3.00																													BACK TO BACK		E-142
		I	36	12	3.00																															E-142
EXIT I RAMP B OFF RAMP 8+26 RT		I	36	36	9.00						2			X		X 29																				E-150
EXIT I RAMP B OFF RAMP 9+84 RT	← BRATTLEBORO 2	I	72	12	6.00						2			X		X 31																				E-123
	← HINSDALE N.H. 5	I	72	12	6.00																															E-123
	GUILFORD 1 →	I	72	12	6.00																															E-123
	← SERVICES	I	54	7.5	2.81																															E-133
	← 1 HOSPITAL	I	54	7.5	2.81																															E-133
	← 2 CAMPING	I	54	7.5	2.81																															E-133
		I	24	24	4.00																														MOUNTED ON BACK OF SERVICE SIGNS 675.60 - ERECT. SALV. SIGN (1) EA.		E-143
EXIT I RAMP B OFF RAMP 10+64 RT	WRONG WAY						I				2			X		X 27																		675.60 - ERECT. SALV. SIGN (1) EA.		
EXIT I RAMP B OFF RAMP 10+64 LT	WRONG WAY	I	36	24	6.00						2			X		X 29																				E-143
EXIT I RAMP B OFF RAMP 11+75 LT		I	18	18	2.25						I		X		X 9																				E-150
																																	(2) TOTAL: ERECT. SALV. SIGN		
												FT	FT 15	FT 135	FT 15	FT 135	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 66.18	SF	EA. 1	SF							FT 139 150			FT 150					LB			EA.	LB				EA.	EA.	~~LB~~ EA 15					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: AC IM 091-1(54)

FILE NAME: 05A014ss02.1
PROJECT LEADER: CRB
DESIGNED BY: CLD
CLD REF. NO. 05-0387
PLOT DATE: 22-JAN-2009 13:4
DRAWN BY: MRS
CHECKED BY: NLL
SHEET 66 OF 69