STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	~~W-SHAPE STEEL REMOVAL~~ FTG. SIZE 24"	FTG. SIZE 30"	~~W-SHAPE STEEL REMOVAL~~ WEIGHT	~~W-SHAPE STEEL REMOVAL~~ POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
EXIT 1 RAMP B OFF RAMP 13+01 LT	36" x 36" x 36" DYN. NOT PASS	1	30	30	3.90 6.25						1			X 13′		X													4			BACK TO BACK		E-146 E-143
	ONE WAY ONE WAY	1 1	36 36	12 12	3.00 3.00																											BACK TO BACK		E-142 E-142
EXIT 1 RAMP B OFF RAMP 13+01 RT	36" x 36" x 36" DYN. NOT PASS	1	30	30	3.90 6.25						1			X 14′		X													3			BACK TO BACK		E-146 E-143
	ONE WAY	1	36	12	3.00																													E-142
																													1					
EXIT 1 RAMP D ON RAMP 0+90 LT		1	18	18	2.25						1		X 9′		X														2					E-150
EXIT 1 RAMP D ON RAMP 2+40 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 31′		X																		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00																													E-142
EXIT 1 RAMP D ON RAMP 11+50 RT		1	30	30	6.25						1			X 14′		X													1					E-143
EXIT 2 RAMP C ON RAMP 3+04 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 34′		X													2					E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00																													E-142
EXIT 2 RAMP C ON RAMP 5+40 RT		1	30	30	6.25						1			X 15′		X													1					E-143
EXIT 2 RAMP C/D OFF RAMP 3+04 LT	WRONG WAY	1	36	24	6.00																								1			MOUNT ON BACK OF DESTINATION BOARDS		E-143
EXIT 2 RAMP C/D 0+79 ℄		1	18	18	2.25									-															1					
EXIT 2 RAMP D 2+15 LT		1	18	18	2.25									9′															1			REPLACED DAMAGED SIGN		
												FT	FT ~~9~~ ~~15~~	FT 130 ~~120~~	FT	FT 15	FT 120	FT		EA	LB	LB	LB		LB	LB	LB	LB						
	TOTALS		SF ~~90.55~~ ~~86.05~~	SF	EA.	SF						FT 139 ~~135~~			FT 135					LB	EA.	LB					EA.	EA.	LB 17					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: AC IM 091-1(54)

FILE NAME: 05A014ss03.1
PROJECT LEADER: CRB
DESIGNED BY: CLD
CLD REF. NO. 05-0387
PLOT DATE: 22-JAN-2009 13:4
DRAWN BY: MRS
CHECKED BY: NLL
SHEET 67 OF 69