STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	~~W SHAPE STEEL~~ REMOVALS FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 2 RAMP C/D OFF RAMP 3+78 CL		1	24	30	5.00						1			X 13'		X													2			RETAIN EXISTING SLEEVE		E-144
		1 1	18 18	18 18	2.25 2.25																											BACK TO BACK		E-150 E-150
EXIT 2 RAMP C/D ON RAMP 13+49 CL		1	24	30	5.00						1			X 13'		X													2			RETAIN EXISTING SLEEVE		E-144
		1 1	18 18	18 18	2.25 2.25																											BACK TO BACK		E-150 E-150
EXIT 2 RAMP D OFF RAMP 6+72 LT		1	36	36	9.00						2			X 29'		X													1					E-150
EXIT 2 RAMP D OFF RAMP 9+76 RT	WRONG WAY	1 1	30 36	30 24	6.25 6.00						2			X 32'		X													3			BACK TO BACK		E-151 E-143
EXIT 3 RAMP A ON RAMP 4+75 RT		1	30	30	6.25						1			X 14'		X													1					E-143
EXIT 3 RAMP C OFF RAMP 0+71 LT		1	48	48	16.00						2			~~X~~		X	SEE NB SHEET 33 FOR FOUNDATIONS AND POSTS													1			W2-6		
		1	48	48	16.00																									1					E-150
	TRAFFIC CIRCLE	1	24	15	2.50																									1			W16-12P		
EXIT 3 RAMP C OFF 14+00 RT	SCHOOL FOR INT. TRAINING KEENE N.H. 15 BELLOWS FALLS 20 BRATTLEBORO 2						4							32'			TEMPORARY INSTALL TO ALLOW G.R. PLACEMENT													4			SEE NB SHEET 33 FOR FOUNDATIONS AND 3" POSTS		
	SERVICES 24 HR GAS/DIESEL CAMPING						3																							3					
	JCT 5 JCT 9 BUS ARROW WRONG WAY						7										SEE NB SHEET 33 FOR FOUNDATIONS AND POSTS													7			675.60 ERECT. SALVAGED SIGNS (14) EA (NB)		
	SUMMARY SHEET 1 TOTAL SUMMARY SHEET 2 TOTAL				~~192.25~~ ~~170.00~~ 66.18		1 + 2					470 195 15 9		99 420 135 130	195 15	420 135													33 13					
	SUMMARY SHEET 3 TOTAL SUMMARY SHEET 4 TOTAL				~~90.55~~ ~~86.05~~ 81.00							15		120 135	15	120 135													17 23			675.60 ERECT. SALVAGED SIGNS TOTAL 17 EA		
												FT	FT 225	FT 810	FT 225	FT 810	FT		EA	LB	LB	LB		LB	LB	LB	LB							
PROJECT TOTALS		SF ~~403.23~~ 429.98	SF	EA. ~~2~~ 17	SF							FT ~~1035~~ 980			FT 1035					LB			EA.	LB				EA.	EA.	~~LB~~ EA. 91					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: AC IM 091-1(54)

FILE NAME: 05A014ss04.1
PROJECT LEADER: CRB
DESIGNED BY: CLD
CLD REF. NO. 05-0387
PLOT DATE: 22-JAN-2009 13:4
DRAWN BY: MRS
CHECKED BY: NLL
SHEET 68 OF 69