STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES

					BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						160	160	CY	COMMON EXCAVATION	203.15	4
						100	100	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	7
						900	900	CY	EARTH BORROW	203.30	EST
						34300	34300	LF	SHOULDER BERM REMOVAL	203.99	EST
						1	1	CY	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	EST
						464,500	464,500	SY	COLD PLANING - BIT. PAVEMENT	210.10	306
						211,500	211,500	LF	MILLED RUMBLE STRIPS	213.10	47
						4400	4400	TON	AGGREGATE SHOULDERS (MOD)	402.12	57
						580	580	CWT	EMULSIFIED ASPHALT	404.65	3
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
						39,000	39,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	317
					550		550	LF	BRIDGE EXPANSION JOINT	516.10	54
						8	8	EA	REHABING DI,CB OR MH CLASS I	604.412	EST
						530	530	HR	POWER GRADER RENTAL	608.15	EST
						530	530	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						315	315	HR	POWER BROOM RENTAL	608.30	EST
						315	315	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						525	525	HR	TRUCK RENTAL	608.37	EST
						525	525	HR	LOADER RENTAL, TYPE I	608.40	EST
						40	40	HR	LOADER RENTAL, TYPE II (MOD.)	608.41	EST
						200	200	LF	TREATED TIMBER CURB	616.35	
						620	620	LF	REMOVAL OF EXISTING CURB	616.41	8
						100	100	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	EST
						4000	4000	LF	STEEL BEAM GUARDRAIL	621.20	212.5
						82	82	LF	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21	3
						41	41	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
						1	1	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	-
						6	6	EA	TRAILING END TERMINAL	621.52	-
						1	1	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING BIT. PAVEMENT
235,730	SY	SOUTHBOUND MAINLINE
210,672	SY	NORTHBOUND MAINLINE
8,082	SY	EXIT # 8 RAMPS
8,321	SY	EXIT # 9 RAMPS
1,389	SY	U-TURNS
464,194	SY	SUBTOTAL
306	SY	ROUNDING
464,500	SY	TOTAL
		AGGREGATE SHOULDERS (MOD)
2,068	TON	SOUTHBOUND MAINLINE
1,848	TON	NORTHBOUND MAINLINE
112	TON	EXIT # 8 RAMPS
116	TON	EXIT # 9 RAMPS
180	TON	GUARDRAIL TERMINALS
19	TON	U-TURNS
4,393	TON	SUBTOTAL
57	TON	ROUNDING
4,400	TON	TOTAL
		SUPERPAVE BITUMINOUS
		CONCRETE PAVEMENT (PG 58-34)
19,644	TON	SOUTHBOUND MAINLINE
17,556	TON	NORTHBOUND MAINLINE
674	TON	EXIT # 8 RAMPS
693	TON	EXIT # 9 RAMPS
116	TON	U-TURNS
38,683	TON	SUBTOTAL
317	TON	ROUNDING
39,000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : MONTPELIER - WATERBURY
PROJECT NO. : IM 089-2(34)
DESIGN FILE NAME: /pave/03a026/p03a026.dgn
IPARM FILE NAME: p03a026qsl.i
PLOT DATE: 11-APR-2005 10:17
SURVEYED BY:
SURVEY DATE:
SQUAD LEADER:
DRAWN BY:
SHEET: 5 OF 23