



BRIDGE APPROACH RAILING
WHEN A RAIL PANEL SPLICE OCCURS AT POST NO. 1 USE SCHEDULE I FOR APPROACH RAILING. WHEN A RAIL PANEL SPLICE OCCURS AT THE BRIDGE END POST USE SCHEDULE II FOR APPROACH RAILING.

SCHEDULE II		
POST NO.	SPACING	PAYMENT FACTOR
1	3'- 1 1/2"	1.4 x 18'-9"
2	3'- 1 1/2"	
3	3'- 1 1/2"	
4	3'- 1 1/2"	
5	3'- 1 1/2"	
6	3'- 1 1/2"	1.2 x 12'-6"
7	4'-2"	
8	4'-2"	
9	4'-2"	
10	4'-2"	
11	6'-3" (TYP.)	1.0 (TYP.)

RAMP DETAIL INTERCHANGE #9 OFF RAMP

PROJECT NAME: MONTPELIER - WATERBURY
 PROJECT NUMBER: IM 089-2(34)
 FILE NAME: /pave/03a026/p03a026.dgn
 PROJECT LEADER:
 DESIGNED BY:
 IPARM NAME: p03a02619#b.1
 PLOT DATE: 11-APR-2005 10:18
 DRAWN BY:
 CHECKED BY:
 SHEET 17 OF 23

NOT TO SCALE