STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAMEMENT REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
EXIT 9 RAMP B OFF RAMP(RT)		1	36	36	9						2			IX6' X		X																	INSTALL APPROXIMATELY 504' FROM STOP CONDITION		E-150
EXIT 9 RAMP B OFF RAMP (LT)&(RT)	STOP	2	30	30	12.50						2			2X14' X		X																			E-143
	ONE WAY / ONE WAY	4	36	12	12																														E-142
EXIT 9 RAMP D OFF RAMP(RT)		1	36	36	9						2			IX6' X		X																	INSTALL APPROXIMATELY 850' FROM STOP CONDITION		E-150
EXIT 9 RAMP D OFF RAMP (LT)&(RT)	STOP	2	30	30	12.50						2			2X14' X		X																			E-143
	ONE WAY / ONE WAY	4	36	12	12																														E-142
EXIT 9 RAMPS "B"&"D" (LT) & (RT)	DO NOT ENTER	4	30	30	25.0																														
																																			E-142
STA. 2815+30 NB LT. SB LT.	NB53.318 LT SB53.327 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 2898+72 NB LT. SB LT.	NB54.894 LT SB54.905 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 2959+02 ~~NB~~ LT. SB LT.	SB56.048 RT	~~1~~ 2	36	36	~~9~~ 18						4			2X14' X		X																	NB RETAINED AS PER RESIDENT		E-143
STA. 3048+36 NB LT. SB LT.	NE57.740 LT NB57.748 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 3079+61 NB LT. SB LT.	NB58.331 LT SB58.342 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 3141+60 NB LT. SB LT.	NB59.500 LT SB59.509 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 3238+12 NB LT. SB LT.	NB61.333 LT SB61.346 RT	2	36	36	18						4			4X14' X		X																			E-143
STA. 3308+13 NB LT. SB LT.	NB62.643 LT SB62.653 RT	2	36	36	18						4			4X14' X		X																			E-143
												FT	FT	FT 508 ~~640~~	FT	FT 640	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF ~~227~~ 211	SF	EA.	SF							FT 640			FT 640					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ~~MONTPELIER -- WATERBURY~~
PROJECT NUMBER: IM 089-2(34)

FILE NAME: /pave/03a026/p03a026.dgn
PROJECT LEADER: _____
DESIGNED BY: _____
IPARM FILE NAME: p03a026ssl.i
PLOT DATE: 11-APR-2005 10:19
DRAWN BY: _____
CHECKED BY: _____
SHEET 22 OF 23