STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL	
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (In) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft			TUBULAR STEEL Ø (In)					W-SHAPE STEEL				SIGN FRAMES REQUIRED		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
																						FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE				
												1.12	2.0	3.0	1.75	2.0	2.5			3.0	4.0	4.0 MOD												
															1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
												OPTION ITEMS																							
STATION 15+75, LT ROUTE 2	ONLY — LEFT ONLY, THRU RIGHT	1	36	30	7.5						1			X		X		1															INSTALL NEW SIGN ON NEW POST		
STATION 20+25, RT ROUTE 2	ONE WAY — R6-1R, ONE- WAY RIGHT	1	36	12	3						1				X			1	1														INSTALL NEW SIGN ON NEW POST		STD. E-142
STATION 29+88, LT ROUTE 2	THRU, THRU, THRU-RIGHT	1	48	30	10						2			X		X		2															INSTALL NEW SIGN ON NEW POSTS		STD. E-145B
STATION 29+88, LT ROUTE 2	BIKE LANE — R3-17, BIKE LANE	1	30	24	5.0																												INSTALL NEW SIGN ON NEW POST		STD. E-155
STATION 31+50, LT ROUTE 2	W11-2, PEDESTRIAN CROSSING	1	30	30	6.25						1			X		X		1															INSTALL NEW SIGN ON NEW POST		STD. E-152
STATION 31+50, LT ROUTE 2	W16-7p, ARROW DOWN LT	1	24	12	2																												INSTALL NEW SIGN ON NEW POSTS, (SUB-MOUNT W/ PREVIOUS SIGNS)		STD. E-152
STATION 32+25, LT ROUTE 2	W4-3, ADDED LANE SIGN	1	30	30	6.25						1			X		X		1															INSTALL NEW SIGN ON NEW POST		STD. E-155
STATION 33+00, LT ROUTE 2	W4-3, ADDED LANE SIGN	1	30	30	6.25						1			X		X		1															INSTALL NEW SIGN ON NEW POST		STD. E-155
STATION 35+15, LT ROUTE 2	W11-2, PEDESTRIAN CROSSING	1	30	30	6.25						1			X		X		1															INSTALL NEW SIGN ON NEW POST		STD. E-152
STATION 35+15, LT ROUTE 2	W16-7p, ARROW DOWN LT	1	24	12	2																												INSTALL NEW SIGN ON NEW POSTS, (SUB-MOUNT W/ PREVIOUS SIGNS)		STD. E-152
STATION 41+49, LT RAMP "C"	SPEED LIMIT 35 — R2-1, SPEED LIMIT 35 MPH	1					1				1			X		X		1															RELOCATE EXISTING SIGN ON NEW POST		STD. E-142
STATION 42+68, RT RAMP "C"	NO TURN ON RED — R10-11B NTOR MAST ARM MOUNT	1	24	24	4																												OVERHEAD MOUNT NEW SIGN ON MAST ARM		STD. E-140
STATION 42+96, RT RAMP "C"	R3-1, NO RIGHT TURNS	1	24	24	4																												SUB-MOUNT NEW SIGN WITH PREVIOUS SIGN		STD. E-143
STATION 42+96, RT RAMP "C"	STOP HERE ON RED — R10-6, STOP HERE ON RED	1	24	36	6						1			X		X		1															INSTALL NEW SIGN ON NEW POST		STD. E-140
												FT	FT	FT 94	FT 12	FT 125	FT		EA 1	LB	LB	LB		LB	LB	LB	LB								
TOTALS			SF 68.5	SF	EA. 1	SF						LF 94			LF 137					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SOUTH BURLINGTON
PROJECT NUMBER: IM 089-3(37)

FILE NAME: z03a178tss.dgn
PROJECT LEADER: KEN UPMAL
DESIGNED BY: V. KACOYANNAKIS
PLOT DATE: 5/22/2006
DRAWN BY: V. KACOYANNAKIS
CHECKED BY: J. FORD
SHEET 64 OF 99