

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							EROSION CONTROL	UTILITIES - BID ITEMS	UTILITIES-BID ITEMS (NO FED./STATE)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
								400			400		CY	TRENCH EXCAVATION OF ROCK	204.21	EST			TRENCH EXCAVATION OF ROCK AND CONCRETE
								400			400		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	EST			FOR BACKFILL WHEN UNSUITABLE MATERIAL IS ENCOUNTERED
								1165			1165		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				MELISI ROAD
								310			310		CY	AGGREGATE SURFACE COURSE	401.10				MELISI ROAD
								177	7		184		CY	AGGREGATE SHOULDERS, IN PLACE	402.10	EST			
								3	.13		3.13		CWT	EMULSIFIED ASPHALT	404.65	EST			
								618	26		644		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	EST			
								40			40		LF	48" CAAP .105 (2-2/3 X 1/2)	601.0257				
								5			5		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
									160		160		LF	TEMPORARY TRAFFIC BARRIER	621.90				
								15.6			15.6		MFBM	INSULATION BOARD	622.10				
								1			1		LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42				
								200			200		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
								1000			1000		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10				
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL	641.10				
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								2			2		EACH	PORTABLE ARROW BOARD	641.16				
								21065			21065		LF	DURABLE 4 INCH WHITE LINE	646.400	EST			
								500			500		SF	PAVEMENT MARKING MASK	646.86	EST			
								2715			2715		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				MELISI ROAD
							1873		30		1903		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								1			1		LS	EPSC PLAN	652.10				
								120			120		HR	MONITORING EPSC PLAN	652.20	EST			
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								50			50		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	EST			
								50			50		CY	VEHICLE TRACKING PAD	653.35	EST			
								1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								5			5		EACH	FILTER BAG	653.45	EST			
							13990		290		14280		LF	PROJECT DEMARCATION FENCE	653.55				
								10			10		EACH	EVERGREEN TREES (THUJA OCCIDENTALIS "NIGRA")(6-8 FT, B & B)	656.20				
								51			51		EACH	FLANGED CHANNEL SIGN POST	675.301				
								6			6		EACH	ERECTING SALVAGED SIGNS	675.60				
								1			1		EACH	SPECIAL PROVISION (AIR RELEASE MANHOLE)(6' I.D.)	900.620				
								2			2		EACH	SPECIAL PROVISION (AIR RELEASE MH)(5' I.D.)	900.620				

PROJECT NAME: **HARTFORD REST AREAS**  
PROJECT NUMBER: **IM BLDG (10)**  
FILE NAME: **Hartford\_Quantities\_5-14-2008.xls** PLOT DATE: **06/23/2008**  
PROJECT MANAGER: **JTM** DRAWN BY: **PZA**  
DESIGNED BY: CHECKED BY: **MCF**  
**QUANTITY SHEET #1** SHEET **3** OF **70**