QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	-
						1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
						6	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						63300	63300	LF	DURABLE 6" WHITE LINE	646.414	132
									(MOD. - RETROREFLECTIVITY / INLAID)		
						51300	51300	LF	DURABLE 6" YELLOW LINE	646.415	128
									(MOD. - RETROREFLECTIVITY / INLAID)		
						1170	1170	LF	DURABLE 12" WHITE LINE	646.44	30
									(MOD. - RETROREFLECTIVITY / INLAID)		
						70	70	LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46	13
						41	41	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	-
						127000	127000	LF	TEMPORARY 6" WHITE LINE (PAINT)	646.614	364
						102500	102500	LF	TEMPORARY 6" YELLOW LINE (PAINT)	646.615	153
						2340	2340	LF	TEMPORARY 12" WHITE LINE (PAINT)	646.64	60
						70	70	LF	TEMPORARY 24" STOP BAR (PAINT)	646.66	13
						41	41	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	-
						3900	3900	EA	LINE STRIPING TARGETS	646.76	41
						780	780	SY	GEOTEXTILE UNDER STONE FILL	649.31	14.7
						25	25	LB	SEED	651.15	3.4
						150	150	LB	FERTILIZER	651.18	15
						1	1	TON	AGRICULTURAL LIMESTONE	651.20	.46
						1	1	TON	HAY MULCH	651.25	.46
						150	150	CY	TOPSOIL	651.35	4.0
						850	850	SY	EROSION MATTING	654.10	16.7
						200	200	SF	TRAFFIC SIGNS, TYPE A	675.20	17.5
									BEGIN OPTION ITEMS		
						600	600	LF	FLANGED CHANNEL SIGN POST	675.301	30
						600	600	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	30
									END OPTION ITEMS		
						24	24	EA	REMOVING SIGNS	675.50	-
						180	180	EA	DELINEATORS W/ STEEL POSTS (TYPE I W/ PLAQUE)	676.10	12
						140	140	EA	DELINEATORS W/ STEEL POSTS (TYPE I)	676.10	13
						110	110	EA	DELINEATORS W/ STEEL POSTS (TYPE II)	676.10	11
						30	30	EA	DELINEATORS W/ STEEL POSTS (TYPE III)	676.10	12
						200	200	LF	VEHICLE LOOP DETECTOR	678.22	16
						1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: COLCHESTER - GEORGIA
PROJECT NUMBER: IM 089-3(59)

FILE NAME: p04a030.DGN
PROJECT LEADER: EPD
DESIGNED BY: JDA

PLOT DATE: 12-OCT-2010 16:38
DRAWN BY: RHB
CHECKED BY: EPD