STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
2+65 EXIT 17 RAMP B		1	18	18	2.25						1	X			X			X															OMI-1 NOTE: BORDER & REFLECTORS TYPE 9 SHEETING		E-150
2+38 EXIT 17 RAMP B	← COLCHESTER 4	1	72	12	6																											MOUNT ON EXISTING POSTS		E-123
	CHAMPLAIN ISLANDS →	1	72	12	6																											MOUNT ON EXISTING POSTS		E-123
	NY STATE VIA FEERY OR BRIDGE →	1	72	20	10																											MOUNT ON EXISTING POSTS		E-123
	← SERVICES	1	54	7.5	2.8																											MOUNT ON EXISTING POSTS		E-133
	←4 CAMPING 6→	1	54	7.5	2.8																											MOUNT ON EXISTING POSTS		E-133
2+30 LT EXIT 18 RAMP C		1	18	18	2.25																											OMI-1 NOTE: BORDER & REFLECTORS ARE TYPE 9 SHEETING MOUNT ON EXISTING POSTS		E-150
5+86 RT EXIT 18 RAMP C	SOUTH	1	24	12	2																											9 SIGNS WITH # 3B FRAME MOUNT ON EXISTING POSTS	E-123	E-136A
	7	1	24	24	4																														
	←	1	21	15	2.2																											9 SIGNS WITH # 3B FRAME MOUNT ON EXISTING POSTS	E-123	E-136B
	TO	1	24	12	2																														
5+86 RT EXIT 18 RAMP C	VERMONT 104 A	1	30	24	5																														
	←	1	21	15	2.2																														
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT					LB			EA.	LB				EA.	EA.	LB					
	TOTALS		SF 49.5		SF		EA.	SF																											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: COLCHESTER - GEORGIA
PROJECT NUMBER: IM 089-3(59)

FILE NAME: p04a030.DGN
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE:

PLOT DATE: 12-OCT-2010 16:39
DRAWN BY: RHB/SJB
CHECKED BY: EPD
SHEET 12a OF 22