STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	NEW SIGN POSTS TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) 675.43 FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REMOVED RETURNED TO SIGN	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																										
EXIT R RAMP "A" OFF RAMP RT		1	36	36	9						2	12-6 13-0		X		X																				I REMOVAL		E-150
EXIT II RAMP "D" OFF RAMP RT 9 LT	ONLY WRONG WAY	1 ~~2~~ 2	36 36	30 24	7.5 ~~6~~ 12				RT LT	2 ~~2~~ 2	13-6 14-0 12-0 12-0		X		X																		WRONG WAY DOUBLE POSTED RT & LT SIDE 3NN05 I REMOVAL		E-145A
EXIT II RAMP "D" OFF RAMP LT & RT	STOP DO NOT ENTER	4	30	30	25				RT LT	1 ~~1~~ 1	12-0 12-0		X		X																		3NN05 2 REMOVE RT 2 REMOVE RT		E-143
	ONE WAY ONE WAY	4	36	12	12																													2 REMOVE RT 2 REMOVE RT		E-142
EXIT 13 RAMP "A" ON RAMP RT		1	48	48	16						2	16-0 16-0		X		X																		INSTALLED REMOVE NEW SIGN I REMOVAL I REMOVAL		E-150
EXIT 13 RAMP "A" ON RAMP RT	YIELD	1	48	48	16						2	16-0 14-6		X		X																		INSTALLED REMOVE NEW SIGN I REMOVAL I REMOVAL		E-146
EXIT 13 RAMP "A" ON RAMP RT	SPEED LIMIT 65	1	48	60	20																													I REMOVAL		
	MINIMUM 40	1	36	48	12						2												2	X	17' 17-6	129.2 133								I REMOVAL		
EXIT 13 RAMP "A" ON RAMP RT			48	48	16																													I REMOVAL	29	
	GROOVED SHOULDER		24	18	3						2												2	X	13-3 12-6	100.7 95								I REMOVAL		E-153B
EXIT 13 RAMP "A" ON RAMP RT	SOUTH		30	15	3.125																													I REMOVAL		
	89	1	36	36	9						1									X	16-6'	21.45#												I REMOVAL		
EXIT II OFF RAMP D	13+47 RT																																	I REMOVAL		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

	SHEET 2 TOTAL	160.625						FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB											
													~~210~~			~~20.8~~				~~402.8~~	457.9													
	TOTALS	SF 121.125	SF	EA.	SF			163.5 FT 210					~~210~~ FT ~~210~~			21.45 LB ~~20.8~~			4 EA. 4		LB ~~402.8~~				EA.	EA.	LB								

21 REMOVE

PROJECT NAME: BOLTON - SO. BURLINGTON
PROJECT NUMBER: AC IM 089-2(36)

FILE NAME: /pave/04all4/p04all4.dgn
PROJECT LEADER:
DESIGNED BY:
IPARM FILE NAME: p04all4ssl.I

PLOT DATE: 17-MAY-2005
DRAWN BY:
CHECKED BY:
SHEET 38 OF 76