QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	TRAFFIC CONTROL	EROSION CONTROL	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
1			1	LS	CLEARING AND GRUBBING (INCL. INDV. TREES & STUMPS)	201.10	-
1600			1800	CY	COMMON EXCAVATION	203.15	147
1000			1000	CY	EARTH BORROW	203.30	87
400			400	CY	SAND BORROW	203.31	16
4500			4500	SY	FINE GRADING - SUBGRADE	203.40	-
3100			3100	SY	COLD PLANING - BIT. PAVEMENT	210.10	30
1200			1200	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	136
250			250	TON	AGGREGATE SHOULDERS (MOD.)	402.12	17
1			1	CWT	EMULSIFIED ASPHALT	404.65	-
1300			1300	TON	SUPERPAVE BITUMINOUS CONTRETE PAVEMENT (PG 64-28)	490.30	141
		25	25	CY	STONE FILL, TYPE I	613.10	3.7
		50	50	CY	STONE FILL, TYPE II	613.11	5.8
		2400	2400	LF	SNOW FENCE (MOD. - PDF)	620.70	42
450			450	LF	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	21
2			2	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	0
1			1	EA	TRAILING END TERMINAL	621.52	0
	1		1	EA	ENERGY ABSORPTION ATTENUATOR (SAND FILLED PLASTIC BARREL)	621.56	0
54			54	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	0
700			700	LF	TEMPORARY TRAFFIC BARRIER	621.90	
3000			3000	LF	DURABLE 6" WHITE LINE (MOD.-RETROREFLECTIVITY/INLAID)	646.414	131
640			640	LF	DURABLE 6" YELLOW LINE (MOD.-RETROREFLECTIVITY/INLAID)	646.415	54
1300			1300	LF	DURABLE 12" WHITE LINE (MOD.-RETROREFLECTIVITY/INLAID)	646.44	80
80			80	LF	DURABLE 24" STOP BAR	646.46	9
40			40	EA	DURABLE LETTER OR SYMBOL	646.50	4
	130		130	LF	TEMPORARY 6" WHITE LINE (TAPE, TYPE II)	646.614	13
	3000		3000	LF	TEMPORARY 6" WHITE LINE (PAINT)	646.614	131
	640		640	LF	TEMPORARY 6" YELLOW LINE (PAINT)	646.615	54
	730		730	LF	TEMPORARY 12" WHITE LINE (TAPE, TYPE II)	646.64	13
	1300		1300	LF	TEMPORARY 12" WHITE LINE (PAINT)	646.64	80
	50		50	LF	TEMPORARY 24" STOP BAR (PAINT)	646.66	2

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		REVISED 06-10-05 LSW

PROJECT NAME: I-89 EXIT 12 SB OFF RAMP
PROJECT NUMBER: IM 089-2(35)

FILE NAME: 618800F40S.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
QUANTITY SHEET

PLOT DATE: 14-JUN-2005
DRAWN BY: JDA / PGJ
CHECKED BY: EPD
SHEET 48 OF 76